



**CEMENTER'S WELL SERVICE, INC.**  
P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

**201168**

Date <b>2-3-13</b>	Well Owner <b>GREAT WESTERN</b>	Well No. <b>JG31-17D</b>	Lease <b>LAND</b>
County <b>WELD</b>	State <b>COLORADO</b>	Field	
Charge to <b>CADE DRILLING, LLC</b>	Charge Code		For Office Use Only
Address <b>3450 WCR 27 UNIT #2 (CADE-25)</b>			
City, State <b>FT WYNTON, COLORADO 80621</b>			
Pump Truck No. <b>1202</b>	Code	Bulk Truck No. <b>1218/1224</b>	Code
Type of Job	Depth	Ft. <b>1036</b>	To
<b>Surface</b> <b>8 5/8" CSG-24 #</b>	Bottom of Surface	Ft. <b>1026</b>	To
Plug	Plug Landed @ <b>984</b>	Ft. Time On <b>1130</b>	
Production	Pipe Landed @ <b>1026</b>	Ft. Time Off <b>PLUG DOWN 1345</b>	

Reference No.	Description	Qty.	Meas.	Unit Price	Amount		
	Pump Truck Charge						
	Cement Neat ✓	670	SKS				
	Poz. Mix						
	Calcium Chloride	3%					
	Gel        %    Flo-Cele $\frac{1}{4}$ #Per Sack						
	Handling Charge						
	Hauling Charge						
	Additional Cement						
8 5/8"	CENTRALIZERS	3					
"	CEMENT BASKET	1					
"	GUIDE SHOE	1					
"	BAFFLE PLATE	1					
	BOX THREADLOCK	1					
	MIX RATE 4 BPM	SLURRY	VOL	1.18 FT <sup>3</sup> /SK - WATER	TEMP 50		
	DISP. RATE 5 BPM	SLURRY	WT	15.2 PPG			
	PLUG LANDED @ 900 PSI	TOTAL	SLURRY VOL	140.8 BBL	CEMENT		
Remarks: PREFLUSH W/ 30 BBL H2O		Tax Reference Code		Sub Total			
DISPLACE W/ 62.5 BBL H2O		State CO 2.9 %		Tax			
CIRCULATE 5 BBL CEMENT		Disc.		Total			
Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
1202		Pump Truck		54			
1218/1224		Bulk Truck		54/54			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By **JOE, JOSH, ERNIE, TUCKER**

Received By

Customer or His Agent