




00224187

OIL AND GAS CONSERVATION COMMISSION  
OF THE STATE OF COLORADO



SUNDRY NOTICES AND REPORTS ON WELLS

INSTRUCTIONS

Notice must be given to the Director, and approval obtained in advance of the time when the owner or operator expects to recomplete or abandon a well or to change plans. Within thirty (30) days after recompletion, change of plans, or remedial work, a detailed report of the work done and the results obtained shall be submitted on this form in duplicate for wells on Patented and Federal lands, and in triplicate for wells on State lands. In work that affects only rods, pumps or tubing or other routine work such as, but not limited to, cleaning out to previous total depth, no report is necessary.

Notice of Intention to Recomplete	<input type="checkbox"/>	Report of Remedial Work	<input type="checkbox"/>
Notice of Intention to Change Plans	<input type="checkbox"/>	Report of Recompletion	<input type="checkbox"/>
Notice of Intention to Abandon Well	<input type="checkbox"/>	Other - Salvage Casing	<input checked="" type="checkbox"/>

(Check appropriate space)

LEASE NAME State of Colorado "A" WELL NO. 1

FIELD Curtis WILDCAT - COUNTY Routt

LOCATION SW NW Section 30 Township 6N Range 85W Meridian 6th  
(Quarter Quarter)

2025 feet from N Section Line and 655 feet from W Section Line  
N or S E or W

(DETAILS OF WORK)

A previous request was approved for permission to abandon this well with the Production casing in the hole. Due to the need for the casing and other considerations; We are now asking for a revocation of that request in favor of a permanent abandonment.

Plugging Procedure as follows:

- Plug at 3850' w/10 sxs cement in 7" casing.
- Cut 7" casing at approximately 3150'
- Pull 7" casing.
- Plug 988' w/ 40 sxs cement in surface casing.
- Dump 5 sxs. cement in top of surface casing & erect dry hole marker.

Well data:

- TD 5826'
- PBTD 4451'
- 7" casing set at 3850'
- 13-3/8" casing set at 988'
- Top of cement at 3250'(Temperature survey)
- Top of Niobrara at 3450'

AD	
DIR	
SEC	
ASST	
CLERK	
FILE	
INDEX	
MAIL	
RECORDS	
TRAINING	
WORK	

Area	
Bond	
Spot	
600 ft.	
1200 ft.	
Wells	
Oil	
Gas	
Status	

I/We hereby swear (or affirm) that the statements herein made are a full and correct report.

APPROVED:

Date  
Director

DEC - 1 1958

*A. J. Germain*

Company Tennessee Gas Transmission Co. Date 11-29-58

Address Box 1772, Casper, Wyoming Phone No. 2-3501

By *P. L. Patterson* Title Superintendent  
(Signature) Patterson Lay