



00285447

Budget Bureau No. 42-R358.4  
Approval expires 12-31-60.

(SUBMIT IN TRIPLICATE)

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
GEOLOGICAL SURVEYLand Office DenverLease No. C-021690

Unit \_\_\_\_\_

## SUNDRY NOTICES AND REPORTS ON WELLS

NOTICE OF INTENTION TO DRILL	SUBSEQUENT REPORT OF WATER SHUT-OFF	
NOTICE OF INTENTION TO CHANGE PLANS	SUBSEQUENT REPORT OF SHOOTING OR ACIDIZING	
NOTICE OF INTENTION TO TEST WATER SHUT-OFF	SUBSEQUENT REPORT OF ALTERING CASING	
NOTICE OF INTENTION TO RE-DRILL OR REPAIR WELL	SUBSEQUENT REPORT OF RE-DRILLING OR REPAIR	
NOTICE OF INTENTION TO SHOOT OR ACIDIZE	SUBSEQUENT REPORT OF ABANDONMENT	<input checked="" type="checkbox"/>
NOTICE OF INTENTION TO PULL OR ALTER CASING	SUPPLEMENTARY WELL HISTORY	
NOTICE OF INTENTION TO ABANDON WELL		

(INDICATE ABOVE BY CHECK MARK NATURE OF REPORT, NOTICE, OR OTHER DATA)

October 10, 1958

Well No. 2 is located 660 ft. from N line and 1880 ft. from W line of sec. 8C. SE 1/4 SW 1/4 Section 8 9 North 78 West 6th P.M.  
(1/4 Sec. and Sec. No.) (Twp.) (Range) (Meridian)South McCallum Jackson Colorado  
(Field) (County or Subdivision) (State or Territory)The elevation of the derrick floor above sea level is \* ft. \*Will furnish later.

## DETAILS OF WORK

(State names of and expected depths to objective sands; show sizes, weights, and lengths of proposed casings; indicate mudding jobs, cementing points, and all other important proposed work)

Gulf Designation: Ballinger-Federal No. 2

Well No. 2 was drilled to a total depth of 2072'. The 8-5/8" OD surface casing was cemented at 324' with 175 sacks, did not circulate, re-cemented from surface with 50 sacks, circulated. Casing parted at 104' and 166'. Top 3 joints and bottom 5 joints O.K. Unable to wash over or fish loose joints. Recovered top 3 joints. Cemented top 100' of hole with 150 sacks cement. Will skid rig 12' and drill new hole #2a. No well logs were run.

I understand that this plan of work must receive approval in writing by the Geological Survey before operations may be commenced.

Company Gulf Oil CorporationAddress P. O. Box 1010CasperWyomingcc: Colorado Oil & Gas Conservation Comm. (2)

By

ORIGINAL SIGNED BY  
H. L. STRIDERTitle Area Production Foreman

GPO 9 18 507