

OIL AND GAS CONSERVATION COMMISSION
OF THE STATE OF COLORADO

RECEIVED
NOV 20 1961



PLUGGING RECORD

OIL & GAS
CONSERVATION COMMISSION

INSTRUCTIONS

Within thirty (30) days after the plugging of any well, the owner or operator thereof shall file this form in duplicate for wells on Patented or Federal lands, and in triplicate for wells on State lands, give a detailed account of the manner in which the abandonment or plugging work was carried out, including the nature and quantities of materials used in plugging and the location and extent (by depths) of the plugs of different materials; records of the amount, size and location (by depths) of casings and junk left in the well; and a detailed statement of the volume and weight of mud fluid used.

Operator Continental Oil Company Field McCallum Wildcat No
Lease Name McCallum Unit Well No. 21 County Jackson
Location NE SW Section 7 Township 9N Range 78W Meridian 6th PM
(Quarter Quarter)
1600 feet from S Section line and 2540 feet from W Section Line
N or S E or W

TOTAL DEPTH 6000' DATE OF PLUGGING 11-1-61

DETAILS OF WORK

This well was plugged and abandoned on 11-1-61 as follows:

- Set 1 sack regular cement plug from 5800' to 5790' GL.
- Set 10 sack regular cement plug from 5549' to 5499' GL.
- Casing cut at 5524' GL.
- Set 15 sack regular cement plug from 944' to 894' GL.
- Surface casing set at 919' GL.
- Set 6 sack regular cement plug from 25' to surface with proper dry hole marker.
- Left 9# mud between plugs.
- Left 919' of 7 5/8" OD 24# H-40 casing and 465' of 4 1/2" OD 11.60# J-55 casing in hole.

AJJ	
DVR	
WRS	
HHM	
JAM	
FJP	✓
JJD	✓
FILE	

I/we hereby swear (or affirm) that the statements herein made are a full and correct report:

Approved: _____ Date NOV 20 1961
Company Continental Oil Company Date 11-16-61
Address Box 126, Craig, Colorado Phone No. TA4-6571
Director [Signature] By _____ Title Dist. Supt.
(Signature)
COGCC(2) - [Signature] - File