



OIL AND GAS CONSERVATION COMMISSION  
OF THE STATE OF COLORADO

RECEIVED  
OCT 20 1961  
OIL & GAS  
CONSERVATION COMMISSION

SUNDRY NOTICES AND REPORTS ON WELLS

INSTRUCTIONS

Notice must be given to the Director, and approval obtained in advance of the time when the owner or operator expects to recomplete or abandon a well or to change plans. Within thirty (30) days after recompletion, change of plans, or remedial work, a detailed report of the work done and the results obtained shall be submitted on this form in duplicate for wells on Patented and Federal lands, and in triplicate for wells on State lands. In work that affects only rods, pumps or tubing or other routine work such as, but not limited to, cleaning out to previous total depth, no report is necessary.

Notice of Intention to Recomplete	<input type="checkbox"/>	Report of Remedial Work	<input type="checkbox"/>
Notice of Intention to Change Plans	<input type="checkbox"/>	Report of Recompletion	<input type="checkbox"/>
✓ Notice of Intention to Abandon Well	<input checked="" type="checkbox"/>	Other	<input type="checkbox"/>

(Check appropriate space)

LEASE NAME McCallum Unit WELL NO. 21

FIELD McCallum Unit WILDCAT                      COUNTY Jackson

LOCATION NE SW Section 7 Township 9N Range 78W Meridian 6th PM  
(Quarter Quarter)

1600 feet from S Section Line and 2540 feet from W Section Line  
N or S E or W

(DETAILS OF WORK)

It is our intention to abandon this well as it has proven to be non-commercial.

We propose to set 10' bottom plug in 4 1/2" OD casing above Muddy perforation at approx. 5800'. Cut off 4 1/2" OD casing at approx. 5500'. Set 50' cement plug at 5500' or where 4 1/2" OD casing is cut. Set 50' cement plug at 930' base of surface pipe. Set 25' cement plug in surface pipe at surface with steel marker. Fill annulus between all plugs with 9# mud.

AJJ	
DVR	
WRS	
HHM	
JAM	
FJP	
JJD	✓
FILE	

I/We hereby swear (or affirm) that the statements herein made are a full and correct report.

APPROVED: OCT 20 1961

Date                      Company Continental Oil Company Date 10-18-61

Director *T. J. Jernin* Address Box 126, Craig, Colorado Phone No. TA 4-6571

By *H. E. White* Title Dist. Supt.  
(Signature)

COGCC(2), File