




OIL AND GAS CONSERVATION COMMISSION
OF THE STATE OF COLORADO



SUNDRY NOTICES AND REPORTS ON WELLS

OIL & GAS
CONSERVATION COMMISSION

INSTRUCTIONS

Notice must be given to the Director, and approval obtained in advance of the time when the owner or operator expects to recomplate or abandon a well or to change plans. Within thirty (30) days after recompletion, change of plans, or remedial work, a detailed report of the work done and the results obtained shall be submitted on this form in duplicate for wells on Patented and Federal lands, and in triplicate for wells on State lands. In work that affects only rods, pumps or tubing or other routine work such as, but not limited to, cleaning out to previous total depth, no report is necessary.

Notice of Intention to Recomplate	<input type="checkbox"/>	Report of Remedial Work	<input type="checkbox"/>
Notice of Intention to Change Plans	<input type="checkbox"/>	Report of Recompletion	<input type="checkbox"/>
Notice of Intention to Abandon Well	<input type="checkbox"/>	Other	<input checked="" type="checkbox"/>

(Check appropriate space)

LEASE NAME McCallum Unit WELL NO. 21
 FIELD McCallum Unit WILDCAT COUNTY Jackson
 LOCATION NE SW Section 7 Township 9N Range 78W Meridian 6th PM
 (Quarter Quarter)
1600 feet from S Section Line and 2540 feet from W Section Line
 N or S E or W

(DETAILS OF WORK)

Drilled sand & shale to 6000' TD. Ran 190 Jts. 4 1/2" casing set @ 6000' RBM. Cemented w/100 sks. regular cement. PBD 5955'. Ran G-N logs TD - surface, and cement log. Cement top 5523'. Perforated Dakota 5906' - 5914' (8') 32 holes, 4 jets per foot. Perforated Dakota 5886' - 5890' w/4 jets/foot. Ran 187 joints 2" tubing. Acidized perforations. Swab tested 9 bbls. water per hour, no oil, trace CO2. PBD 5857'. Cemented w/100 sks. cement thru perforations 5886' - 5890'. Made cut @ 5837' w/Abrasijet tool, sand fraced (Muddy formation). No oil. Abandoned as dry hole, but not plugged.

AJ	
DVR	
WRS	
HHM	
JAM	
FJP	
JJD	<input checked="" type="checkbox"/>
FILE	

I/We hereby swear (or affirm) that the statements herein made are a full and correct report.

APPROVED:

Company Continental Oil Date 12-15-60

DEC 21 1960

Address Box 126, Craig, Colo. Phone No. TA 4-6571

Date _____
 Director *A. J. Jordan*

By *Janner* Title Dist. Supt.
 (Signature)