



North Wellington #21-1

Nielson & Associates, Inc.
714' FSL & 1894' FEL Sec 21-T11N-R68W
API # 05-069-06330-00
Larimer County, Colorado
Current Wellbore Configuration

RECEIVED

NOV - 1 01

GOGCC

5782' KB
5772' GL

TOC @ surface

8-5/8" 24# J-55 Set at 625' KB in 11" hole
Cemented with 440 sks

1000 ft

2000 ft

3000 ft

4000 ft

5000 ft

6000 ft

7000 ft

TOC @ 6150' KB

Perf's 7539' - 7560'

5-1/2", 15.5 & 17#, J-55 set at 7639' KB
Cemented with 225 sacks

PBTD @ 7609' KB

TD @ 7650' KB

Prepared By T.R. Ziehl