


OIL AND GAS CONSERVATION COMMISSION
OF THE STATE OF COLORADOOIL & GAS
CONSERVATION COMMISSION

00819127

PLUGGING RECORD

INSTRUCTIONS

Within thirty (30) days after the plugging of any well, the owner or operator thereof shall file this form in duplicate for wells on Patented or Federal lands, and in triplicate for wells on State lands, give a detailed account of the manner in which the abandonment or plugging work was carried out, including the nature and quantities of materials used in plugging and the location and extent (by depths) of the plugs of different materials; records of the amount, size and location (by depths) of casings and junk left in the well; and a detailed statement of the volume and weight of mud fluid used.

Operator United States Smelting Refining & Mining Co. Field Unnamed WildcatLease Name Henderson Well No. 1-19 County LoganLocation SE/4 SW/4 Section 19 Township 9N Range 55W Meridian 6 P.M.
(Quarter Quarter)661 feet from S Section line and 1933 feet from W Section Line
N or S E or WTOTAL DEPTH 5727 DATE OF PLUGGING April 30, 1958

DETAILS OF WORK

Spudded well April 21, 1958. Drilled 12 1/4" hole to 210', set 9 jts. 195' of 8 5/8" 24# at 203' K.B. w/175 sxs. reg. 2% cacl. Drilled to 5640' Cored 5640-90' Recovered 50'. Drilled to T.D. 5727'. No tests were taken.

Plugged and abandoned on April 30, 1958 as follows:

Plug #1	5650-5488'	50 sxs. reg. cmt.
#2	210-88'	40 sxs. reg. cmt.
#3	10 sxs. cmt. top of 8 5/8" surface csg.	

Hole intervals filled with heavy mud.

AJJ	
DVR	
WRS	<input checked="" type="checkbox"/>
HHM	
JAM	
FJP	<input checked="" type="checkbox"/>
JJD	<input checked="" type="checkbox"/>
FILE	

I/we hereby swear (or affirm) that the statements herein made are a full and correct report:

Approved:

Company United States Smelting Refining and Mining Co. Date 4-30-58Date MAY - 6 1958Address 900 Patterson Building Phone No. KE 4-5304

Director

By [Signature] Title Manager - Denver Oil Operations
(Signature)