



1 Mile Offset:

No PR Sussex

Deepest WW: 200'

No fox hills aquifer data

Upper Pierre Base @ 1115'

Pump 10 sx at top of surface casing

calc 26' coverage

Pump 10 sx at bottom of surface csg

Pump 40 sx @ 2310'

Cut & pull casing @ 6061'

5-1/2" CIBP set @ 6200'
9/15/1987

WELLBORE DIAGRAM
CURRENT WBD

1980 FSL 1980 FWL

Wellbore currently exposed

MD = 7900'

PBMD =

Operator:	Walter Properties
Well Name:	Thayer 2-30
Lease Number:	
Location:	NESW 30 6N 67W
Field:	Mako - #52420
County, State:	Weld CO
API Number:	05-123-12031
Diagram Date:	7/27/2020
Lat/Long	40.455913/-104.936947

KB

GL 4955'

Spud Date: 10/28/1984

Surface Casing : 13-1/4" hole

9-5/8" 24# set @ 533'

Cmt w/ 300 sx Class G w/ 3% CaCl₂

Production Casing : 7-7/8" hole

5-1/2" 20# set @ 7900'

Cmt w/ 390 sx Class G w/ 10% salt

Tubing Detail:

Formation Tops:

Pierre	2355'
Parkman	3550'
Sussex	4252'
Shannon	4638'
Niobrara	6961'
Fort Hays	7272'
Codell	7290'
J Sand	7765'

Perforations

J Sand: