

Document Number:  
402509887

Date Received:  
10/13/2020

**WELL ABANDONMENT REPORT**

This form is to be submitted as an Intent to Abandon whenever an abandonment is planned on a borehole. After the abandonment is complete, this form shall again be submitted as a Subsequent Report of the actual work completed. The approved intent shall be valid for six months after the approval date, after that period, a new intent will be required. Attachments required with the Intent to Abandon are wellbore diagrams of the current configuration and the proposed configuration with plugs set. A Subsequent Report of Abandonment shall indicate the actual work completed. Attachments required with a Subsequent Report are a wellbore diagram showing plugs that were set and casing remaining in the hole, the job summaries from all plugging contractors used, including wireline and cementing (third party verification) and any logs that may have been run during abandonment.

OGCC Operator Number: 12950 Contact Name: Shannon Chollett  
 Name of Operator: CALIFORNIA OIL GROUP, LTD Phone: (303) 894-2100 x5102  
 Address: \_\_\_\_\_ Fax: \_\_\_\_\_  
 City: DENVER State: CO Zip: \_\_\_\_\_ Email: shannon.chollett@state.co.us

**For "Intent" 24 hour notice required,** Name: Moran, Rick Tel: (720) 827-6689  
 Email: rick.moran@state.co.us  
**COGCC contact:** \_\_\_\_\_

Type of Well Abandonment Report:  Notice of Intent to Abandon  Subsequent Report of Abandonment

API Number 05-103-05254-00  
 Well Name: A C MCLAUGHLIN JR (OWP) Well Number: 33  
 Location: QtrQtr: NWNE Section: 33 Township: 2N Range: 102W Meridian: 6  
 County: RIO BLANCO Federal, Indian or State Lease Number: \_\_\_\_\_  
 Field Name: RANGELY Field Number: 72370

*Only Complete the Following Background Information for Intent to Abandon*

Latitude: 40.105577 Longitude: -108.844224  
 GPS Data: GPS Quality Value: 0.6 Type of GPS Quality Value: Accuracy in Meters Date of Measurement: 10/03/2020  
 GPS Instrument Operator's Name: Shannon Chollett  
 Reason for Abandonment:  Dry  Production Sub-economic  Mechanical Problems  
 Other OWP PA  
 Casing to be pulled:  Yes  No Estimated Depth: \_\_\_\_\_  
 Fish in Hole:  Yes  No If yes, explain details below  
 Wellbore has Uncemented Casing leaks:  Yes  No If yes, explain details below  
 Details: \_\_\_\_\_

**Current and Previously Abandoned Zones**

Formation	Perf. Top	Perf. Btm	Abandoned Date	Method of Isolation	Plug Depth
MANCOS	2590	2642	04/01/1999		
Total: 1 zone(s)					

**Casing History**

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bot	Cement Top	Status
SURF	8+1/2	7+0/0	23	37	5	37	0	VISU
OPEN HOLE	8+1/2			2,642				

## Plugging Procedure for Intent and Subsequent Report

CIBP #1: Depth \_\_\_\_\_ with \_\_\_\_\_ sacks cmt on top. CIBP #2: Depth \_\_\_\_\_ with \_\_\_\_\_ sacks cmt on top.  
CIBP #3: Depth \_\_\_\_\_ with \_\_\_\_\_ sacks cmt on top. CIBP #4: Depth \_\_\_\_\_ with \_\_\_\_\_ sacks cmt on top.  
CIBP #5: Depth \_\_\_\_\_ with \_\_\_\_\_ sacks cmt on top.

NOTE: Two(2) sacks cement required on all CIBPs.

Set 100 sks cmt from 2642 ft. to 2342 ft. Plug Type: OPEN HOLE Plug Tagged:   
Set 20 sks cmt from 87 ft. to 0 ft. Plug Type: CASING Plug Tagged:   
Set \_\_\_\_\_ sks cmt from \_\_\_\_\_ ft. to \_\_\_\_\_ ft. Plug Type: \_\_\_\_\_ Plug Tagged:   
Set \_\_\_\_\_ sks cmt from \_\_\_\_\_ ft. to \_\_\_\_\_ ft. Plug Type: \_\_\_\_\_ Plug Tagged:   
Set \_\_\_\_\_ sks cmt from \_\_\_\_\_ ft. to \_\_\_\_\_ ft. Plug Type: \_\_\_\_\_ Plug Tagged:   
Perforate and squeeze at \_\_\_\_\_ ft. with \_\_\_\_\_ sacks. Leave at least 100 ft. in casing \_\_\_\_\_ CICR Depth  
Perforate and squeeze at \_\_\_\_\_ ft. with \_\_\_\_\_ sacks. Leave at least 100 ft. in casing \_\_\_\_\_ CICR Depth  
Perforate and squeeze at \_\_\_\_\_ ft. with \_\_\_\_\_ sacks. Leave at least 100 ft. in casing \_\_\_\_\_ CICR Depth  
(Cast Iron Cement Retainer Depth)  
Set \_\_\_\_\_ sacks half in. half out surface casing from \_\_\_\_\_ ft. to \_\_\_\_\_ ft. Plug Tagged:   
Set \_\_\_\_\_ sacks at surface  
Cut four feet below ground level, weld on plate Above Ground Dry-Hole Marker:  Yes  No  
Set \_\_\_\_\_ sacks in rat hole Set \_\_\_\_\_ sacks in mouse hole

### Additional Plugging Information for Subsequent Report Only

Casing Recovered: \_\_\_\_\_ ft. \_\_\_\_\_ inch casing Cut and Cap Date: \_\_\_\_\_  
of \_\_\_\_\_  
\*Wireline Contractor: \_\_\_\_\_ \*Cementing Contractor: \_\_\_\_\_  
Type of Cement and Additives Used: \_\_\_\_\_  
Flowline/Pipeline has been abandoned per Rule 1105  Yes  No

Technical Detail/Comments:

This well is part of a larger OWP PA Project.

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: Shannon Chollett  
Title: OWP Engineer Date: 10/13/2020 Email: shannon.chollett@state.co.us

Based on the information provided herein, this Well Abandonment Report (Form 6) complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: Katz, Aaron Date: 10/15/2020

**CONDITIONS OF APPROVAL, IF ANY:** \_\_\_\_\_

Expiration Date: 4/14/2021

<b>COA Type</b>	<b>Description</b>
	<p>1)Provide 48 hour notice of plugging MIRU via electronic Form 42.</p> <p>2)The approved Form 6, Notice of Intent will be at the location during all phases of plugging operations.</p> <p>3)Operator shall implement measures to control venting and to ensure that vapors and odors from well plugging operations do not constitute a nuisance or hazard.</p> <p>4)Properly abandon flowlines as per Rule 1105. File electronic Form 42 once on location abandonment complete. Within 30 days of an operator completing abandonment requirements for an off-location flowline or crude oil transfer line the operator shall submit a Flowline Report, Form 44.</p> <p>5)In accordance with the Notice to Operators (NTO): Timing for COGCC Forms adopted on 05/01/2020, this Form 6 Notice of Intent to Abandon is valid for 12 months from the date of approval expiring on 10/15/2021. This NTO does not alter the deadlines for submission of, or compliance with any other Commission rule or Form.</p> <p>6)Check bradenhead annulus pressure prior to MIRU. Perform a bradenhead test if bradenhead pressure is greater than 25 psi, submit results electronically on a Form 17, and contact COGCC area engineer.</p> <p>If a well has a bradenhead pressure greater than 25 PSI measured at the time of the test then a sample of both the production and bradenhead gas (if sufficient volume to analyze) shall be collected and submitted for laboratory analysis of the gas composition and stable isotopes. The compositional analysis should include hydrogen, argon, oxygen, carbon dioxide, nitrogen, methane (C1), ethane (C2), ethene, propane (nC3), isobutane (iC4), butane (nC4), isopentane (iC5), pentane (nC5), hexanes +, specific gravity and British Thermal Units (BTU).The stable isotope analysis should include delta DC1, delta 13C1, delta 13C2, delta 13C3, delta 13iC4, delta 13nC4, delta 13iC5 (if possible), delta 13nC5 (if possible), and delta 13C of CO2 (if possible). The analytical results shall be submitted to the COGCC via Form 43 (Analytical Sample Submittal Form).</p> <p>Gas sample containers should be filled in accordance with container manufacturer or laboratory recommendations; purging multiple container volumes may not be feasible due to limited gas volumes.</p> <p>If water is encountered in the bradenhead during testing then samples (if sufficient quantity to analyze) should be collected and submitted for the laboratory analysis of major anions (chloride, carbonate, bicarbonate, and sulfate), cations (sodium, potassium, calcium, and magnesium) total dissolved solids (TDS), BTEX, DRO, GRO, and dissolved gasses (RSK 175). If there is a limited amount of water available then anions, cations and BTEX should be given first priority. Data from bradenhead water samples shall be submitted to the COGCC via Form 43.</p> <p>Please refer to Appendix A of the COGCC Operator Instructions for Bradenhead Testing and Reporting for more information regarding testing and sampling protocol. The operator shall provide notice to Environmental Supervisor Alex Fischer at alex.fischer@state.co.us or 303-894-2100 X 5138 and COGCC Engineer Craig Burger at craig.burger@state.co.us or 970-319-4194, a minimum of 72 hours prior to conducting field operations. Bradenhead testing and sample collection (if applicable). If samples are collected, copies of all final laboratory analytical results shall be provided to the COGCC within three (3) months of collecting the samples.</p>

**Attachment Check List**

<b>Att Doc Num</b>	<b>Name</b>
402509887	FORM 6 INTENT SUBMITTED
402509955	WELLBORE DIAGRAM

Total Attach: 2 Files

### General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Engineer	Limited historical information is available No water wells within 1 mile	10/15/2020
Permit	-Confirmed as-drilled well location. -Reviewed WBDs. -Confirmed productive interval. -Pass.	10/13/2020

Total: 2 comment(s)