


OIL AND GAS CONSERVATION COMMISSION
OF THE STATE OF COLORADO



PLUGGING RECORD

INSTRUCTIONS

Within thirty (30) days after the plugging of any well, the owner or operator thereof shall file this form in duplicate for wells on Patented or Federal lands, and in triplicate for wells on State lands, give a detailed account of the manner in which the abandonment or plugging work was carried out, including the nature and quantities of materials used in plugging and the location and extent (by depths) of the plugs of different materials; records of the amount, size and location (by depths) of casings and junk left in the well; and a detailed statement of the volume and weight of mud fluid used.

Operator TEXACO Inc. Field Tow Creek Wildcat -
Lease Name Quaintance Hocking Well No. 10 County Routt
Location SW NE Section 18 Township 6N Range 86W Meridian 6th PM
(Quarter Quarter)
1830 feet from N Section line and 2450 feet from E Section Line
N or S E or W

Int. rec'd Oct. 1961

TOTAL DEPTH	<u>2689 ft.</u>	DATE OF PLUGGING	<u>Aug. 8, 1962</u>
-------------	-----------------	------------------	---------------------

DETAILS OF WORK

Moved in and rigged up unit. Pulled rods. Pulled 85 joints of 2 3/8" tubing. Set bridge plug with one sack cement at 2500 ft. with wireline. Ran a 10 sack cement plug at 2500 ft. Shot off 5-1/2" casing at 2043 ft. Pulled 2043 ft. of 5-1/2" casing. Filled hole with mud laden fluid. Gel Based mud, weight 8.9. Set a 10 sack cement plug at surface.

Casing left in hole:

Size	From	To
12-1/2"	44'	Surface
10-3/4"	507'	Surface
5-1/2"	2617'	2043'

Cement plugs:

Size	From	To
10 sx	2500'	2420'
10 sx	20'	Surface

DVR	
WRS	
HHM	
JAM	
FJP	
JJD	<input checked="" type="checkbox"/>
FILE	

prc oil

I/we hereby swear (or affirm) that the statements herein made are a full and correct report:

Approved: _____ Date SEP 27 1962
Company TEXACO Inc. Date 8-30-62
Address Box 157, Craig, Colo. Phone No. 824-6565
By H. S. McMinn Title _____
(Signature)
H. S. McMinn, District Superintendent
Director ARB-b
OGCC (3) GRW HSMcM ASN