


COLORADO OIL AND GAS CONSERVATION COMMISSION
 PUBLIC NOTICE AND REPORTS OF WELLS




00212847



(Indicate nature of data by checking below)

Notice of intention to drill (attach plat) ☒ X
 Notice of intention to change plans _____
 Notice of date for test of water shut-off _____
 Report on result of test of water shut-off _____
 Notice of intention to re-drill or repair well _____
 Notice of intention to clean out well _____
 Statement of shooting _____
 Statement of perforating _____
 Notice to pull or otherwise alter casing _____
 Notice of intention to abandon well _____
 Report of work done on well since previous report _____

Locate Well Correctly



Notice to do work ☒ X Land: Fee and Patented ☐
 Report of work done ☐ State ☒ X Lease No. _____

Colorado State Routt County Tow Creek Field

10 Quaintance-Hocking NE 18 6N 86W 6
 (Well No.) (Lease) (1/4 Sec.) (Sec.) (Twp.) (Range) (Meridian)

The Well is located 1830 Ft. (N) of Section Line and 2450 Ft. (E) of
 (S) (W)
 Section Line.

The elevation above sea level is 6502 Ft. Ground

Details of Plan of Work: (State names of and expected depths to objective sands.
 Show sizes, weights, and length of proposed casings; indicate mudding jobs, cementing
 points, and all other important proposed work.)

The cable tool development well will be drilled to an estimated
 T.D. between 2550' and 3195' and completed in Mancos Shale fracture
 zones. 500' of 10-3/4" surface casing will be set and cemented to
 surface. Up to 1500' of 8-5/8" cave string will be set and ultimately
 retrieved--- some cementing may be done. 5 1/2" production casing will
 be set at about 2500' above any pay horizons. No special electric
 or radioactivity logs, or completion techniques are anticipated.

| | |
|------|-------------------------------------|
| AJJ | |
| DVR | |
| FJK | |
| WRS | |
| HHM | |
| AH | |
| JJD | <input checked="" type="checkbox"/> |
| FILE | |

Approved: MAY 28 1956

Director

Date May 25, 1956

Company The Texas Company

Address Craig, Colorado

By H. L. McManis

Title District Superintendent

Submit reports of proposed work, for approval, on this form in Duplicate for patented
 lands and in Triplicate for school and state lands.