


OIL AND GAS CONSERVATION COMMISSION
OF THE STATE OF COLORADOOIL & GAS
NOTICES AND REPORTS ON WELLS
CONSERVATION COMMISSION

INSTRUCTIONS

Notice must be given to the Director, and approval obtained in advance of the time when the owner or operator expects to recompleate or abandon a well or to change plans. Within thirty (30) days after recompleation, change of plans, or remedial work, a detailed report of the work done and the results obtained shall be submitted on this form in duplicate for wells on Patented and Federal lands, and in triplicate for wells on State lands. In work that affects only rods, pumps or tubing or other routine work such as, but not limited to, cleaning out to previous total depth, no report is necessary.

Notice of Intention to Recomplete

☐

Report of Remedial Work

☐

Notice of Intention to Change Plans

☐

Report of Recompleation

☐

Notice of Intention to Abandon Well

☒

Other

☐

(Check appropriate space)

LEASE NAME State Lubers WELL NO. 1
FIELD Tow Creek WILDCAT COUNTY Routt
LOCATION NW SE Section 18 Township 6N Range 86 Meridian 6th PM
(Quarter Quarter)
2300 feet from S Section Line and 2000 feet from E Section Line
N or S E or W

(DETAILS OF WORK)

We propose to abandon this well as it is uneconomical to produce. Approximately 500 ft. of 10", 1500 ft. of 8 1/4", and 2685 ft. of 6 1/4" casing will be pulled, the well will be plugged, and a marker set as per OGCC regulations.

We plan to pull rods, tubing, and 6 5/8" casing. Set a 10 sack cement plug in the 8 5/8" casing at 2000 ft. using the pump and plug method. Cut and pull approximately 1500 ft. of 8 5/8" casing. Fill hole with mud laden fluid and set a 10 sack cement plug and marker at the surface.

AJJ	
DVR	
WRS	
HHM	
JAM	
FJP	
JJD	
FILE	

I/We hereby swear (or affirm) that the statements herein made are a full and correct report.

APPROVED:

AUG 20 1962

Date

Director

Company TEXACO Inc.Date 8-4-62Address Box 157, Craig, Colo. Phone No. 824-6565

By

(Signature)

Title

JNH-ARB

OGCC (3) GRW HSMcM

H. S. McMinn, District Superintendent