


OIL AND GAS CONSERVATION COMMISSION
OF THE STATE OF COLORADO

PLUGGING RECORD

OIL & GAS
CONSERVATION COMMISSION

INSTRUCTIONS

Within thirty (30) days after the plugging of any well, the owner or operator thereof shall file this form in duplicate for wells on Patented or Federal lands, and in triplicate for wells on State lands, give a detailed account of the manner in which the abandonment or plugging work was carried out, including the nature and quantities of materials used in plugging and the location and extent (by depths) of the plugs of different materials; records of the amount, size and location (by depths) of casings and junk left in the well; and a detailed statement of the volume and weight of mud fluid used.

Operator The Texas Company Field Tow Creek Wildcat
Lease Name State Peterson Well No. 2 County Routt
Location C NW $\frac{1}{4}$ NE $\frac{1}{4}$ SW $\frac{1}{4}$ Section 18 Township 6N Range 86W Meridian 6th
(Quarter Quarter)
3016 feet from N Section line and 1571 feet from W Section Line
N or S E or W

TOTAL DEPTH 3800DATE OF PLUGGING 11-9-57

DETAILS OF WORK

Load hole with mud 9.2# from present TD approximately 3800' to 3070' the bottom of 5 $\frac{1}{2}$ " casing. Place bridge in bottom of 5 $\frac{1}{2}$ ", dump 5 sacks cement on top of bridge. Cut-off 5" above free-point at approximately 2470'. Place bridge at top of parted 5 $\frac{1}{2}$ " casing, dump 5 sacks cement at this point. Pull 5 $\frac{1}{2}$ " casing, load hole with 9.2# mud. Place bridge at 105', bottom of 13-3/8" surface. Dump 15 sacks on top of bridge. Load pipe with mud, place 10 sacks of cement at top of 13-3/8" casing.

DISTRICT OFFICE
OAKRIDGE
DEC 13 1957
PRODUCING DEPARTMENT
RECEIVED

AJJ	
DVD	
FJK	
WRS	<input checked="" type="checkbox"/>
HMA	
AH	
JJD	
FILE	

I/we hereby swear (or affirm) that the statements herein made are a full and correct report:

Approved:

Company The Texas Company Date 12-19-57Date DEC 21 1957Address Craig, Colorado Phone No. TA 4-6565

Director

By A. S. McManis Title Dist. Supt.
(Signature)

OGCC (3) TTF HSMcM CLM