


OIL AND GAS CONSERVATION COMMISSION
OF THE STATE OF COLORADOOIL & GAS
CONSERVATION COMMISSION

PLUGGING RECORD

INSTRUCTIONS

Within thirty (30) days after the plugging of any well, the owner or operator thereof shall file this form in duplicate for wells on Patented or Federal lands, and in triplicate for wells on State lands, give a detailed account of the manner in which the abandonment or plugging work was carried out, including the nature and quantities of materials used in plugging and the location and extent (by depths) of the plugs of different materials; records of the amount, size and location (by depths) of casings and junk left in the well; and a detailed statement of the volume and weight of mud fluid used.

Operator TEXACO Inc. Field Tow Creek Wildeat -
Lease Name State Lubers Well No. 3 County Routt
Location NW SE Section 18 Township 6N Range 86W Meridian 6th PM
(Quarter Quarter)
2300 feet from S Section line and 1500 feet from E Section Line
N or S E or W

Int rec'd Oct 1961
TOTAL DEPTH 2742 ft. DATE OF PLUGGING Aug. 11, 1962

DETAILS OF WORK

Moved in and rigged up. Pulled rods. Pulled 83 joints of 2-3/8" tubing. Set bridge plug at 2500 ft. Set a 10 sack cement plug at 2500 ft. Shot off 5-1/2" casing at 2247 ft. Pulled 2247 ft. of 5-1/2" casing. Filled hole with mud laden fluid. Set a 10 sack cement plug at surface. Used Gel based mud, weight 8.9.

Casing left in hole:

Size	From	To
10-3/4"	557'	Surface
5-1/2"	2588'	2247'

Cement plugs:

Size	From	To
10 sx	2500'	2420'
10 sx	20	Surface

DVR	
WRS	
HHM	
JAM	
FJP	
JJD	
FILE	

per oil

I/we hereby swear (or affirm) that the statements herein made are a full and correct report:

Approved:

Company TEXACO Inc. Date 8-30-62Date SEP 27 1962Address Box 157, Craig, Colo Phone No. 824-6565By H. S. McMinn Title _____
(Signature)

H. S. McMinn, District Superintendent

Director

ARB-b

OGCC (3) GRW HSMcM ASN