

FORM  
6

Rev  
02/20

# State of Colorado

## Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

Document Number:

402513474

Date Received:

### WELL ABANDONMENT REPORT

This form is to be submitted as an Intent to Abandon whenever an abandonment is planned on a borehole. After the abandonment is complete, this form shall again be submitted as a Subsequent Report of the actual work completed. The approved intent shall be valid for six months after the approval date, after that period, a new intent will be required. Attachments required with the Intent to Abandon are wellbore diagrams of the current configuration and the proposed configuration with plugs set.

A Subsequent Report of Abandonment shall indicate the actual work completed. Attachments required with a Subsequent Report are a wellbore diagram showing plugs that were set and casing remaining in the hole, the job summaries from all plugging contractors used, including wireline and cementing (third party verification) and any logs that may have been run during abandonment.

OGCC Operator Number: 10433 Contact Name: Dan Fouts  
Name of Operator: LARAMIE ENERGY LLC Phone: (970) 852-1170  
Address: 1401 SEVENTEENTH STREET #1401 Fax: \_\_\_\_\_  
City: DENVER State: CO Zip: 80202 Email: dfouts@laramie-energy.com

**For "Intent" 24 hour notice required,** Name: \_\_\_\_\_ Tel: \_\_\_\_\_  
COGCC contact: Email: \_\_\_\_\_

Type of Well Abandonment Report:  Notice of Intent to Abandon  Subsequent Report of Abandonment

API Number 05-077-09236-00  
Well Name: RED MOUNTAIN RANCH Well Number: 33-13  
Location: QtrQtr: NESW Section: 33 Township: 9S Range: 94W Meridian: 6  
County: MESA Federal, Indian or State Lease Number: \_\_\_\_\_  
Field Name: PLATEAU Field Number: 69300

#### Only Complete the Following Background Information for Intent to Abandon

Latitude: 39.232502 Longitude: -107.887408  
GPS Data: GPS Quality Value: 2.6 Type of GPS Quality Value: PDOP Date of Measurement: 06/13/2008  
GPS Instrument Operator's Name: Matt Busker

Reason for Abandonment:  Dry  Production Sub-economic  Mechanical Problems  
 Other \_\_\_\_\_

Casing to be pulled:  Yes  No Estimated Depth: \_\_\_\_\_

Fish in Hole:  Yes  No If yes, explain details below

Wellbore has Uncemented Casing leaks:  Yes  No If yes, explain details below

Details: \_\_\_\_\_

#### Current and Previously Abandoned Zones

Formation	Perf. Top	Perf. Btm	Abandoned Date	Method of Isolation	Plug Depth
COZZETTE	6841	6980	04/01/2015	B PLUG CEMENT TOP	5300
CORCORAN	6980	7010	04/01/2015	B PLUG CEMENT TOP	5300
WILLIAMS FORK - CAMEO	5350	6363	04/01/2015	B PLUG CEMENT TOP	5300

Total: 3 zone(s)

#### Casing History

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bot	Cement Top	Status
CONDUCTOR	24	16	.25 wall	40	100	40	0	CALC
SURF	12+1/4	8+5/8	32	1,513	420	1,513	0	CALC
1ST	7+7/8	4+1/2	11.6	7,208	1,200	7,208	1,130	CBL

### Plugging Procedure for Intent and Subsequent Report

CIBP #1: Depth \_\_\_\_\_ with \_\_\_\_\_ sacks cmt on top. CIBP #2: Depth \_\_\_\_\_ with \_\_\_\_\_ sacks cmt on top.  
 CIBP #3: Depth \_\_\_\_\_ with \_\_\_\_\_ sacks cmt on top. CIBP #4: Depth \_\_\_\_\_ with \_\_\_\_\_ sacks cmt on top.  
 CIBP #5: Depth \_\_\_\_\_ with \_\_\_\_\_ sacks cmt on top.

NOTE: Two(2) sacks cement required on all CIBPs.

Set 10 sks cmt from 3512 ft. to 3380 ft. Plug Type: CASING Plug Tagged:   
 Set 20 sks cmt from 1919 ft. to 1655 ft. Plug Type: CASING Plug Tagged:   
 Set 15 sks cmt from 1602 ft. to 1404 ft. Plug Type: CASING Plug Tagged:   
 Set \_\_\_\_\_ sks cmt from \_\_\_\_\_ ft. to \_\_\_\_\_ ft. Plug Type: \_\_\_\_\_ Plug Tagged:   
 Set \_\_\_\_\_ sks cmt from \_\_\_\_\_ ft. to \_\_\_\_\_ ft. Plug Type: \_\_\_\_\_ Plug Tagged:

Perforate and squeeze at 100 ft. with 42 sacks. Leave at least 100 ft. in casing \_\_\_\_\_ CICR Depth  
 Perforate and squeeze at \_\_\_\_\_ ft. with \_\_\_\_\_ sacks. Leave at least 100 ft. in casing \_\_\_\_\_ CICR Depth  
 Perforate and squeeze at \_\_\_\_\_ ft. with \_\_\_\_\_ sacks. Leave at least 100 ft. in casing \_\_\_\_\_ CICR Depth  
 (Cast Iron Cement Retainer Depth)

Set \_\_\_\_\_ sacks half in. half out surface casing from \_\_\_\_\_ ft. to \_\_\_\_\_ ft. Plug Tagged:   
 Set \_\_\_\_\_ sacks at surface  
 Cut four feet below ground level, weld on plate Above Ground Dry-Hole Marker:  Yes  No  
 Set \_\_\_\_\_ sacks in rat hole Set \_\_\_\_\_ sacks in mouse hole

### Additional Plugging Information for Subsequent Report Only

Casing Recovered: \_\_\_\_\_ ft. of \_\_\_\_\_ inch casing Cut and Cap Date: 09/22/2020  
 \*Wireline Contractor: DLD Pipe Recovery \*Cementing Contractor: ProPetro  
 Type of Cement and Additives Used: Premium (G) Neat  
 Flowline/Pipeline has been abandoned per Rule 1105  Yes  No

Technical Detail/Comments:  
 The flowline is in the process of being abandoned; a Form 42 will be submitted when the abandonment is completed.

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.  
 Signed: \_\_\_\_\_ Print Name: Joan Proulx  
 Title: Regulatory Analyst Date: \_\_\_\_\_ Email: jproulx@laramie-energy.com

Based on the information provided herein, this Well Abandonment Report (Form 6) complies with COGCC Rules and applicable orders and is hereby approved.  
 COGCC Approved: \_\_\_\_\_ Date: \_\_\_\_\_

**CONDITIONS OF APPROVAL, IF ANY:**

COA Type	Description

## Attachment Check List

<u>Att Doc Num</u>	<u>Name</u>
402513481	WELLBORE DIAGRAM
402513482	CEMENT JOB SUMMARY
402513483	WIRELINER JOB SUMMARY

Total Attach: 3 Files

## General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
		Stamp Upon Approval

Total: 0 comment(s)