

FORM
6Rev
02/20

State of Colorado Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

402424270

Date Received:

06/17/2020

WELL ABANDONMENT REPORT

This form is to be submitted as an Intent to Abandon whenever an abandonment is planned on a borehole. After the abandonment is complete, this form shall again be submitted as a Subsequent Report of the actual work completed. The approved intent shall be valid for six months after the approval date, after that period, a new intent will be required. Attachments required with the Intent to Abandon are wellbore diagrams of the current configuration and the proposed configuration with plugs set.

A Subsequent Report of Abandonment shall indicate the actual work completed. Attachments required with a Subsequent Report are a wellbore diagram showing plugs that were set and casing remaining in the hole, the job summaries from all plugging contractors used, including wireline and cementing (third party verification) and any logs that may have been run during abandonment.

OGCC Operator Number: 100322

Contact Name: Kevin Monaghan

Name of Operator: NOBLE ENERGY INC

Phone: (970) 3812990

Address: 1001 NOBLE ENERGY WAY

Fax:

City: HOUSTON State: TX Zip: 77070

Email: kevin.monaghan@nblenergy.com

For "Intent" 24 hour notice required,

Name:

Tel:

COGCC contact:

Email:

Type of Well Abandonment Report:



Notice of Intent to Abandon



Subsequent Report of Abandonment

API Number 05-123-23226-00

Well Name: BERNHARDT J

Well Number: 31-19

Location: QtrQtr: SENW

Section: 31

Township: 5N

Range: 66W

Meridian: 6

County: WELD

Federal, Indian or State Lease Number:

Field Name: WATTENBERG

Field Number: 90750

Only Complete the Following Background Information for Intent to Abandon

Latitude: 40.359460

Longitude: -104.826850

GPS Data: GPS Quality Value: 2.1 Type of GPS Quality Value: Date of Measurement: 07/03/2007

GPS Instrument Operator's Name: Paul Tappy

Reason for Abandonment:



Dry



Production Sub-economic



Mechanical Problems

☐ Other

Casing to be pulled:



Yes



No

Estimated Depth:

Fish in Hole:



Yes



No

If yes, explain details below

Wellbore has Uncemented Casing leaks:



Yes



No

If yes, explain details below

Details:

Current and Previously Abandoned Zones

Formation	Perf. Top	Perf. Btm	Abandoned Date	Method of Isolation	Plug Depth
CODELL	7354	7371	10/02/2019	B PLUG CEMENT TOP	6982
NIOBRARA	7030	7170	10/02/2019	B PLUG CEMENT TOP	6982

Total: 2 zone(s)

Casing History

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bot	Cement Top	Status
SURF	12+1/4	8+5/8	24	537	375	537	0	VISU
1ST	7+7/8	4+1/2	11.6	7,498	150	7,498	6,558	CBL
S.C. 1.1				5,276	530	5,256	3,242	CBL

Plugging Procedure for Intent and Subsequent Report

CIBP #1: Depth 6982 with 10 sacks cmt on top. CIPB #2: Depth _____ with _____ sacks cmt on top.
CIBP #3: Depth _____ with _____ sacks cmt on top. CIPB #4: Depth _____ with _____ sacks cmt on top.
CIBP #5: Depth _____ with _____ sacks cmt on top.

NOTE: Two(2) sacks cement required on all CIBPs.

Set <u>10</u> sks cmt from <u>6980</u> ft. to <u>6848</u> ft.	Plug Type: <u>CASING</u>	Plug Tagged: <input type="checkbox"/>
Set <u>220</u> sks cmt from <u>2563</u> ft. to <u>2158</u> ft.	Plug Type: <u>STUB PLUG</u>	Plug Tagged: <input checked="" type="checkbox"/>
Set <u>100</u> sks cmt from <u>2153</u> ft. to <u>1893</u> ft.	Plug Type: <u>OPEN HOLE</u>	Plug Tagged: <input type="checkbox"/>
Set _____ sks cmt from _____ ft. to _____ ft.	Plug Type: _____	Plug Tagged: <input type="checkbox"/>
Set _____ sks cmt from _____ ft. to _____ ft.	Plug Type: _____	Plug Tagged: <input type="checkbox"/>

Perforate and squeeze at _____ ft. with _____ sacks. Leave at least 100 ft. in casing _____ CICR Depth

Perforate and squeeze at _____ ft. with _____ sacks. Leave at least 100 ft. in casing _____ CICR Depth

Perforate and squeeze at _____ ft. with _____ sacks. Leave at least 100 ft. in casing _____ CICR Depth

(Cast Iron Cement Retainer Depth)

Set 265 sacks half in. half out surface casing from 751 ft. to 0 ft. Plug Tagged: ☒

Set 5 sacks at surface

Cut four feet below ground level, weld on plate Above Ground Dry-Hole Marker: ☐ Yes ☐ No

Set _____ sacks in rat hole Set _____ sacks in mouse hole

Additional Plugging Information for Subsequent Report Only

Casing Recovered: 2500 ft. of 4+1/2 inch casing Cut and Cap Date: 02/10/2020

*Wireline Contractor: SPN

*Cementing Contractor: Ranger, Cementers Well Service

Type of Cement and Additives Used: Class G Neat

Flowline/Pipeline has been abandoned per Rule 1105 ☒ Yes ☐ No

Technical Detail/Comments:

Form 17 DocNum: 402196772
Form 42 DocNum: 402190938
Form 44 DocNum: 402362829

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Lindsay Rodriguez

Title: Regulatory Analyst Date: 6/17/2020 Email: denverregulatory@nblenergy.com

Based on the information provided herein, this Well Abandonment Report (Form 6) complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: Jacobson, Eric Date: 11/19/2020

CONDITIONS OF APPROVAL, IF ANY:

COA Type	Description

Attachment List

<u>Att Doc Num</u>	<u>Name</u>
402424270	FORM 6 SUBSEQUENT SUBMITTED
402424278	CEMENT BOND LOG
402424279	GYRO SURVEY
402424280	CEMENT JOB SUMMARY
402424281	OPERATIONS SUMMARY
402424282	WELLBORE DIAGRAM
402424283	WIRELINE JOB SUMMARY

Total Attach: 7 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
		Stamp Upon Approval

Total: 0 comment(s)