

# DUCO INCORPORATED

Well Servicing Company

2403 1/2 E. Main - PO Box 416 (mailing)

Rangely, CO 81648

Phone (970-629-1906 or (970)-675-8685

## CMT Package

11/5/2020

INVOICE #C0110520CMT

### COMMENTS

Hiring Company: Ensign

CMT truck operator: Brian Rector

Pod trailer operator: Nick Rohr

fuel used:65 gallons

Lease: *MILLAGE 11-10*

Company Foreman:

Signature:



Hour Work Started:

Hour Work Completed:

BREAKDOWN OF CHARGES	HOURS/QT.	RATE	AMOUNT
Day Rate for CMT truck and Pod trailer	1.00		
skts of cmt	170.00		
	0.00		
	0.00		
	0.00		
	0.00		
	0.00		
	0.00		
	0.00		
	0.00		
	0.00		
	0.00		
	0.00		
	0.00		
	0.00		

#### DESCRIPTION OF WORK PERFORMED:

11-5-20 arrived at location RIH WL perf @1480' and 1280' set CICR @1295' Mix and pump 90skts of class g cmt 1.15 yeild 15.8lbs below CICR and 10skts on top brings good CMT top to 1163' lay down 18 joints MIX and pump 60skts of class g cmt 1.15 yeild 15.8lbs bring good cmt to surface TOOH laying rest of TBG down top off well with 10skts of class g cmt bring good cmt to surface.

Make all checks payable to: **Duco Inc.**

All accounts net 30 days. 24% per annum interest plus cost of attorney's fees and collection fees

THANK YOU FOR YOUR BUSINESS!

## RMWS - Service Ticket & Invoice:

Rocky Mountain Wireline Service  
2144 Hwy 6 & 50  
Grand Junction, CO 81505  
970-245-9828



**Ticket Number**

**115114**

**Date**

11/5/2020

**Well**

Millage 11-10

**Field**

dj

**County / State**

Weld / Colorado

### Services provided for:

ENSIGN WELL SERVICE  
2154 Hwy 6 & 50  
Grand Junction, Colorado 81505

### Job Data

<b>Field Office</b>	<b>Line Truck #</b>	<b>Crane #</b>	<b>Pickup Truck #</b>	<b>Explosives Permit #</b>	<b>CSG Size</b>	<b>WT</b>
Casper-WY	216		68	1-998-05047	4.5	10.5
<b>Crew Members</b>						
M HARTFORD , K ARIMA						
<b>Zero</b>	<b>Fluid</b>	<b>Level</b>	<b>RMWS TD</b>	<b>Corrected</b>	<b>To Agree With</b>	<b>Dated</b>
16	WATER	FULL	3500		KB	11/5/2020
<b>Consultant</b>						

### Job Notes

### Travel

<b>Report To Shop</b>	<b>Arrive At Location</b>	<b>On Well</b>	<b>Off well</b>
11/5/2020 8:00 AM MST	11/5/2020 9:45 AM MST		
<b>Depart Location</b>	<b>Return To Shop</b>	<b>Travel Notes</b>	

### Activity

#### Logging - Bid Work

Description	From	To	Units Used
Ensign - CBL 2,000' +		0 3500	1.00 Units

#### Miscellaneous - Bid Work

Description	From	To	Units Used
Ensign - 4 1/2" 10K CIBP @ 5,000' or less		3200	1.00 Units
Ensign - Dump Bail 2 SX Cement (STANDARD)		3200	1.00 Units
Ensign - CICR @ 5,000' or less (CICR NOT INCLUDED)		1295	1.00 Units
Ensign - Slow Set Charge		1295	1.00 Units

#### Perforating - Bid Work

Description	Stage	From	To	Plug	Date	Units Used
Ensign - 4 1/2" or 5 1/2" Upper & Lower Sqz 3spf/1' @ 5,000' or less		1480	1280			1.00 Units

### Signatures

**Authorization Signature**

A handwritten signature in black ink, appearing to be "M" or "McGraw", written over a horizontal line.

**Authorization Notes**

11/5/2020 3:49 PM MST

**AFE**

**Cost Code**

**Well / Lease**

**Approver Name**

matt mcgraw

**Stamp**

11/6/2020 2:23 PM MST

RMWS - Service Ticket & Invoice #115114

Page 1 of 1