



## Well History

**Well Name: Nelson 43-32D**

API 05123331120000		Surface Legal Location SESE 32 7N 66W		Field Name Eaton		State CO		Well Configuration Type Directional	
Ground Elevation (ft) 4,860.00	Original KB Elevation (ft) 4,874.00	KB-Ground Distance (ft) 14.00	Spud Date 6/14/2011 12:30	Rig Release Date 6/18/2011 20:15	On Production Date 8/10/2011	Abandon Date 11/6/2020			

### Daily Operations

Start Date	Summary	End Date
11/6/2020	<p>MIRU ENSIGN RIG 312</p> <p>HELD SAFETY MEETING. SITP 270 PSI, SICP 120 PSI, SIBH 0 PSI. WELL WAS OPENED UP AND BURNED OFF THROUGH INCINERATOR TO 0 PSI ON BOTH TBG AND CSG. SPOTTED IN EQUIPMENT, R/U RIG 312, R/U PUMP AND LINES. BROKE CIRCULATION WITH 130 BBLS, ROLLED HOLE FOR 1.5 HRS TO ELIMINATE ALL OIL AND GAS FROM WELLBORE. N/D PRODUCTION TREE, N/U AND FUNCTION TESTED BOP STACK, R/U RIG FLOOR AND HANDLING TOOLS. UNLANDED TBG, REMOVED TBG HANGER, TOOH WITH 24 STANDS (48 JTS) TO DERRICK, LAYED DOWN 180 JTS ONTO TBG TRAILER (228 TOTAL JTS PULLED FROM WELL). R/U WIRELINE, RIH WITH 4.5" GAUGE RING TO 7100', POOH, RIH WITH 4.5" CIBP AND SET @ 7078', GOOD SET, POOH, RIH AND DUMP BAILED 2 SXS CEMENT ON TOP OF PLUG, POOH. FILLED CSG WITH 17 BBLS, PRESSURED UP TO 1000 PSI, HELD FOR 10 MINUTES WITH 0 PSI LOSS. RIH WITH 4.5" CIBP AND SET @ 2700', GOOD SET, POOH, RIH AND DUMP BAILED 2 SXS CEMENT ON TOP OF PLUG, POOH, R/D WIRELINE. TIH WITH 24 STANDS (48 JTS) PLACING EOT @ 1540'. R/U CEMENT, PRESSURE TESTED LINES TO 2000 PSI, GOOD TEST. PUMPED 5 BBLS FW FOLLOWED BY 119 SXS (24.5 BBLS) 15.8# 'G' CEMENT TO BRING CEMENT TO SURFACE. LAYED DOWN TBG ONTO TRAILER. R/D RIG FLOOR AND HANDLING TOOLS, N/D BOP STACK. TOP CAPPED WELL WITH 15 SXS (3 BBLS) 15.8# 'G' CEMENT, R/D CEMENT. SECURED WELL, CLEANED UP LOCATION. DUG UP WELL. CUT AND CAPPED WELL 6' BELOW GROUND LEVEL. WELDED ON MARKER PLATE AND BURIED WELL. TURNED OVER TO THE CONSTRUCTION DEPT TO ABANDON THE FLOWLINE.</p> <p>THIS IS THE FINAL REPORT.</p> <p>NOTE THERE WAS NO CSG RECOVERED FROM THIS WELL. THERE WAS 228 JTS 2 3/8" 4.70# J-55 8RD TBG SOLD TO KARST.</p>	11/6/2020