

FORM

2

Rev  
02/20

## State of Colorado

## Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203  
Phone: (303) 894-2100 Fax: (303) 894-2109

Document Number:

402286134

## APPLICATION FOR PERMIT TO:

☒ Drill
 ☐ Deepen
 ☐ Re-enter
 ☐ Recomplete and Operate

Date Received:

10/12/2020

TYPE OF WELL OIL ☒ GAS ☐ COALBED ☐ OTHER: \_\_\_\_\_Refiling ☒ZONE TYPE SINGLE ZONE ☒ MULTIPLE ZONES ☐ COMMINGLE ZONES ☐Sidetrack ☐

Well Name: Buford

Well Number: 33-2-4L

Name of Operator: CONFLUENCE DJ LLC

COGCC Operator Number: 10518

Address: 1001 17TH STREET #1250

City: DENVER State: CO Zip: 80202

Contact Name: Brittany Rothe

Phone: (303)226-9519

Fax: ( )

Email: brothe@confluencelp.com

## RECLAMATION FINANCIAL ASSURANCE

Plugging and Abandonment Bond Surety ID: 20160056

## WELL LOCATION INFORMATION

QtrQtr: SWSW Sec: 34 Twp: 1N Rng: 65W Meridian: 6

Latitude: 40.002660

Longitude: -104.656270

Footage at Surface: 770 Feet FNL/FSL FSL 919 Feet FEL/FWL FWL

Field Name: WATTENBERG

Field Number: 90750

Ground Elevation: 5137

County: WELD

GPS Data:

GPS Quality Value: 1.4

Type of GPS Quality Value: PDOP

Date of Measurement: 05/30/2017

Instrument Operator's Name: Kyle Daley

If well is ☐ Directional ☒ Horizontal (highly deviated) submit deviated drilling plan.

Footage at Top of Prod Zone: FNL/FSL FEL/FWL Bottom Hole: FNL/FSL FEL/FWL

470 FSL 536 FEL 470 FNL 536 FEL

Sec: 33 Twp: 1N Rng: 65W Sec: 28 Twp: 1N Rng: 65W

## LOCAL GOVERNMENT INFORMATION

County: WELD

Municipality: N/A

Per § 34-60-106 (1)(f)(I)(A), the following questions pertain to the "local government with jurisdiction to approve the siting of the proposed oil and gas location."

The local government with jurisdiction is: County

Does the local government with jurisdiction regulate the siting of Oil and Gas Locations, with respect to this location? If the local government does regulate the siting, but has waived its right to precede the COGCC in siting determination, indicate by selecting "YES" here and selecting "Waived" for the disposition below.

☒ Yes ☐ NoIf yes, in checking this box, I hereby certify that an application has been filed with the local government with jurisdiction to approve the siting of the proposed oil and gas location. ☒

The local government siting permit type is: WOGLA

The local government siting permit was filed on: 01/17/2018

The disposition of the application filed with the local government is: Approved

Additional explanation of local process:

WOGLA18-0002 was approved on March 19, 2018.

## LOCATION SURFACE & MINERALS & RIGHT TO CONSTRUCT

Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

The Surface Owner is: ☐ is the mineral owner beneath the location.

(check all that apply) ☐ is committed to an Oil and Gas Lease.

☐ has signed the Oil and Gas Lease.

☐ is the applicant.

The Mineral Owner beneath this Oil and Gas Location is: ☒ Fee ☐ State ☐ Federal ☐ Indian

The Minerals beneath this Oil and Gas Location will be developed by this Well: No

The right to construct the Oil and Gas Location is granted by: Surface Use Agreement

Surface damage assurance if no agreement is in place: \_\_\_\_\_ Surface Surety ID: \_\_\_\_\_

## LEASE INFORMATION

Using standard QtrQtr, Sec, Twp, Rng format, describe one entire mineral lease that will be produced by this well (Describe lease beneath surface location if produced. Attach separate description page or map if necessary.)

T1N R65W Section 33: All

Total Acres in Described Lease: 640 Described Mineral Lease is: ☒ Fee ☐ State ☐ Federal ☐ Indian

Federal or State Lease # \_\_\_\_\_

Distance from Completed Portion of Wellbore to Nearest Lease Line of described lease: 0 Feet

## CULTURAL DISTANCE INFORMATION

Distance to nearest:

Building:	<u>1046</u> Feet
Building Unit:	<u>1216</u> Feet
High Occupancy Building Unit:	<u>5280</u> Feet
Designated Outside Activity Area:	<u>5280</u> Feet
Public Road:	<u>754</u> Feet
Above Ground Utility:	<u>1201</u> Feet
Railroad:	<u>5280</u> Feet
Property Line:	<u>402</u> Feet
School Facility:	<u>5280</u> Feet
School Property Line:	<u>5280</u> Feet
Child Care Center:	<u>5280</u> Feet

### INSTRUCTIONS:

- All measurements shall be provided from center of the Proposed Well to nearest of each cultural feature as described in Rule 303.a.(5).
- Enter 5280 for distance greater than 1 mile.
- Building - nearest building of any type. If nearest Building is a Building Unit, enter same distance for both.
- Building Unit, High Occupancy Building Unit, Designated Outside Activity Area, School Facility, and Child Care Center – as defined in 100 Series Rules.

## DESIGNATED SETBACK LOCATION INFORMATION

Check all that apply. This location is within a:

-  Buffer Zone
-  Exception Zone
-  Urban Mitigation Area

- Buffer Zone – as described in Rule 604.a.(2), within 1,000' of a Building Unit
- Exception Zone - as described in Rule 604.a.(1), within 500' of a Building Unit.
- Urban Mitigation Area - as defined in 100-Series Rules.

Pre-application Notifications (required if location is within 1,000 feet of a building unit):

Date of Rule 305.a.(1) Urban Mitigation Area Notification to Local Government:

Date of Rule 305.a.(2) Buffer Zone Notification to Building Unit Owners:

## SPACING and UNIT INFORMATION

Distance from completed portion of proposed wellbore to nearest completed portion of offset wellbore permitted or completed in the same formation: 288 Feet

Distance from Completed Portion of Wellbore to Nearest Unit Boundary	470	Feet (Enter 5280 for distance greater than 1 mile.)
--	-----	---

Federal or State Unit Name (if appl): \_\_\_\_\_ Unit Number: \_\_\_\_\_

### SPACING & FORMATIONS COMMENTS

\_\_\_\_\_

If this Form 2 is associated with a Drilling and Spacing Unit application, provide docket number:

## OBJECTIVE FORMATIONS

<u>Objective Formation(s)</u>	<u>Formation Code</u>	<u>Spacing Order Number(s)</u>	<u>Unit Acreage Assigned to Well</u>	<u>Unit Configuration (N/2, SE/4, etc.)</u>
-------------------------------	-----------------------	--------------------------------	--------------------------------------	---

CODELL	CODL	407-2173	1280	Sec: 28 & 33: All
--------	------	----------	------	-------------------

## DRILLING PROGRAM

Proposed Total Measured Depth: 17720 Feet

Distance from the proposed wellbore to nearest existing or proposed wellbore belonging to another operator, including plugged wells:

Enter distance if less than or equal to 1,500 feet: 124 Feet ☐ No well belonging to another operator within 1,500 feet

Will a closed-loop drilling system be used? Yes

Is H<sub>2</sub>S gas reasonably expected to be encountered during drilling operations at concentrations greater than or equal to 100 ppm? No (If Yes, attach an H<sub>2</sub>S Drilling Operations Plan)

Will salt sections be encountered during drilling? No

Will salt based (>15,000 ppm Cl) drilling fluids be used? No

Will oil based drilling fluids be used? Yes

BOP Equipment Type: ☒ Annular Preventor ☒ Double Ram ☒ Rotating Head ☐ None

## GROUNDWATER BASELINE SAMPLING AND MONITORING AND WATER WELL SAMPLING

Water well sampling required per Rule 318A

## DRILLING WASTE MANAGEMENT PROGRAM

Drilling Fluids Disposal: OFFSITE Drilling Fluids Disposal Methods: Commercial Disposal

Cuttings Disposal: OFFSITE Cuttings Disposal Method: Commercial Disposal

Other Disposal Description:

Beneficial reuse or land application plan submitted?

Reuse Facility ID:  or Document Number:

## CASING PROGRAM

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	26	16	43	0	80	400	80	0
SURF	13+1/2	9+5/8	36	0	1500	878	1500	0
1ST	8+1/2	5+1/2	20	0	17720	1928	17720	

☐ Conductor Casing is NOT planned

## DESIGNATED SETBACK LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 604.a.(1)A. Exception Zone (within 500' of Building Unit)
- ☐ Rule 604.b.(1)A. Exception Location (existing or approved Oil & Gas Location now within a Designated Setback as a result of Rule 604.a.)
- ☐ Rule 604.b.(1)B. Exception Location (existing or approved Oil & Gas Location is within a Designated Setback due to Building Unit construction after Location approval)
- ☐ Rule 604.b.(2) Exception Location (SUA or site-specific development plan executed on or before August 1, 2013)
- ☐ Rule 604.b.(3) Exception Location (Building Units constructed after August 1, 2013 within setback per an SUA or site-specific development plan)

## GREATER WATTENBERG AREA LOCATION EXCEPTIONS

Check all that apply:

- ☒ Rule 318A.a. Exception Location (GWA Windows).
- ☒ Rule 318A.c. Exception Location (GWA Twinning).

## RULE 502.b VARIANCE REQUEST

☐ Rule 502.b. Variance Request from COGCC Rule or Spacing Order Number \_\_\_\_\_

## OTHER LOCATION EXCEPTIONS

Check all that apply:

☐ Rule 318.c. Exception Location from Rule or Spacing Order Number \_\_\_\_\_

☐ Rule 603.a.(2) Exception Location (Property Line Setback).

ALL exceptions and variances require attached Request Letter(s). Refer to applicable rule for additional required attachments (e.g. waivers, certifications, SUAs).

## OPERATOR COMMENTS AND SUBMITTAL

Comments Distance from completed portion of the wellbore to nearest wellbore permitted or completed well in the same formation and within the unit was measured to the permitted Buford 33-2-2L measured in 3-D, and determined from an Anti-Collision Report for the Buford 33-2-2L.

The distance from the proposed wellbore to nearest existing or proposed wellbore belonging to another operator, including plugged wells was measured to the Jordan 34-9, Status: PA API#: 05-123-12937 in 2-D separation. No stimulation setback consent is not required because the offset well is D&A'd.

This well is less than 150' to the Kerr McGee HSR Cherry Knolls 9-33; status DA, API # 05-123-19677. No stimulation setback consent is not required because the offset well is D&A'd.

Changes to this well are landing point, bottom hole, casing and cement program.

The oil and gas location has been built and has a producing well on it.

The 2A was amended in July of 2019 with updated Best Management Practices (BMP"s), per the director's objective criteria.

The Exception Location Waiver for Rule 318A.a. and 318A.c. is located in the attached Surface Use Agreement on page 2, section 6.

This application is in a Comprehensive Drilling Plan \_\_\_\_\_ No \_\_\_\_\_ CDP #: \_\_\_\_\_

Location ID: 449244

Is this application being submitted with an Oil and Gas Location Assessment application? \_\_\_\_\_ No \_\_\_\_\_

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: Andrea Gross

Title: Permit Agent Date: 10/12/2020 Email: agross@upstreampm.com

Operator must have a valid water right or permit allowing for industrial use or purchased water from a seller that has a valid water right or permit allowing for industrial use, otherwise an application for a change in type of use is required under Colorado law. Operator must also use the water in the location set forth in the water right decree or well permit, otherwise an application for a change in place of use is required under Colorado law. Section 37-92-103(5), C.R.S. (2011).

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules, applicable orders, and SB 19-181 and is hereby approved.

COGCC Approved:  Director of COGCC Date: 12/28/2020

Expiration Date: 12/27/2022

**API NUMBER**

05 123 45934 00

## Conditions Of Approval

**All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.**

<u>COA Type</u>	<u>Description</u>
Drilling/Completion Operations	Per COGCC Order 1-232, Bradenhead tests shall be performed according to the following schedule and Form 17 submitted within 10 days of each test: 1) Within 60 days of rig release, prior to stimulation. If any pressure greater than 200 psi, must contact COGCC engineer prior to stimulation. 2) If a delayed completion, 6 months after rig release and prior to stimulation. If any pressure greater than 200 psi, must contact COGCC engineer prior to stimulation. 3) A post-production test within 60 days after first sales, as reported on the Form 10, Certificate of Clearance.
Drilling/Completion Operations	Operator acknowledges the proximity of the listed non-operated wells. Operator assures that this offset list will be remediated per the DJ Basin Horizontal Offset Policy (option 3). Operator will submit a Form 42 ("OFFSET MITIGATION COMPLETED") stating what appropriate mitigation occurred and that it has been completed, prior to the hydraulic stimulation of these wells. API#123-10319, GLEN YOUNG 1 API#123-10449, GLEN YOUNG 2 API#123-10181, CHAMPLIN 365 AMOCO UNIT A 2 API#123-19677, HSR-CHERRY KNOLLS 9-33 API#123-12937, JORDAN 34-9 API#123-14809, JORDAN-LOUSTAUNAU 34-10
Drilling/Completion Operations	Operator acknowledges the proximity of the non-operated listed wells. Operator agrees to: provide mitigation option 1 or 2 (per the DJ Basin Horizontal Offset Policy) to mitigate the situation, ensure all applicable documentation is submitted based on the selected mitigation option chosen, and submit a Form 42 ("OFFSET MITIGATION COMPLETED") stating that appropriate mitigation occurred and that it has been completed, prior to the hydraulic stimulation of these wells. API#123-10497, STRAWDER 1 API#123-10540, NECKIEN 1 API#123-12567, JORDAN 34-3
Drilling/Completion Operations	1) Submit Form 42 electronically to COGCC 48 hours prior to MIRU (spud notice) for the first well activity with a rig on the pad and provide 48 hour spud notice via Form 42 for all subsequent wells drilled on the pad. 2) Comply with Rule 317.j. and provide cement coverage from TD to a minimum of 500' above Niobrara. Verify coverage with cement bond log. 3) Oil-based drilling fluid is to be used only after all fresh water aquifers are covered.
Drilling/Completion Operations	In a comment on the Form 5A submit tab, operator will provide the following information for any other wells belonging to another operator within 150' of the current as-drilled wellbore: well name and API number, the depth of the perforation in this well nearest to the treated interval of the offset well, and the distance between the wells at that depth. Operator will provide the certification that they are in compliance with 317.s
Interim Reclamation	Operator shall comply with Notice to Operators: Interim Reclamation Procedures for Delayed Operation (dated January 5, 2017).
Interim Reclamation	If conductors are preset, Operator shall comply with Notice to Operators: Procedures for Preset Conductors (dated September 1, 2016, revised October 6, 2016).

## Best Management Practices

<u>No</u>	<u>BMP/COA Type</u>	<u>Description</u>
1	Drilling/Completion Operations	Logging: The Judy 3-4, API No. 05-123-50294, well drilled on the pad was logged with an open-hole Resistivity Log and Gamma Ray Log from the kick-off point into the surface casing. All wells on the pad will have a cement bond log with gamma-ray run on production casing (or on intermediate casing if production liner is run) into the surface casing. The horizontal portion of every well will be logged with a measured-while-drilling gamma-ray log. The Form 5, Completion Report, for each well on the pad will list all logs run and have those logs attached. The Form 5 for a well without open-hole logs shall clearly state "No open-hole logs were run. The Judy 3-4, API No. 05-123-50294, is the well in which open-hole logs were run.
2	Drilling/Completion Operations	Anti-collision: Operator will perform an anti-collision evaluation of all active (producing, shut in, or temporarily abandoned) offset wellbores that have the potential of being within 150 feet of a proposed well prior to drilling operations for the proposed well. Notice shall be given to all offset operators prior to drilling.
3	Drilling/Completion Operations	Bradenhead Monitoring: Operator acknowledges and will comply with COGCC Policy for Braden-head Monitoring during Hydraulic Fracturing Treatments in the Greater Wattenberg Area dated May 29, 2012.

Total: 3 comment(s)

## Applicable Policies and Notices to Operators

Notice Concerning Operating Requirements for Wildlife Protection.  
[http://cogcc.state.co.us/documents/reg/Policies/Wildlife\\_Notice.pdf](http://cogcc.state.co.us/documents/reg/Policies/Wildlife_Notice.pdf)

Policy for Bradenhead Monitoring During Hydraulic Fracturing Treatments in the Greater Wattenberg Area.  
<http://cogcc.state.co.us/documents/reg/Policies/PolicyGwaBradenheadMonitoringFinal.pdf>

## Attachment List

<u>Att Doc Num</u>	<u>Name</u>
402286134	FORM 2 RESUBMITTED
402485115	FORM 2 REJECTED
402508774	OffsetWellEvaluations Data
402508782	DEVIATED DRILLING PLAN
402508786	WELL LOCATION PLAT
402508789	SURFACE AGRMT/SURETY
402508927	DIRECTIONAL DATA
402523072	EXCEPTION LOC REQUEST
402561523	OFFSET WELL EVALUATION

Total Attach: 9 Files

## General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Permit	Final Review Completed.	12/03/2020
Permit	COGCC conducted the technical review for the related Oil and Gas Location Assessment permit, Form 2A document #401960745 under the statutory authority provided through SB 19-181, including the Objective Criteria. The Director approved the Form 2A on 7/23/2019, amending Location ID #449244 subject to conditions included in the permit. The well proposed by this related Form 2 was contemplated during COGCC's review of the Form 2A. The Objective Criteria Review Memo (Doc# 2316560) can be found in the document file for this Location.	12/01/2020
Permit	•Permitting review complete and task passed.	12/01/2020

Permit	<ul style="list-style-type: none"> <li>•COGCC Staff has added the approved WOGLA permit number per the Weld County website.</li> <li>•Passed Completeness.</li> </ul>	11/10/2020
Permit	<p>Returned to Draft:</p> <ul style="list-style-type: none"> <li>•Add GPS quality on Well Location Tab.</li> <li>•Update doc#s on the exception location request.</li> <li>•Logging BMP references the incorrect well that was logged.</li> </ul>	10/30/2020
Permit	•Returned to draft at Operator's request.	10/12/2020
Permit (Rejected)	<p>This application has been reviewed by COGCC staff and cannot be approved based on the information submitted; therefore, the COGCC is rejecting this application consistent with the Rejection Process – Form 2 and 2A (May 21, 2019) posted in the Form 2 and Form 2A Instructions section of our website. In compliance with § 24-65.1-108(1), C.R.S., the COGCC is returning this application to the applicant to remedy the deficiencies. The applicant may resubmit this application for COGCC review; upon determination of completeness for any resubmitted application, the COGCC will have 60 days in which to approve, deny, or request all additional information necessary to complete the regulatory review.</p> <p>In addition to all standard required information and attachments, the COGCC hereby confirms the following information is necessary prior to determination of completeness:</p> <p>1.Spacing and Formations Tab: Distance from completed portion of proposed wellbore to nearest completed portion of the offset wellbore permitted or completed in the same formation is incorrect. Provide an updated distance and correct "offset wellbore" name on the Submit tab.</p>	09/09/2020
Permit	IN PROCESS – received requested information from Operator on 7/21/2020; COGCC review will resume and be conducted within 60 days (by 9/19/2020).	08/24/2020
Permit	<p>ON HOLD: This application has been reviewed by COGCC staff and cannot be approved based on the information submitted; therefore, the COGCC is placing this form ON HOLD until additional information is received from the applicant.</p> <p>In compliance with § 24-65.1-108(1), C.R.S., the COGCC is providing this written request for all additional information necessary for the COGCC to respond to this application. The applicant may provide all requested additional information to COGCC via email. Upon receipt of all requested information, the COGCC will have 60 days in which to approve, deny, or request all additional information necessary to complete the regulatory review. If the applicant no longer requires this application be approved, the applicant may request to withdraw the application.</p> <p>In addition to all standard required information and attachments, the COGCC hereby confirms the following information is necessary for review:</p> <p>1. Provide signed stimulation setback consents for the Buford 33-4-4L (Doc#402286120), Buford 33-3-1L (Doc#402286133), Buford 33-3-3L (Doc#402286132), and Buford 33-2-2L (Doc#402286137).</p>	03/30/2020
Permit	COGCC conducted the technical review for the related Oil and Gas Location Assessment permit, Form 2A document #401960745 under the statutory authority provided through SB 19-181, including the Objective Criteria. The Director approved the Form 2A on 7/23/2019, amending Location ID #449244 subject to conditions included in the permit. The well proposed by this related Form 2 was contemplated during COGCC's review of the Form 2A. The Objective Criteria Review Memo (Doc# 2316560) can be found in the document file for this Location.	03/05/2020
Permit	<p>Made the following changes with concurrence from the operator:</p> <ul style="list-style-type: none"> <li>•Corrected the referenced well in the open hole logging BMP from the Buford 33-9-3L, API No. 05-123-45544, to the Judy 3-4, API No. 05-123-50294.</li> <li>•Permitting review complete and ready to pass.</li> </ul>	03/03/2020
Permit	Passed completeness.	01/31/2020
Permit	Returned to draft per operator request.	01/29/2020
Total: 13 comment(s)		