

FORM  
6Rev  
11/20

## State of Colorado

## Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

Document Number:

402560618

Date Received:

## WELL ABANDONMENT REPORT

This form is to be submitted as an Intent to Abandon whenever an abandonment is planned on a borehole. After the abandonment is complete, this form shall again be submitted as a Subsequent Report of the actual work completed. The approved intent shall be valid for six months after the approval date, after that period, a new intent will be required. Attachments required with the Intent to Abandon are wellbore diagrams of the current configuration and the proposed configuration with plugs set.

A Subsequent Report of Abandonment shall indicate the actual work completed. Attachments required with a Subsequent Report are a wellbore diagram showing plugs that were set and casing remaining in the hole, the job summaries from all plugging contractors used, including wireline and cementing (third party verification) and any logs that may have been run during abandonment.

OGCC Operator Number: 100322

Contact Name: Kevin Monaghan

Name of Operator: NOBLE ENERGY INC

Phone: (970) 381-2990

Address: 1001 NOBLE ENERGY WAY

Fax:

City: HOUSTON State: TX Zip: 77070

Email: kevin.monaghan@nblenergy.com

For "Intent" 24 hour notice required,

Name:

Tel:

COGCC contact:

Email:

Type of Well Abandonment Report:

☐ Notice of Intent to Abandon☒ Subsequent Report of Abandonment

API Number 05-123-17623-00

Well Name: ROTHE

Well Number: 2-10

Location: QtrQtr: NWSE

Section: 2

Township: 4N

Range: 64W

Meridian: 6

County: WELD

Federal, Indian or State Lease Number:

Field Name: WATTENBERG

Field Number: 90750

## Only Complete the Following Background Information for Intent to Abandon

Latitude: 40.340064

Longitude: -104.514678

GPS Data: GPS Quality Value: 4.2

Type of GPS Quality Value: PDOP

Date of Measurement: 11/09/2006

Reason for Abandonment:

☐ Dry☐ Production Sub-economic☐ Mechanical Problems☐ Other

Casing to be pulled:

☐ Yes☐ No

Estimated Depth:

Fish in Hole:

☐ Yes☐ No

If yes, explain details below

Wellbore has Uncemented Casing leaks:

☐ Yes☐ No

If yes, explain details below

Details:

## Current and Previously Abandoned Zones

Formation	Perf. Top	Perf. Btm	Abandoned Date	Method of Isolation	Plug Depth
CODELL	6802	6816	01/27/2020	B PLUG CEMENT TOP	6480
NIOBRARA	6532	6689	01/27/2020	B PLUG CEMENT TOP	6480

Total: 2 zone(s)

## Casing History

Casing Type	Size of Hole	Size of Casing	Grade	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top	Status
SURF	12+1/4	8+5/8	J-55	24	0	510	383	510	0	VISU
1ST	7+7/8	3+1/2	M-75	7.7	0	6971	250	6971	5654	CBL

Subsurface hazards include, but are not limited to, the following: overpressured zones, underpressured zones, major geologic faults, salt sections, H2S at concentrations greater than or equal to 100 ppm.

## Plugging Procedure for Intent and Subsequent Report

CIBP #1: Depth 6480 with 2 sacks cmt on top. CIPB #2: Depth 5700 with 2 sacks cmt on top.  
CIBP #3: Depth \_\_\_\_\_ with \_\_\_\_\_ sacks cmt on top. CIPB #4: Depth \_\_\_\_\_ with \_\_\_\_\_ sacks cmt on top.  
CIBP #5: Depth \_\_\_\_\_ with \_\_\_\_\_ sacks cmt on top.

NOTE: Two(2) sacks cement required on all CIBPs.

Set 21 sks cmt from 2500 ft. to 2000 ft. Plug Type: CASING Plug Tagged: ☐  
Set 120 sks cmt from 1013 ft. to 728 ft. Plug Type: STUB PLUG Plug Tagged: ☒  
Set \_\_\_\_\_ sks cmt from \_\_\_\_\_ ft. to \_\_\_\_\_ ft. Plug Type: \_\_\_\_\_ Plug Tagged: ☐  
Set \_\_\_\_\_ sks cmt from \_\_\_\_\_ ft. to \_\_\_\_\_ ft. Plug Type: \_\_\_\_\_ Plug Tagged: ☐  
Set \_\_\_\_\_ sks cmt from \_\_\_\_\_ ft. to \_\_\_\_\_ ft. Plug Type: \_\_\_\_\_ Plug Tagged: ☐

Perforate and squeeze at 2500 ft. with 161 sacks. Leave at least 100 ft. in casing \_\_\_\_\_ CICR Depth  
Perforate and squeeze at \_\_\_\_\_ ft. with \_\_\_\_\_ sacks. Leave at least 100 ft. in casing \_\_\_\_\_ CICR Depth  
Perforate and squeeze at \_\_\_\_\_ ft. with \_\_\_\_\_ sacks. Leave at least 100 ft. in casing \_\_\_\_\_ CICR Depth

(Cast Iron Cement Retainer Depth)

Set 289 sacks half in. half out surface casing from 728 ft. to 0 ft. Plug Tagged: ☐

Set \_\_\_\_\_ sacks at surface

Cut four feet below ground level, weld on plate Above Ground Dry-Hole Marker: ☐ Yes ☐ No

Set \_\_\_\_\_ sacks in rat hole Set \_\_\_\_\_ sacks in mouse hole

## Additional Plugging Information for Subsequent Report Only

Casing Recovered: 1010 ft. of 3+1/2 inch casing Number of Days from Setting Surface Plug to Capping or Sealing the Well: 149  
Surface Plug Setting Date: 02/11/2020 Cut and Cap Date: 07/09/2020

\*Wireline Contractor: Patriot \*Cementing Contractor: Superior

Type of Cement and Additives Used: Class G

Flowline/Pipeline has been abandoned per Rule 1105 ☒ Yes ☐ No

Technical Detail/Comments:

1. Form 42 Submitted 1/23/2020, Doc 402292940
2. well was static
3. Cement to surface
4. all plugs have a min. of 100' of cement
5. Form 44 submitted 9/1/2020, Doc 402479336
7. well was static

Form 17 submitted 3/4/2020, Doc 402332207

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: Julie Webb

Title: Sr. Regulatory Analyst Date: \_\_\_\_\_ Email: Denverregulatory@nblenergy.com

Based on the information provided herein, this Well Abandonment Report (Form 6) complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: \_\_\_\_\_

Date: \_\_\_\_\_

**CONDITIONS OF APPROVAL, IF ANY:**

<u>COA Type</u>	<u>Description</u>
-----------------	--------------------

--	--

**Attachment Check List**

<u>Att Doc Num</u>	<u>Name</u>
--------------------	-------------

402560619	CEMENT JOB SUMMARY
402560620	OPERATIONS SUMMARY
402560621	WELLBORE DIAGRAM
402562885	WIRELINE JOB SUMMARY

Total Attach: 4 Files

**General Comments**

<u>User Group</u>	<u>Comment</u>
-------------------	----------------

Comment Date

		Stamp Upon Approval
--	--	---------------------

Total: 0 comment(s)