


COLORADO OIL AND GAS CONSERVATION COMMISSION  
SUNDRY NOTICES AND REPORTS OF WELLS



OIL &amp; GAS

CONSERVATION COMMISSION



00806898

Locate well correctly

(Indicate nature of data by checking below)

Notice of intention to drill (attach plat) ☒ X  
 Notice of intention to change plans \_\_\_\_\_  
 Notice of date for test of water shut-off \_\_\_\_\_  
 Report on result of test of water shut-off \_\_\_\_\_  
 Notice of intention to re-drill or repair well \_\_\_\_\_  
 Notice of intention to clean out well \_\_\_\_\_  
 Statement of shooting \_\_\_\_\_  
 Statement of perforating \_\_\_\_\_  
 Notice to pull or otherwise alter casing \_\_\_\_\_  
 Notice of intention to abandon well \_\_\_\_\_  
 Report of work done on well since previous report \_\_\_\_\_

			o
		18	

Notice to do work ☒ X  
 Report of work done ☐

Land: Fee and Patented ☒ X  
 State \_\_\_\_\_

Lease No. \_\_\_\_\_

Colorado  
 State

Moffat  
 County

Wildcat  
 Field

1 (Well No.) Emily Nelson (Lease) NE  $\frac{1}{4}$  NE  $\frac{1}{4}$  18 (1/4 Sec.) (Sec.) 8 N (Twp.) 92 W (Range) 6th P.M. (Meridian)

The Well is located 660 Ft. ~~N~~ of Section Line and 660 Ft. ~~E~~ of Section Line. (S) (W)

Will report  
 The elevation above sea level is \_\_\_\_\_ Ft.

Details of Plan of Work: (State names of and expected depths to objective sands. Show sizes, weights, and length of proposed casings; indicate mudding jobs, cementing points, and all other important proposed work.)

## Objective sands:

1. Wasatch - Stringer @ 685'
2. Ft. Union - Stringer @ 1460'
3. Lance - Stringer @ 1870'

## Casing Program:

- 10-3/4" - 32.75# Surface casing @ 100' with 100 sacks  
 5-1/2" - 14# Production casing cemented at completion

Well will be mudded up immediately below surface casing.

A portable mud analyzer will be installed when surface cement drilled out.

All shows will be drill stem tested.

An electrical log will be run at T.D.

T.D.	
DVR	
FJK	
OPS	
HHM	
AH	
JJD	<input checked="" type="checkbox"/>
FILE	

Approved: MAY 20 1955

Date May 18, 1955

United States Smelting  
 Company Refining and Mining Company  
 311 Equitable Building  
 Address Denver 2, Colorado

By Thomas B. Garber  
 Title Petroleum Engineer

Note: This well is jointly owned

by: Halbert & Jennings  
 Moore & Gilmore  
 Dixilyn Oil Company  
 United States Smelting Refining  
 and Mining Company (Operator)

Submit reports of proposed work, for approval, on this form in Duplicate for patented lands and in Triplicate for school and state lands.