


**COLORADO OIL AND GAS CONSERVATION COMMISSION
SUNDRY NOTICES AND REPORTS OF WELLS**



(Indicate nature of data by checking below)

Notice of intention to drill (attach plat) _____
 Notice of intention to change plans _____
 Notice of date for test of water shut-off _____
 Report on result of test of water shut-off _____
 Notice of intention to re-drill or repair well _____
 Notice of intention to clean out well _____
 Statement of shooting _____
 Statement of perforating _____
 Notice to pull or otherwise alter casing _____
 Notice of intention to abandon well _____ ☒
 Report of work done on well since previous report _____ ☒

Locate Well Correctly

			18

Notice to do work ☐
 Report of work done ☒

Land: Fee and Patented ☒
 State ☐

Lease No. _____

Colorado
State

Moffat
County

Wildcat
Field

1 Emily Nelson NE/4 NE/4 18 8N 92W 6th P.M.
 (Well No.) (Lease) (1/4 Sec.) (Sec.) (Twp.) (Range) (Meridian)

The Well is located 660 Ft. ~~(N)~~ of Section Line and 660 Ft. ~~(E)~~ of
 (S) (W)
 Section Line.

The elevation above sea level is 6751 Ft. G.L.

Details of Plan of Work: (State names of and expected depths to objective sands.
 Show sizes, weights, and length of proposed casings; indicate mudding jobs, cementing
 points, and all other important proposed work.)

10-3/4" 32.75# Casing was run and cemented at 101'. Cemented with 75 sx. Cement circulated. WOC a total of 6 days and tested casing with 500# pressure for 30 minutes. Test satisfactory.

Mudded up hole at the shoe of surface casing and drilled to total depth with water base caustic-quebracho mud.

A portable drilling mud analyzer was employed to log the mud from the shoe of surface casing to total depth.

A Schlumberger electric log and microlog were run from T.D. to shoe of surface casing.

The well was plugged with 25 sx of cement in the top of the 10-3/4" surface casing and the location was abandoned June 23, 1955.

AJJ	
DVR	
FJK	
OPS	
HHM	
AH	
JJD	<input checked="" type="checkbox"/>
FILE	

Approved: JUL 5 1955

Date June 28, 1955

Company United States Smelting Refining and Mining Company

Address 311 Equitable Building
Denver 2, Colorado

By Thomas B. Garber

Title Petroleum Engineer

Note: This well is jointly owned by:
 Halbert & Jennings
 Moore & Gilmore
 Dixilyn Oil Company
 United States Smelting Refining
 and Mining Company (Operator)

Submit reports of proposed work, for approval, on this form in Duplicate for patented lands and in Triplicate for school and state lands.