


OIL AND GAS CONSERVATION COMMISSION
OF THE STATE OF COLORADO

PLUGGING RECORD



SSION

INSTRUCTIONS

Within thirty (30) days after the plugging of any well, the owner or operator thereof shall file this form in duplicate for wells on Patented or Federal lands, and in triplicate for wells on State lands, give a detailed account of the manner in which the abandonment or plugging work was carried out, including the nature and quantities of materials used in plugging and the location and extent (by depths) of the plugs of different materials; records of the amount, size and location (by depths) of casings and junk left in the well; and a detailed statement of the volume and weight of mud fluid used.

Operator SINCLAIR OIL & GAS COMPANY Field _____ Wildcat X
Lease Name CLARA STURMAN ESTATE Well No. 1 County MOFFAT
Location NE NE Section 23 Township 8N Range 92W Meridian _____
(Quarter Quarter)
660 feet from North Section line and 660 feet from East Section Line
N or S E or W

TOTAL DEPTH 9650DATE OF PLUGGING 7-1-62

DETAILS OF WORK

6-30-62 - Set 25 sack cement plug 9050-8984', 5485-5419', 1780-1714', 35 sacks 640-564'.

7-1 -62 - Capped with 10 sacks in surface and welded cap on surface pipe.

Left in hole: Heavy drilling mud between plugs. 10 3/4" OD casing set at 608' ground measurement with 455 sacks 50-50 Pozmix and 75 sacks regular cement. Cemented from top to bottom.

No junk left in hole.

8/11/64 - Location checked, P & A OK
Jim & Hawk

AJJ	
DVR	
WRS	
HHM	✓
JAM	✓
FJP	✓
JJD	✓
FILE	

I/we hereby swear (or affirm) that the statements herein made are a full and correct report:

Approved:

Date JUL - 9 1962

Director

Company SINCLAIR OIL & GAS COMPANY Date July 3, 1962Address 601 Denver Club Building Phone No. AMhurst 62461By M.E. Brown Title Div. Chief Clerk
M.E. Brown (Signature)