



COMPANY Public Service Company of Colorado				DATE 3/24/21	
LEASE Roundup #7 (API# 05-087-07065)					
Surface Casing	Weight	Grade	Thread	Depth	
8-5/8"	24#	J-55	ST&C	172'	
Prod Casing	Weight	Grade	Thread	Depth	
5-1/2"	10.5	K-55	LT&C	6484'	
Tubing String	Size	Weight	Grade	Thread	Depth
	2-7/8"	6.5#	J-55	8 Rnd EUE	6398
Second String	Size	Weight	Grade	Thread	Depth
Prepared for:			Perforations: J Sand		
ITEM No#	Length	Description	ID	OD	Depth
1		150 sks of surface cement from 172' - 0'			
2		12-1/4" surface hole.	12.25		
3		8-5/8" Surface Casing @ 172'. Ran 1967	7.972	8.625	172.00
4		Hole size 7-7/8"	7.875		
		Original Cement job.			
		150 Sacks 50/50 Poz Mix cement.			
		Cement top 5550. CBL dated 2/8/1979.			
6		2-3/8" production tubing landed at 6398'			6398.00
7		J Sand Perfs 6422' to 6428'			6422.00
8		5-1/2" Casing landed @ 6484'.			6484.00
PREPARED BY Jeff Schneider			PHONE: 970-381-9588		
OFFICE Fort Morgan, CO			PHONE 970-867-9437		INVOICE #