

FORM
5Rev
12/20

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

402635048

Date Received:

DRILLING COMPLETION REPORT

Per Rule 308A, this form and all required attachments shall be submitted after completing the drilling operations to drill, sidetrack, or deepen a wellbore and after changing the casing and/or cement configuration of a wellbore. If any attempt has been made to test, complete, or produce the well, the operator shall also submit a Form 5A (Completed Interval Report) per Rule 308B. If the well has been plugged, the operator shall also submit a Form 6 (Well Abandonment Report) per Rule 311.

Completion Type ☒ Final completion ☐ Preliminary completion

OGCC Operator Number: 96850

Contact Name: Jeff Kirtland

Name of Operator: TEP ROCKY MOUNTAIN LLC

Phone: (970) 263-2736

Address: PO BOX 370

Fax:

City: PARACHUTE State: CO Zip: 81635

Email: jkirtland@terraep.com

API Number 05-045-24357-00

County: GARFIELD

Well Name: CHEVRON

Well Number: GM 43-19

Location: QtrQtr: SWNW Section: 20 Township: 6S Range: 96W Meridian: 6
FNL/FSL FEL/FWL

Footage at surface: Distance: 1927 feet Direction: FNL Distance: 674 feet Direction: FWL

As Drilled Latitude: 39.511771 As Drilled Longitude: -108.139479

GPS Data: GPS Quality Value: 2.4 Type of GPS Quality Value: PDOP Date of Measurement: 12/02/2020

** If directional footage at Top of Prod. Zone Dist: 2519 feet Direction: FSL Dist: 765 feet Direction: FEL
Sec: 19 Twp: 6S Rng: 96W** If directional footage at Bottom Hole Dist: 2463 feet Direction: FSL Dist: 825 feet Direction: FEL
Sec: 19 Twp: 6S Rng: 96w

Field Name: GRAND VALLEY

Field Number: 31290

Federal, Indian or State Lease Number: COC023794

Spud Date: (when the 1st bit hit the dirt) 12/13/2020 Date TD: 01/18/2021 Date Casing Set or D&A: 01/19/2021

Rig Release Date: 01/29/2021 Per Rule 308A.b.

Well Classification:

☐ Dry ☐ Oil ☒ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☐ Observation

Total Depth MD 7395 TVD** 6824 Plug Back Total Depth MD 7358 TVD** 6787

Elevations GR 5752 KB 5776

Digital Copies of ALL Logs must be Attached



List All Logs Run:

CBL, (DEN/NEU on 045-24351)

FLUID VOLUMES USED IN DRILLING OPERATIONS

(Enter "0" if a type of a fluid was not used. Do not leave blank.)

Total Fluids (bbls): 3231 Fresh Water (bbls): 2000

Recycled or Reused Fluids That Offset the Use of Fresh Water (bbls): 1231

CASING, LINER AND CEMENT

<u>Casing Type</u>	<u>Size of Hole</u>	<u>Size of Casing</u>	<u>Grade</u>	<u>Wt/Ft</u>	<u>Csg/Liner Top</u>	<u>Setting Depth</u>	<u>Sacks Cmt</u>	<u>Cmt Btm</u>	<u>Cmt Top</u>	<u>Status</u>
CONDUCTOR	30	20	X65	78.67	0	84	199	84	0	VISU
SURF	13+1/2	9+5/8	J-55	36	0	1027	268	1027	0	VISU
1ST	8+3/4	4+1/2	P-110	11.6	0	7390	713	7395	3069	CBL

Bradenhead Pressure Action Threshold 308 psig

This threshold is calculated per Rule 308A.b.(2)G. If this well is located in a bradenhead test area (see Rule 207.b) per an Order of the Commission, it may be subject to a different threshold.

Does the casing centralization comply with Rule 317.g? Yes

If "NO", provide details below.

STAGE/TOP OUT/REMEDIAL CEMENT

Cement work date: _____

Method used	String	Cementing tool setting/perf depth	Cement volume	Cement top	Cement bottom

Details of work:

FORMATION LOG INTERVALS AND TEST ZONES

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analysis must be submitted to COGCC)
	Top	Bottom	DST	Cored	
WASATCH G	2,473				
WASATCH	3,254				
OHIO CREEK	4,347				
WILLIAMS FORK	4,648				
CAMEO	6,663				
ROLLINS	7,382				

Operator Comments:

The GPS "as drilled" coordinates and dates of measurement is actual data of the existing well conductor location prior to the spud date.

No MUD logs were run on this well.

Alternative Logging Program: No open hole logs were run. Density Neutron log was run on Chevron GM 31-19 (API 045-24351).

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____

Print Name: Ashley Noonan

Title: Sr. Regulatory Analyst

Date: _____

Email: anoonan@terraep.com

Attachment Check List

Att Doc Num	Document Name	attached ?
<u>Attachment Checklist</u>		
402642978	CMT Summary *	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
	Core Analysis	Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>
402635163	Directional Survey **	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
	DST Analysis	Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>
	Logs	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
	Other	Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>
<u>Other Attachments</u>		
402635135	LAS-CBL 1ST RUN	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
402635136	PDF-CBL 1ST RUN	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
402635164	DIRECTIONAL DATA	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
		Stamp Upon Approval

Total: 0 comment(s)