

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203
Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:
402658726
Receive Date:
04/16/2021
Report taken by:
RICK ALLISON

Site Investigation and Remediation Workplan (Supplemental Form)

This form shall be submitted to the Director for approval prior to the initiation of site investigation and remediation activities. However, this shall not preclude the Operator from taking immediate action to protect public health or safety, the environment, wildlife, or livestock.

This Form 27 describes site conditions as currently understood by the Operator; approval of this Form 27 by COGCC is based on the site conditions accurately described herein; any changes in site conditions identified during or subsequent to the performance of the approved workplan may necessitate additional investigation or remediation which shall be described on a supplemental Form 27.

This Form 27 is intended to provide basic information regarding the proposed site investigation and remediation actions, but the workplan may be more fully described in attached documentation.

Refer to Rules 340, 905, 906, 907, 908, 909, and 910

OPERATOR INFORMATION

| | | |
|--|--|------------------------------|
| Name of Operator: <u>PDC ENERGY INC</u> | Operator No: <u>69175</u> | Phone Numbers |
| Address: <u>1775 SHERMAN STREET - STE 3000</u> | | |
| City: <u>DENVER</u> | State: <u>CO</u> | Zip: <u>80203</u> |
| Contact Person: <u>Karen Olson</u> | Email: <u>COGCCSpillRemediation@pdce.com</u> | |
| | | Phone: <u>(303) 860-5800</u> |
| | | Mobile: <u>()</u> |

PROJECT, PURPOSE & SITE INFORMATION

PROJECT INFORMATION
Remediation Project #: 16654 Initial Form 27 Document #: 402592052

PURPOSE INFORMATION

| | |
|--|--|
| <input type="checkbox"/> 901.e. Sensitive Area Determination | <input type="checkbox"/> 909.c.(5), Rule 910.b.(4): Remediation of impacted ground water |
| <input type="checkbox"/> 909.c.(1), Rule 905: Pit or PW vessel closure | <input type="checkbox"/> Rule 909.e.(2)A.: Notice completion of remediation in accordance with Rule 909.b. |
| <input type="checkbox"/> 909.c.(2), Rule 906: Spill/Release Remediation | <input type="checkbox"/> Rule 909.e.(2)B.: Closure of remediation project |
| <input type="checkbox"/> 909.c.(3), Rule 907.e.: Land treatment of oily waste | <input type="checkbox"/> Rule 906.c.: Director request |
| <input type="checkbox"/> 909.c.(4), Rule 908.g.: Centralized E&P Waste Management Facility closure | <input checked="" type="checkbox"/> Other <u>Tank Battery Closure</u> |

SITE INFORMATION N Multiple Facilities (in accordance with Rule 909.c.)

| | | | |
|---|---|-------------------------------|---|
| Facility Type: <u>LOCATION</u> | Facility ID: <u>311347</u> | API #: _____ | County Name: <u>WELD</u> |
| Facility Name: <u>BOLET-66N65W 17SESW</u> | Latitude: <u>40.481280</u> | Longitude: <u>-104.689170</u> | |
| | ** correct Lat/Long if needed: Latitude: <u>40.480438</u> | Longitude: <u>-104.686076</u> | |
| QtrQtr: <u>SESW</u> | Sec: <u>17</u> | Twp: <u>6N</u> | Range: <u>65W</u> Meridian: <u>6</u> Sensitive Area? <u>Yes</u> |

SITE CONDITIONS

General soil type - USCS Classifications SM Most Sensitive Adjacent Land Use Agriculture/Residential

Is domestic water well within 1/4 mile? Yes Is surface water within 1/4 mile? Yes

Is groundwater less than 20 feet below ground surface? No

Other Potential Receptors within 1/4 mile

A domestic water well is located 374 feet northeast of the tank battery. The Eaton Draw is located 758 feet to the east. Occupied housing is located 283 feet to the southwest. FWS wetlands are located 738 feet to the east (riverine/Eaton Draw) and 984 feet to the northwest (riverine/Greeley No. 2 Canal). The tank battery is located within a HPH habitat (Aquatic Native Species Conservation Waters).

SITE INVESTIGATION PLAN

TYPE OF WASTE:

- | | | |
|--|--|--|
| <input checked="" type="checkbox"/> E&P Waste | <input type="checkbox"/> Other E&P Waste | <input type="checkbox"/> Non-E&P Waste |
| <input checked="" type="checkbox"/> Produced Water | <input type="checkbox"/> Workover Fluids | _____ |
| <input checked="" type="checkbox"/> Oil | <input type="checkbox"/> Tank Bottoms | |
| <input checked="" type="checkbox"/> Condensate | <input type="checkbox"/> Pigging Waste | |
| <input type="checkbox"/> Drilling Fluids | <input type="checkbox"/> Rig Wash | |
| <input type="checkbox"/> Drill Cuttings | <input type="checkbox"/> Spent Filters | |
| | <input type="checkbox"/> Pit Bottoms | |
| | <input type="checkbox"/> Other (as described by EPA) | _____ |

DESCRIPTION OF IMPACT

| Impacted? | Impacted Media | Extent of Impact | How Determined |
|-----------|----------------|----------------------------------|----------------------------|
| No | SOILS | Refer to Tables 1-3 and Figure 1 | Confirmation Soil Sampling |

INITIAL ACTION SUMMARY

Description of initial action or emergency response measures take to abate, investigate, and/or remediate impacts associated with E&P Waste.

In accordance with COGCC Rule 911, this form serves as notification for decommissioning and/or abandonment of the production facility or the off-location wellhead and flowline. The ground and sub-surfaces will be visually inspected for hydrocarbon impacts during equipment decommissioning. Field observations and photo documentation will be recorded in a field inspection form for submittal to the COGCC.

PROPOSED SAMPLING PLAN

Proposed Soil Sampling

Will soil samples be collected as part of this investigation? (Number, type (grab/composite), analyses, and locations of samples):

Grab soil samples will be collected below and/or adjacent to applicable facility equipment, as defined in the Rule 911.a.(4) guidance document (1/4/21), for field screening purposes. Discrete soil samples will be collected for laboratory analysis either in any area of observed hydrocarbon impacts, or in the sample locations designated by the COGCC. GPS data will be collected for all soil sample locations. Soil samples will be submitted for laboratory for analysis of benzene, toluene, ethylbenzene, total xylenes (BTEX), naphthalene, total petroleum hydrocarbons (TPH C6-C36) by EPA Methods 8260B and 8015. Additionally, soil sample(s) will be collected in the area most likely to be impacted by produced water to confirm soil suitability for reclamation. The sample(s) will be submitted for laboratory analysis of electrical conductivity (EC), pH, sodium adsorption ratio (SAR), and boron by saturated paste and hot water soluble extraction methods. Refer to the Proposed Sample Location Map.

Proposed Groundwater Sampling

Will groundwater samples be collected as part of this investigation? (Number, analyses, and locations of samples):

If groundwater is encountered during decommissioning and/or abandonment activities, a grab sample will be collected as soon as practical. If contaminated soil is in contact with groundwater or if free product/hydrocarbon sheen are observed, the release will be reported in accordance with Rule 912.b. Groundwater samples will be submitted for laboratory analysis of BTEX, naphthalene, 1,2,4-trimethylbenzene, and 1,3,5-trimethylbenzene by EPA Method 8260.

Proposed Surface Water Sampling

Will surface water samples be collected as part of this investigation? (Number, analyses, and locations of samples):

Additional Investigative Actions

Additional alternative investigative actions described in attached Site Investigation Plan (summary):

SITE INVESTIGATION REPORT

SAMPLE SUMMARY

Soil

Number of soil samples collected 5
Number of soil samples exceeding 910-1 0
Was the areal and vertical extent of soil contamination delineated? Yes
Approximate areal extent (square feet) 100

NA / ND

-- Highest concentration of TPH (mg/kg) 294
-- Highest concentration of SAR 0.565
BTEX > 910-1 No
Vertical Extent > 910-1 (in feet) 4

Groundwater

Number of groundwater samples collected 0
Was extent of groundwater contaminated delineated? No
Depth to groundwater (below ground surface, in feet)
Number of groundwater monitoring wells installed
Number of groundwater samples exceeding 910-1

Highest concentration of Benzene (µg/l)
Highest concentration of Toluene (µg/l)
Highest concentration of Ethylbenzene (µg/l)
Highest concentration of Xylene (µg/l)
Highest concentration of Methane (mg/l)

Surface Water

0 Number of surface water samples collected
 Number of surface water samples exceeding 910-1
If surface water is impacted, other agency notification may be required.

OTHER INVESTIGATION INFORMATION

Were impacts to adjacent property or offsite impacts identified?

Were background samples collected as part of this site investigation?

Was investigation derived waste (IDW) generated as part of this investigation?

Volume of solid waste (cubic yards) Volume of liquid waste (barrels)

Is further site investigation required?

REMEDIAL ACTION PLAN

Does this Supplemental Form 27A include changes to a previously approved Remedial Action Plan? No _____

SOURCE REMOVAL SUMMARY

Describe how source is to be removed.

No soil was removed from the location during tank battery decommissioning and closure activities.

REMEDIATION SUMMARY

Describe how remediation of existing impacts to soil and groundwater is to be accomplished (i.e. summarize remedial action plan). Provide a brief narrative description including: technical justification, schedule for implementation, estimated time to attain NFA status, plus plans and specifications for the selected remedial action technology.

Soil encountered on site and below production equipment was visually inspected and field screened for volatile organic compound (VOC) concentrations using a photoionization detector (PID). Per the approved proposed soil sampling plan, samples were collected below and/or adjacent to the above ground storage tanks (AST), separator flowline, and dump lines (SEP-FL and SEP-DL). The samples were submitted for laboratory analysis of benzene, toluene, ethylbenzene, total xylenes (BTEX), naphthalene and TPH (C6-C36). In addition, one sample was collected adjacent to the separator dump line and was submitted for laboratory analysis of pH, electrical conductivity (EC), sodium adsorption ration (SAR) and boron. Per the approved Initial Form 27, trimethylbenzene (TMB) analysis was not included for this location as soil sampling was conducted prior to March 4, 2021. Analytical results indicated that organic compounds and soil suitability constituents were in compliance with the applicable COGCC Table 915-1 Protection of Groundwater SSLs in all laboratory sample locations. Analytical results are summarized in Tables 1 and 2, GPS coordinates and field screened VOC concentrations are summarized in Table 3. Field screening and laboratory sample locations are illustrated on Figure 1. The laboratory report is included as Attachment A and the tank battery decommissioning field notes and photo log are included in Attachment B.

Soil Remediation Summary

In Situ

- _____ Bioremediation (or enhanced bioremediation)
- _____ Chemical oxidation
- _____ Air sparge / Soil vapor extraction
- _____ Natural Attenuation
- _____ Other _____

Ex Situ

- _____ Excavate and offsite disposal
- _____ If Yes: Estimated Volume (Cubic Yards) _____
- _____ Name of Licensed Disposal Facility or COGCC Facility ID # _____
- _____ Excavate and onsite remediation
- _____ Land Treatment
- _____ Bioremediation (or enhanced bioremediation)
- _____ Chemical oxidation
- _____ Other _____

Groundwater Remediation Summary

- _____ Bioremediation (or enhanced bioremediation)
- _____ Chemical oxidation
- _____ Air sparge / Soil vapor extraction
- _____ Natural Attenuation
- _____ Other _____

GROUNDWATER MONITORING

If groundwater has been impacted, describe proposed monitoring plan, including # of wells or sample points, monitoring schedule, analytical methods, points of compliance. Attach a groundwater monitoring location diagram.

REMEDATION PROGRESS UPDATE

PERIODIC REPORTING

Frequency: Quarterly Semi-Annually Annually Other Tank Battery Closure Request

Report Type: Groundwater Monitoring Land Treatment Progress Report O&M Report

Other Tank Battery Closure Request

WASTE DISPOSAL INFORMATION

Was E&P waste generated as part of this remediation? No

Describe beneficial use, if any, of E&P Waste derived from this remediation project:

Volume of E&P Waste (solid) in cubic yards _____

E&P waste (solid) description _____

COGCC Disposal Facility ID #, if applicable: _____

Non-COGCC Disposal Facility: _____

Volume of E&P Waste (liquid) in barrels _____

E&P waste (liquid) description _____

COGCC Disposal Facility ID #, if applicable: _____

Non-COGCC Disposal Facility: _____

REMEDATION COMPLETION REPORT

REMEDATION COMPLETION SUMMARY

Is this a Final Closure Request for this Remediation Project? Yes

Do all soils meet Table 910-1 standards? Yes

Does the previous reply indicate consideration of background concentrations? No

Are the only residual soil impacts pH, SAR, or EC at depths greater than 3 feet below ground surface? _____

Does Groundwater meet Table 910-1 standards? Yes

Is additional groundwater monitoring to be conducted? No

RECLAMATION PLAN

RECLAMATION PLANNING

Describe reclamation plan. Discuss existing and new grade recontouring; method and testing of compaction alleviation; and reseeding program, including location of new seed, seed mix and noxious weed prevention. Attach diagram or drawing.

Following tank battery decommissioning activities, the location was backfilled, compacted, and re-contoured to match pre-existing conditions. The location will be reclaimed in accordance with the COGCC 1000 series.

Is the described reclamation complete? Yes

Does the reclamation described herein constitute interim or final reclamation of the Oil and Gas Location?

Interim? Final?

Did the Surface Owner approve the seed mix? _____

If NO, does the seed mix comply with local soil conservation district recommendations? _____

IMPLEMENTATION SCHEDULE

PRIOR DATES

Date of Surface Owner notification/consultation, if required. 12/04/2020

Actual Spill or Release date, if known. _____

SITE INVESTIGATION DATES

Date of Initial Actions described in Site Investigation Plan (start date). 02/08/2021

Date of commencement of Site Investigation. 02/26/2021

Date of completion of Site Investigation. 02/26/2021

REMEDIAL ACTION DATES

Date of commencement of Remediation. 02/26/2021

Date of completion of Remediation. 02/26/2021

SITE RECLAMATION DATES

Date of commencement of Reclamation. _____

Date of completion of Reclamation. _____

OPERATOR COMMENT

Based on the analytical results and field observations recorded during the decommissioning of the Bolet 34-17 tank battery, PDC is submitting a tank battery closure request for this location.

I hereby certify all statements made in this form are to the best of my knowledge true, correct, and complete.

Signed: ` Karen Olson _____

Title: Senior Program Manager _____

Submit Date: ` 04/16/2021 _____

Email: COGCCSpillRemediation@pdce.com _____

Based on the information provided herein, this Application for Site Investigation and Remediation Workplan complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: RICK ALLISON _____

Date: 04/26/2021 _____

Remediation Project Number: 16654 _____

Condition of Approval**COA Type****Description**

| | |
|-------|---|
| | <p>Based on the information presented, it appears that no further action is necessary at this time and the COGCC approves the closure request. However, should future conditions at the site indicate contaminant concentrations in soils exceeding COGCC standards or if groundwater is found to be impacted, then further investigation and/or remediation activities may be required.</p> <p>The surface area disturbed by the remediation activity shall be reclaimed in accordance with the 1000 Series Reclamation Rules.</p> |
| 1 COA | |

Attachment Check List

Upon approval, the approved Form 27 and all listed attachments will be indexed to the Remediation Project file. Only the approved Form 27 will also be indexed to the related Facilities.

Att Doc Num**Name**

| | |
|-----------|--------------------------------|
| 402658726 | FORM 27-SUPPLEMENTAL-SUBMITTED |
| 402658728 | SOIL SAMPLE LOCATION MAP |
| 402658729 | ANALYTICAL RESULTS |
| 402659268 | PHOTO DOCUMENTATION |

Total Attach: 4 Files

General Comments**User Group****Comment****Comment Date**

| | | |
|--|--|---------------------|
| | | Stamp Upon Approval |
|--|--|---------------------|

Total: 0 comment(s)