


OIL AND GAS CONSERVATION COMMISSION
OF THE STATE OF COLORADO

PLUGGING RECORD

INSTRUCTIONS

Within thirty (30) days after the plugging of any well, the owner or operator thereof shall file this form in duplicate for wells on Patented or Federal lands, and in triplicate for wells on State lands, give a detailed account of the manner in which the abandonment or plugging work was carried out, including the nature and quantities of materials used in plugging and the location and extent (by depths) of the plugs of different materials; records of the amount, size and location (by depths) of casings and junk left in the well; and a detailed statement of the volume and weight of mud fluid used.

Operator United States Smelting Refining and Mining Co. Field North Craig Wilcat
Lease Name State of Colorado Well No. 1-34 County Moffat
Location NE/4 SW/4 Section 34 Township 8 N. Range 90 W. Meridian 6 P.M.
(Quarter Quarter)
1850 feet from S Section line and 1950 feet from W Section Line
N or S E or W

TOTAL DEPTH 2924DATE OF PLUGGING June 22, 1958

DETAILS OF WORK

The above well was spudded on June 14, 1958. 315' of 8 5/8" O.D., 24#, J-55, set at 327' K.B. cemented with 200 sacks cement plus 2% cacl. Drilled to 2924'. Ran electric and Micrologs. Total depth of well 2924' in shale. Plugged and abandoned on June 22, 1958 as follows: Hole filled with heavy mud. Plug #1 2550-2315' with 75 sacks cement. Plug #2 330-210' with 40 sacks of cement. Plug #3 10 sacks of cement in top of surf. csg. Welded steel plate on surface casing.

AJJ	
DVR	
WRS	
HHM	
JAM	
FJP	✓
JJD	✓
FILE	

I/we hereby swear (or affirm) that the statements herein made are a full and correct report:

Approved:

Company United States Smelting Refining and Mining Co. Date June 24, 1958Date JUN 27 1958Address 900 Patterson Building Phone No. KE 4-5304

Director

By *George S. Hudson* Title

(Signature)

Manager - Denver Oil Operations