

RECEIVED

JUN - 6 1967

COLO. OIL & GAS CONS. COMM.

OIL AND GAS CONSERVATION COMMISSION
OF THE STATE OF COLORADO

SUNDRY NOTICES AND REPORTS ON WELLS

INSTRUCTIONS

Notice must be given to the Director, and approval obtained in advance of the time when the owner or operator expects to recomplete or abandon a well or to change plans. Within thirty (30) days after recompletion, change of plans, or remedial work, a detailed report of the work done and the results obtained shall be submitted on this form in duplicate for wells on Patented and Federal lands, and in triplicate for wells on State lands. In work that affects only rods, pumps or tubing or other routine work such as, but not limited to, cleaning out to previous total depth, no report is necessary.

Notice of Intention to Recomplete ☐Report of Remedial Work ☐Notice of Intention to Change Plans ☐Report of Recompletion ☐Notice of Intention to Abandon Well ☐Other Well History ☒

(Check appropriate space)

LEASE NAME State 2018

WELL NO. 1

FIELD North Craig

WILDCAT

COUNTY Moffat

LOCATION NW NW

Section 34

Township 8N

Range 90W

Meridian 6th PM

990

feet from N

N or S

Section Line and

990

feet from W

E or W

Section Line

DVR

FJP

HHM

JAM

JJD

(DETAILS OF WORK)

5-10/22-67: Too muddy to M.I. completion rig.

5-23-67: 3100'TD - M.I. Unit, Installed BOP's

5-24-67: Ran tbg & pkr to 1937'. Ran GR Corr. log thru tbg, perf. 2802/05', 2811/16', 2823/28', 2830/33' w/ 2 JSPF, lowered 2" tbg to 2798', pkr @ 2767', ran swab & swbd dry, prep to acidize.

5-25-67: Spotted acid over perfs. Reset pkr @ 2767', tbg @ 2798', acidized perfs w/ 800 gals 15% mud acid & 200 gals alcohol, BDP-2800/500#, tr.press-500/1000#, avg rate 1/3 BPM, dropped 40 ball sealers during treatment, FP-1000#, ISDP-1000# 15 mins 1000#, cmpt 10:30 a.m., S.I. 30 mins, flwd back 11 BLW, TP-1000/0, 6 hrs @ 5 p.m. swbd L&AW, FL-2700', no fluid or gas entering.

5-26-67: Ran swab twice, no fluid or gas, FL-2700', circ. hole w/ S.W., trip out w/ tbg & pkr, prep to frac down csg w/ 30,000 gals sodium chloride wtr.

5-27-67: Fraced w/ 30,000 gals sodium chloride wtr @ 10#/bbl w/ 2800# 10/20 sd, 2000# 8/12 glass beads, BDP-1300#, tr.press-1800# @ 22 BPM, ISI-1200#, 15 mins S.I. 1200#, job cmpt 10:45 a.m.

5-26-67. Well S.I.

5-28-67: Opened well @ 7:30 a.m. w/ 1000# press. Flwd thru 2" for 3½ hrs ending 11 a.m. w/ press 1000# to zero. Well died, tagged top of sd at 2809', sand pmpd 2809 to 2824 in 3 hrs ending 3 p.m. Lost btm of sd pump in hole, S.I. well over nite.

5-29-67: Ran overshot w/ 1½" grapple, no rec. Ran impression block on sd line & found 1½" plunger 2" up. Ran overshot w/ 1½" grapple & rec. fish. S.I. over nite.

5-30-67: Shut down 7 a.m.-12 Noon W.I. equip. In 6 hrs ending 6 p.m. cleaned out sd & beads to 2840'.

5-31-67: McCull. ran perf. log fm 2790/2840', perfs in correct position. Ran 88 jts. 2-3/8" tbg, TS-2788', pkr @ 2757'. In 7 hrs ending 5 p.m. swbd salty wtr, FL-2750'. In 1 hr ending 6 p.m. swbd salty wtr w/ sli show of gas in front of pulls, S.I. over nite. FL @ 7 a.m.

(cont'd)

I/We hereby swear (or affirm) that the statements herein made are a full and correct report.

APPROVED:

Company SUN OIL COMPANY

Date 6-5-67

Date

Address P.O. Box 1798

Phone No. 266-2181

Director

By

(Signature)

Title Office Supervisor

Oper. Dept.

