



Well History

Well Name: Clemons 32-3

API 05123220350000		Surface Legal Location SWNE 3 5N 64W		Field Name Wattenberg		State CO		Well Configuration Type Vertical					
Ground Elevation (ft) 4,630.00		Original KB Elevation (ft) 4,640.00		KB-Ground Distance (ft) 10.00		Spud Date 3/15/2004 00:00		Rig Release Date 4/14/2004 00:00		On Production Date 4/30/2004		Abandon Date	

Daily Operations

Start Date	Summary	End Date
1/25/2021	<p>CREW TRAVEL TO LOCATION AND HELD SAFETY MEETING. RIG UP RIG PUMP AND TANK CHECKED SIWP, SITP 300PSI/SICP 300PSI/ SIBHP 0PSI. OPEN WELL TO WORK TANK AND BLOW DOWN. PUMPED 35BBL KILL ON TBG AND 35BBLS ON CASING. REMOVED 3K WELL HEAD AND INSTALLED 5K WELLHEAD. FUNCTION TEST AND NU BOP. RU WORK FLOOR AND TBG EQUIPMENT. UNLAND TBG LD 4' SUB AND BEGAN TOOH TO DERRIK TALLYING W/103 STANDS LD 11 JTS, TOTAL OF 217 JTS 2 3/8 4.7# J-55 EUE TBG. MIRU RANGER WIRELINE HELD SAFETY MEETING. PU GUAGE RING RIH, RUN WAS GOOD POOH. PU 10K 4 1/2" CIBP RIH CORRELATED W/ LOG SET @ 6768' POOH PU BAILOR RIH DUMP BAIL 2 SXS OF CEMENT ON TOP OF CIBP POOH RDMO RANGER WIRELINE. PU 2 3/8" SN AND NC AND BEGAN TITH FROM DERRIK W/103 STANDS PLACING EOT@ 6497'. RU KELLY HOSE PUMP DOWN CASING TO ESTABLISH CIRCULATION. BROKE CIRCULATION, CIRCULATED UNTIL FLUID WAS CLEAN. PRESSURE TEST CASING TO 1000PSI HELD FOR 10MINS TEST WAS GOOD BLED OFF TO WORK TANK. MIRU PETRO STAR AND PERFORM MIT, MIT WAS GOOD RDMO PETRO STAR UNIT. LD 10 JTS LAND WELL W/196 JTS @6134.34'KB RD TBG EQUIPMENT AND WORK FLOOR. ND BOP NU TOP FLANGE MIRU PICK TESTERS TORQUE AND TEST UNIT. WELLHEAD TEST WAS GOOD RDMO PICK TESTERS UNIT. RD RIG PUMP AND TANK CLEANED UP LOCATION AND MOVED OUT. MOVED EQUIPMENT TO THE GROVES 43-34 MIRU RIG PUMP TANK. CREW TRAVELED TO YARD</p> <p>TBG LANDED AS FOLLOWS 196 JTS 2 3/8 4.7# J-55 EUE 6122.74' 2 3/8 SN 1.1 ' 2 3/8 NC .5 ' KB 10' TOTAL LANDED @ 6134.34'KB 633.66' ABOVE CIBP</p>	1/25/2021

Recompletion, <dtmstart>

Job Category Completion/Workover	Primary Job Type Recompletion	Start Date	End Date	Objective
-------------------------------------	----------------------------------	------------	----------	-----------

Daily Operations

Start Date	Summary	End Date

WBI - Abandon Well PDC, <dtmstart>

Job Category Abandon	Primary Job Type WBI - Abandon Well PDC	Start Date	End Date	Objective
-------------------------	--	------------	----------	-----------

Daily Operations

Start Date	Summary	End Date