





Daily Operations

Well Name: GUTTERSEN D09-22

Daily Operations				
Well Name	API	Job Type	Start Date	Summary
GUTTERSEN D09-22	05-123-27023	CIBP	11/24/2020	11/24/20 CREW AND EQUIP TO LOCATION. HELD SAFETY MTG. SPOTTED IN EQUIP AND RIG. RU SPN 714 AND PUMP AND TANK SDFN
GUTTERSEN D09-22	05-123-27023	CIBP	11/25/2020	11/25/20 CREW TO LOCATION. HELD SAFETY MTG. PRESSURE TEST ALL SURF EQUIP AND BOPS. IWP 150/150# SURF 0#. PUMPED 30/40 BBLs FOR WELL CONTROL. ND WELLHEAD AND NU BOPS AND TEST. RU FLOOR. UNLAND TBG AND POOH. SB 5600' AND LAY DOWN THE REST ON TRAILER. HELD SAFETY MTG. W/ALL ON LOCATION. RU SPN WIRELINE. PICKED UP CIBP AND TIH. SET CIBP AT 6604' KB. POOH PICKED UP BAILER AND TIH. DUMP 2 SKS CMT ON TOP OF CIBP. POOH. RD WIRELINE. SECURE WELL SDFN
GUTTERSEN D09-22	05-123-27023	CIBP	11/30/2020	11/30/20 CREW TO LOCATION. HELD SAFETY MTG. STARTED AND WARMED UP EQUIP. CONDUCT RAMP UP FROM LONG WEEKEND. IWP 0/0# SURF 0#. PICKUP NC AND SN. TIH W/183 JTS 2 3/8 J-55 TBG. LAND TBG. ND BOPS AND NU WELLHEAD W/5K MASTER VALVE. CIRCULATE WELL BORE CLEAN OF OIL AND GAS. PRE TEST FOR MIT. PRESSURED UP TO 500# AND HELD FOR 15 MIN. GOOD TEST. BLED PRESSURE OFF. CLEAN UP LOCATION. RDMOL