

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203
Phone: (303) 894-2100 Fax: (303) 894-2109



OGCC RECEPTION

Receive Date:

04/24/2020

Document Number:

402380467

Produced Water Transfer System

The Flowline Report, Form 44, shall be submitted to register, report realignment, report removal from service, provide pre-abandonment notices, or report abandonment of Off-Location Flowlines, Flowline Systems, Produced Water Transfer Systems, or Crude Oil Transfer Lines or Systems as required by the 1100 Series Rules. The Form 44 shall also be submitted to register, report realignment, or report abandonment of Domestic Taps, and to report Grade 1 Gas Leaks from Flowlines per Rules 610 and

Operator Information

OGCC Operator Number: 10687 Contact Person: Nathan Bennett
Company Name: ELEVATION MIDSTREAM LLC Phone: (720) 354-4616
Address: 370 17TH ST SUITE 5300 Email: nbennett@extractionog.com
City: DENVER State: CO Zip: 80202
Is the Operator a Tier One member of the Utility Notification Center of Colorado (CO811) that participates in Colorado's One Call notification system? Yes ☒ No ☐

PRODUCED WATER TRANSFER SYSTEM

PRODUCED WATER TRANSFER SYSTEM IDENTIFICATION

Facility ID: 465861 Transfer System Name: BADGER WATER SYSTEM Action Type: As Built
Estimated Daily Transfer Volume: 1580 barrels Financial Assurance Rule 712 Facility Surety ID: 20190063

PRODUCED WATER TRANSFER SYSTEM REGISTRATION

Planned Construction Date: 06/13/2018
A representative legal location and associated latitude and longitude near the center of the transfer system.
County: WELD
Qtr Qtr: SWSE Section: 28 Township: 1N Range: 68W Meridian: 6
Latitude: 40.016860 Longitude: -105.004324
GPS Quality Value: 1.6 Type of GPS Quality Value: PDOP Measurement Date: 08/19/2018

PRODUCED WATER TRANSFER LINE AS-BUILT

Date Produced Water Transfer Line was Placed into Service: 10/02/2019

Pipe Description and Testing

Type of Fluid Transferred: Produced Water Pipe Material: Other Standard Dimension Ratio: (for HDPE pipe only)
Max outer Diameter (inches): 9.290 Wall Thickness: 1.660 Weight (lb/ft): 21.20 Grade:
Coating: True Pipe Material: Native Materials Burial Depth: 4
Max Anticipated Operating PSI: 400 Testing Pressure: 750 Test Date: 07/21/2019

Description of Corrosion Protection:

Elevations uses Flexsteel for its produced water lines. The waterline is made of HDP that is wrapped in steel that is again wrapped with HDPE (high-density polyethylene), which creates a protection mechanism both internally and externally of the pipeline.

Description of Integrity Management Program:

Program available upon request.

Description of the construction method used for public by-ways, road crossings, sensitive wildlife habitats, sensitive areas, and natural and manmade watercourses (i.e., open trench, bored and cased, or bored only), if applicable.

Elevation used various construction methods for all public by-ways, road crossings, sensitive wildlife habitats, sensitive areas, and natural and manmade watercourses. The I-25 segment was cased, Northwest Parkway will be cased, and Highway 7 will be cased. Local roads and floodplain segments will not be cased.

OPERATOR COMMENTS AND SUBMITTAL

Comments Replaces previously filed Form 44, Document #402191212.

I hereby certify that the statements made in this form are, to the best of my knowledge, true, correct and complete.

Signed: _____ Date: 05/26/2021 Email: nbennett@extractionog.com

Print Name: Nathan Bennett Title: Regulatory Supervisor

Based on the information provided herein, this Flowline Report complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved:  **Director of COGCC** Date: 5/26/2021

Conditions of Approval

COA Type

Description

Attachment Check List

Att Doc Num

Name

402380467	Form44 Submitted
402380512	AFFIDAVIT OF COMPLETION
402380514	PRESSURE TEST
402701610	PRODUCED WATER TRANSFER SYSTEM GIS SHP

Total Attach: 4 Files

General Comments

User Group

Comment

Comment Date

		Stamp Upon Approval
--	--	------------------------

Total: 0 comment(s)