

## CURRENT CONDITION

Well Name: Fork Unit-Federal #3-22-1-2  
Location: NENW Sec. 22, T1S, R102W  
Field: Dragon Trail (Douglas Creek North per COGCC)  
Spud Date: 11/15/78  
Completed: 12/02/78  
Latitude: 39.952667  
Longitude: -108.833150

API No. 05-103-08283  
County: Rio Blanco  
State: Colorado  
Elev.-KB: 5761'  
Elev.-GL: 5749'  
Prepared by: MJN on 05/26/21  
BLM Lease: COC02741; COC47627D

Surface Casing  
8-5/8" 24# set @ 170  
cmt w/150 sx cmt

Found holes in casing 195-288 feet (5/26/21)

Tubing per 11/17/97 MDC sketch (refer to 1/91)  
59 jts 2-3/8" tubing, anchor, 14 jts 2-3/8"  
tubing, SN, 1 jt 2-3/8" tubing  
EOT est 2,415' ??  
Rods; 2 - 6' 5/8" pony; 95 - 5/8"  
rods (per 12/29/00 ticket)

Castlegate (Moropas) 1082'

Top of Cement Est at 1440'  
200 sx, 5bbl/sx, 0.03086 bbl/ft  
85' OH and 35' inside csg

Mancos B (Emery) 2,250'

Perfs Mancos "B" (12/2/78)  
2317 - 2377' (24 holes)  
Acidize w/2000 gal 15% and 55 balls  
Fraced w/90,930 gal water, 230,000# sand,  
& 110 tons CO2

Float Collar PBSD 2508'

Production Casing  
5-1/2" 15.5# & 14# set @ 2543'  
Cmt w/200sx 50-50 poz

TD 2628'