



40.08757, -108.89479, 5299.7ft, 57°  
05/25/2021 12:31:06 PM



**COLORADO**  
Oil & Gas Conservation  
Commission  
Department of Natural Resources

**Photo 1. Gravel funneled into well.**

**Emerald C-134**

**API: 05-103-05446**

**Inspection: 701500910**





148' Cement plug		10 3/4" Csg set @ 28' from surface
		Plug #4 Class ASTM C Cement 152' to 4' from surface 95-115 Sacks
298' Rock & shale plug		Plug #3 Shale & rock plug 450' to 152'
150' Cement plug		Plug #2 Class ASTM C Cement 600' to 450' 120-125 sacks
888' Rock & shale plug		Plug #1 Shale & rock mix 1488' to 600'
TD @ 1488'		Sludge, rock & mud bridged off (Unable to get to bottom)
		Surface Open hole to 1488' Open hole size 11" to 13"