

FORM
2

Rev
12/20

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203
Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

402721450

(SUBMITTED)

Date Received:

06/17/2021

APPLICATION FOR PERMIT TO:

☒ Drill ☐ Deepen ☐ Re-enter ☐ Recomplete and Operate

Amend ☐

TYPE OF WELL OIL ☐ GAS ☐ COALBED ☒ OTHER: Lateral 1 BP 1

Refill ☐

ZONE TYPE SINGLE ZONE ☒ MULTIPLE ZONES ☐ COMMINGLE ZONES ☐

Sidetrack ☒

Well Name: Harper 01-18 Well Number: 2
Name of Operator: CATAMOUNT ENERGY PARTNERS LLC COGCC Operator Number: 10464
Address: 1001 17TH STREET STE 1160
City: DENVER State: CO Zip: 80202
Contact Name: Nolan Redmond Phone: (720)484-2344 Fax: ()
Email: nredmond@catamountep.com

RECLAMATION FINANCIAL ASSURANCE

Plugging and Abandonment Bond Surety ID: 20160137

WELL LOCATION INFORMATION

Surface Location

QtrQtr: NWSW Sec: 18 Twp: 34N Rng: 6W Meridian: N
Footage at Surface: 1274 Feet FSL 1631 Feet FWL
Latitude: 37.187209 Longitude: -107.544714
GPS Data: GPS Quality Value: 2.1 Type of GPS Quality Value: PDOP Date of Measurement: 09/26/2017
Ground Elevation: 6919
Field Name: IGNACIO BLANCO Field Number: 38300

Well Plan: is ☐ Directional ☒ Horizontal (highly deviated) ☐ Vertical

If Well plan is Directional or Horizontal attach Deviated Drilling Plan and Directional Data.

Subsurface Locations

Top of Productive Zone (TPZ)

Sec: 18 Twp: 34N Rng: 6W Footage at TPZ: 1559 FSL 1601 FWL
Measured Depth of TPZ: 2992 True Vertical Depth of TPZ: 2728 FNL/FSL FEL/FWL

Base of Productive Zone (BPZ)

Sec: 18 Twp: 34N Rng: 6W Footage at BPZ: 1964 FSL 710 FEL
Measured Depth of BPZ: 2709 True Vertical Depth of BPZ: 2800 FNL/FSL FEL/FWL

Bottom Hole Location (BHL)

Sec: 18 Twp: 34N Rng: 6W Footage at BHL: 1964 FSL 710 FEL
FNL/FSL FEL/FWL

LOCAL GOVERNMENT PERMITTING INFORMATION

County: LA PLATA

Municipality: N/A

Is the Surface Location of this Well in an area designated as one of State interest and subject to the requirements of § 24-65.1-108 C.R.S.? No

Per § 34-60-106(1)(f)(I)(A) C.R.S., the following questions pertain to the Relevant Local Government approval of the siting of the proposed Oil and Gas Location.

SB 19-181 provides that when "applying for a permit to drill," operators must include proof that they sought a local government siting permit and the disposition of that permit application, or that the local government does not have siting regulations. § 34-60-106(1)(f)(I)(A) C.R.S.

Does the Relevant Local Government regulate the siting of Oil and Gas Locations, with respect to this Location? ☒ Yes ☐ No

☒ If yes, in checking this box, I hereby certify that an application has been filed with the local government with jurisdiction to approve the siting of the proposed oil and gas location.

The disposition of the application filed with the Relevant Local Government is: Approved Date of Final Disposition: 12/09/2020

Comments: The La Plata County Permit was approved 12/9/2020 under Project #2020-0270.

SURFACE AND MINERAL OWNERSHIP AT WELL'S OIL & GAS LOCATION

Surface Owner of the land at this Well's Oil and Gas Location: ☒ Fee ☐ State ☐ Federal ☐ Indian

Mineral Owner beneath this Well's Oil and Gas Location: ☒ Fee ☐ State ☐ Federal ☐ Indian

Surface Owner Protection Financial Assurance (if applicable): _____ Surety ID Number (if applicable): _____

MINERALS DEVELOPED BY WELL

The ownership of all the minerals that will be developed by this Well is (check all that apply):

- ☒ Fee
☐ State
☒ Federal
☐ Indian
☐ N/A

LEASE INFORMATION

Using standard QtrQtr, Section, Township, Range format describe one entire mineral lease as follows:

* If this Well is within a unit, describe a lease that will be developed by the Well.

* If this Well is not subject to a unit, describe the lease that will be produced by the Well.

(Attach a Lease Map or Lease Description or Lease if necessary.)

Sec 18U: Lots 3, 4, E/2 SW/4, 34N-6W, N.M.P.M. and
Sec 13U: SE/4, 34N-7W, N.M.P.M. all South of the Ute Line

Total Acres in Described Lease: 315 Described Mineral Lease is: ☒ Fee ☐ State ☐ Federal ☐ Indian

Federal or State Lease # _____

SAFETY SETBACK INFORMATION

Distance from Well to nearest:

Building: 272 Feet
Building Unit: 808 Feet
Public Road: 1623 Feet
Above Ground Utility: 202 Feet

INSTRUCTIONS:

- Specify all distances per Rule 308.b.(1).
- Enter 5280 for distance greater than 1 mile.
- Building - nearest building of any type. If nearest Building is a Building Unit, enter same distance for both.
- Building Unit – as defined in 100 Series Rules.

Railroad: 5280 Feet
Property Line: 914 Feet

OBJECTIVE FORMATIONS

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
FRUITLAND COAL	FRLDC	112-215	320	S/2

Federal or State Unit Name (if appl): Unit Number:

SUBSURFACE MINERAL SETBACKS

Enter 5280 for distance greater than 1 mile.

Is this Well within a unit? Yes

If YES:

Enter the minimum distance from the Completed Zone of this Well to the Unit Boundary: 710 Feet

Enter the minimum distance from the Completed Zone of this Well to the Completed Zone of an offset Well within the same unit permitted or completed in the same formation: 330 Feet

If NO:

Enter the minimum distance from the Completed Zone of this Well to the Lease Line of the described lease: Feet

Enter the minimum distance from the Completed Zone of this Well to the Completed Zone of an offset Well producing from the same lease and permitted or completed in the same formation: Feet

Exception Location

☐ If this Well requires the approval of a Rule 401.c Exception Location, enter the Rule or spacing order number and attach the Exception Location Request and Waivers.

SPACING & FORMATIONS COMMENTS

DRILLING PROGRAM

Proposed Total Measured Depth: 5709 Feet TVD at Proposed Total Measured Depth 2800 Feet

Distance from the proposed wellbore to nearest existing or proposed wellbore belonging to another operator, including plugged wells:

Enter distance if less than or equal to 1,500 feet: Feet ☒ No well belonging to another operator within 1,500 feet

Will a closed-loop drilling system be used? Yes

Is H₂S gas reasonably expected to be encountered during drilling operations at concentrations greater than or equal to 100 ppm? No If yes, attach an H₂S Drilling Plan unless a plan was already submitted with the Form 2A per Rule 304.c.(10).

Will there be hydraulic fracture treatment at a depth less than 2,000 feet in this well? No

Will salt sections be encountered during drilling? No

Will salt based (>15,000 ppm Cl) drilling fluids be used? Yes

Will oil based drilling fluids be used? No

BOP Equipment Type: ☒ Annular Preventor ☒ Double Ram ☐ Rotating Head ☐ None

Beneficial reuse or land application plan submitted?

Reuse Facility ID: or Document Number:

CASING PROGRAM

Casing Type	Size of Hole	Size of Casing	Grade	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
SURF	12+1/4	8+5/8	J55	24	0	350	246	350	0
1ST	7+7/8	5+1/2	J55	15.5	0	3705	395	3705	0
1ST LINER	4+3/4	2+7/8	J55	6.5	3530	5704			

☒ Conductor Casing is NOT planned

POTENTIAL FLOW AND CONFINING FORMATIONS

Zone Type	Formation /Hazard	Top M.D.	Top T.V.D.	Bottom M.D.	Bottom T.V.D.	TDS (mg/L)	Data Source	Comment
Groundwater	Quaternary	0	0	100	100	0-500	Groundwater Atlas	Water Well Sample.
Groundwater	Upper Animas	100	100	1720	1628	0-500	Groundwater Sample	Water Well Sample.
Groundwater	Animas Modermott	1720	1628	2129	2031	501-1000	USGS	W.R.I 95-4190
Confining Layer	Upper Kirtland Shale	2129	2031	2251	2152	1001-10000	USGS	W.R.I 95-4190
Hydrocarbon	Farmington SS	2251	2152	2715	2565	1001-10000	USGS	W.R.I 95-4190
Confining Layer	Lower Kirtland Shale	2715	2565	2992	2728	1001-10000	USGS	W.R.I 95-4190
Hydrocarbon	Fruitland	2992	2728	3482	2935	>10000	Produced Water Sample	
Hydrocarbon	Pictured Cliffs	3482	2935	3705	3029	>10000	Produced Water Sample	

OPERATOR COMMENTS AND SUBMITTAL

Comments: This application is for an unplanned sidetrack to replace the Harper 01-18 #2 Lateral 1 API #05-067-10022-0100.

This application is in a Comprehensive Area Plan No

CAP #:

Oil and Gas Development Plan Name

OGDP ID#:

Location ID: 334337

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____

Print Name: Nolan Redmond

Title: Geo/Eng Tech

Date: 6/17/2021

Email: nredmond@catamountep.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules, applicable orders, and SB 19-181 and is hereby approved.

COGCC Approved: _____

Director of COGCC

Date: _____

Expiration Date: _____

API NUMBER

05 067 10022 05

Conditions Of Approval

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

COA Type

Description

--	--

Best Management Practices

No BMP/COA Type

Description

--	--

Attachment List

Att Doc Num

Name

--	--

Total Attach: 0 Files

General Comments

User Group

Comment

Comment Date

		Stamp Upon Approval
--	--	---------------------

Total: 0 comment(s)

Public Comments

No public comments were received on this application during the comment period.

