

CNTY:	<u>Adams</u>	FTG:	<u>2040 FSL and 2040 FEL</u>	IP GAS:	_____
STATE:	<u>CO</u>	Q-Q:	<u>NWSE</u>	IP OIL:	_____
ROTARY SPUD:	<u>13-Jun-90</u>	SEC.:	<u>11</u>	IP WTR:	_____
COMP:	<u>25-Jul-90</u>	TWS:	<u>3S</u>	CUM GAS:	_____
STATUS:	<u>SI</u>	RGE:	<u>65W</u>	CUM OIL:	_____
WBD DATE:	<u>6-May-21</u>	BY:	<u>RJD</u>	CUM WTR:	_____
LAT/LONG:	<u>39.803645, -104.628403</u>			LAST PROD:	<u>Apr-20</u>

WELLBORE DIAGRAM

KBE:	5406.0	'
KB:	10.0	'
GLE:	5396	'

Sep-15 TD (ft): 8300 '
PBSD (ft): 8237 '

12 1/4" hole

8 5/8" 24# Csg @ 231'
w/ 200 sx's to surf

7 7/8" hole

Top Fox Hills @ 1498 '

Howco FO DV Tool @ 1648 '10/17/90 cmt'd w/ 492 sx to surf

CBL DV Tool cmt Btm

Top Sussex @ 5006 '

CALC TOC @ 7500 '

Top Niobrara @	7410'
Top Fort Hays @	7746'
Top Carlile @	7775'
Top Greenhorn @	7854'

Top D Sand @ 8093 '
p Huntsman @ 8142 '

Top J Sand @ 8183 '

EOT @ [8178](#) '

J Sand **8194'-8218'**

Top Skull Creek @ 8229 '

ORIG PBTB @ 8256 '
4 1/2" 11.6# Csg @ 8296 '
Cmtd w/250 sxs
TD @ 8300 '
7 7/8" Hole

CASING HEAD: [Unknown](#)

WELLHEAD: [Unknown](#)

WELLHEAD: CASING RECORD

HOLE (in)	SIZE (in)	WT (lb/ft)	GRADE	TOP (ft)	BTM (ft)	JTS
12 1/4	8 5/8	24		0	231	
7 7/8	4 1/2	11.6	J-80, J-55 L T	0	8296	Top 400' N-80
DV Tool				1,648		cmt to surf

TUBING RECORD

COND:

DATE:

[illegible]

ITEM	DESC	SIZE (in)	TALLY (ft)	JTS
TBG	J-55 4.7# 8 rnd EUE	2 3/8	8176.90	262
SN		2 3/8	1.10	1
KB				
EOT @			8178.00	

PERFORATION RECORD

ZONE	TOP (ft)	BTM (ft)	SPF	DATE SHOT	STATUS	STIM
J Sand	8194	8218	3		SI	1000 GAL 7.5% HCL
ACID & FRAC'D W/37,320 GAL GELLED WATER & 62,100# 20/40 SAND						

WELLWORK HISTORY

56th Ave. & Hudson Rd. N1/4, W1/2