

MARALEX RESOURCES, INC.

Operator # 53255

6/2021

WELL NAME	USA 1-8 MR		
LOCATION	SENE Sec 8 T10S R99W 6 PM		
GPS	39.204487	-108.458599	PDOP 2.4
GPS OPERATOR	M. Nastal	DATE	11/8/2010
FEDERAL LEASE No.	COC13701		
ELEVATION	6460'	KB	12'

FIELD	Bronco Flats		
COUNTY	Mesa		
API #	05-077-08415		
FORMATION	Dakota (DKTA)		
COGCC LOCATION ID	312509		
COGCC FACILITY ID	221813		

CASING

SURFACE

SIZE & WT	13 ³ / ₈ " 48#
SET @	166'
HOLE SIZE	17 ¹ / ₂ "
CEMENT	170 sxs
TOC @ surface	

INTERMEDIATE

SIZE & WT	8 ⁵ / ₈ " 24#
SET @	1064'
HOLE SIZE	12 ¹ / ₄ "
CEMENT	400 sxs
Calc TOC @ surface	

PRODUCTION

SIZE & WT	4 ¹ / ₂ " 10.5#
SET @	6546'
HOLE SIZE	7 ⁷ / ₈ "
CEMENT	1st stage: 250 sxs Calc TOC
at 5328'	2nd stage: 60 sxs Calc TOC
at 1635'	

STAGE TOOL

@ 1927'

PERFORATIONS

6117.5'-6128.5'	16 shots
6245'-6467'	12 shots

FORMATION TOPS

Cozzette	1590'
Corcoran	1814'
Dakota	6074'

