

MARALEX RESOURCES, INC.

Operator # 53255

P & A Wellbore

WELL NAME	Dry Fork Federal (USA) 1-29		
LOCATION	SWNE Sec 29 T7S R99W 6 PM		
GPS	39.417579	-108.462673	PDOP 3.5
GPS OPERATOR	M. Nastal	DATE	11/24/2010
FEDERAL LEASE No.	COC12828B		
ELEVATION	6505'	KB	11'

FIELD	Dry Fork		
COUNTY	Garfield		
API #	05-045-06218		
FORMATION	Dakota		
COGCC LOCATION ID	322423		
COGCC FACILITY ID	210462		

CASING

SURFACE

SIZE & WT	9 ⁵ / ₈ " 36#
SET @	215'
HOLE SIZE	12 ¹ / ₄ "
CEMENT	120 sxs w/ 2% CaCl ₂
TOC @ surface	(calculated)

PRODUCTION

SIZE & WT	5 ¹ / ₂ " 15.5 & 17 #
SET @	9264'
HOLE SIZE	8 ³ / ₄ "
CEMENT	450 sxs
TOC @	7215' (Calculated)

BRIDGE PLUGS @ 8558' & 8795'

PERFORATIONS

8517'-8531'	8 holes
8693'-8705'	13 holes BP @8558'
8836'-8856'	32 holes BP @ 8795'

FORMATION TOPS

Rollins	3686'
Cozette-Corcoran	3930'
Dakota	8500'
Morrison	8710'
Entrada	9250'

Steel plate w/ weep hole and well info inscribed

