

Equity Oil & Gas
Emerald #C-134
API # 103-05446

3' of Cement		10 3/4" Csg set @ 28' from surface
147' Cement plug		Plug #4 Class ASTM C Cement 147' to 4' from surface 92 Sacks
271' Rock & shale plug		Plug #3 Shale & rock plug 418' to 147'
155' Cement plug		Plug #2 Class ASTM C Cement 573' to 418' 102 sacks
915' Rock & shale plug		Plug #1 Shale & rock mix 1488' to 573'
TD @ 1488'		Sludge, rock & mud bridged off (Unable to get to bottom)
		Surface Open hole to 1488' Open hole size 11" to 13" Originally Drilled to 3425'