

**FORM
INSP**Rev
X/20**State of Colorado
Oil and Gas Conservation Commission**1120 Lincoln Street, Suite 801, Denver, Colorado 80203
Phone: (303) 894-2100 Fax: (303) 894-2109

Inspection Date:

07/15/2021

Submitted Date:

07/19/2021

Document Number:

700300204**FIELD INSPECTION FORM**Loc ID 32222 Inspector Name: LABOWSKIE, STEVE On-Site Inspection ☐ 2A Doc Num: _____**Operator Information:**OGCC Operator Number: 10664Name of Operator: HARWOOD FUNERAL SERVICESAddress: 225 E MAIN STREETCity: FLORENCE State: CO Zip: 81226**Status Summary:**

- ☐ THIS IS A FOLLOW UP INSPECTION
- ☐ FOLLOW UP INSPECTION REQUIRED
- ☐ NO FOLLOW UP INSPECTION REQUIRED

Findings:11 Number of Comments4 Number of Corrective Actions☒ Corrective Action Response Requested**ANY CORRECTIVE ACTION(S) FROM
PREVIOUS INSPECTIONS THAT HAVE NOT
BEEN ADDRESSED ARE STILL APPLICABLE****Contact Information:**

Contact Name	Phone	Email	Comment
MacLaren, Joe		joe.maclaren@state.co.us	
Beardslee, Tom		tom.beardslee@state.co.us	
Burn, Diana		diana.burn@state.co.us	
Ferrin, Jeremy		jeremy.ferrin@state.co.us	
Harwood, Lloyd	719-458-1552/ 719-334-2445	harwoodfuneral@yahoo.com	Canyon City Office

Inspected Facilities:

Facility ID	Type	Status	Status Date	Well Class	API Num	Facility Name	Insp Status
210030	WELL	DM	05/12/1996	GW	043-06108	PRIDE OF WEST 1	SI

General Comment:

Inspection to follow up on emails and phone calls where COGCC required operator of record (Harwood Funeral Services) to stop supplying gas from well until ownership transfer could be completed, current surface owner (David Fyler) was copied on email and told verbally on phone to stop using gas, which was documented being used to heat two separate residences. No Form 44 found for domestic tap registration or gas delivery points found in digital well file. A different surface owner had been using well after purchasing property from Harwood Funeral Services without ever becoming an operator or obtaining ownership transfer of well.

In attendance were Mr. Fyler, representative from PUC Janie and representatives from Atmos. Neither Harwood Funeral Services or surface owner had stopped supplying gas to residences. COGCC explained that once ownership transferred occurred the flowlines would be required to pass a pressure test, be odorized, regulated, marked and registered in addition to requirements that PUC or the safety certificate holder for the area (Atmos) may require for operating a gas distribution system.

After verbally being compliance issues from all 3 representatives that a new user would need comply, Mr. Fyler stated he was no longer interested in obtaining ownership of well and started making arrangements to have gas delivery run to his houses. At this point, due to lack of representation by Harwood, COGCC Inspection Supervisor closed valves on well and flowline and due to concerns for public safety they shall remain closed until well is plugged or ownership can be transferred and compliance with COGCC 1100 series rules are met. Operator of record is required to disconnect domestic flowlines, lock out and tag out well, correct well sign information including 24 hour operator contact number, plug well, abandon flowlines and reclaim location per Rule 211.a and others.

LocationOverall Good: ☐

Signs/Marker:			
Type	WELLHEAD		
Comment:	incorrect information		
Corrective Action:	correct well sign information to reflect current operator of record	Date:	

Emergency Contact Number:			
Comment:	sign has information for new surface owner, not operator of record		
Corrective Action:		Date:	

Overall Good: ☐

Spills:				
Type	Area	Volume		

In Containment: No

Comment: ☐ Multiple Spills and Releases?

Fencing/:			
Type	WELLHEAD		
Comment:			
Corrective Action:		Date:	

Equipment:			corrective date
Type: Ancillary equipment	#		
Comment:	casing head/wellhead		
Corrective Action:		Date:	
Type: Flow Line	# 3		
Comment:	(1) 3/4' line goi g below grade supplying 2 1 1/2 steel domestic lines going to to separate residential building units. (1) above grade 2" line going to garage. Lines are not odorized, marked or regulated at delivery point Lines werde active at time of inspection until unauthorized use of gas by third party surface owner (David Fyler) was terminated due to conerns for public safety and welfare		
Corrective Action:	Disconnect and anbonned lines		Date:
Type: Flow Line	# 2		
Comment:	(2) domestic lines with exposed risers at residential delivery points, not abandoned. 1" line at east residence has clam shell type cap. 1 1/2" line at west residence is open and not not capped		
Corrective Action:	abandon unused flowlines		Date:
Type: Other	#		
Comment:	vertical dryer/separator		
Corrective Action:		Date:	

Venting:			
Yes/No	NO		
Comment:			
Corrective Action:		Date:	

Flaring:			
Type			
Comment:			
Corrective Action:		Date:	

--	--	--	--

Inspected FacilitiesFacility ID: 210030 Type: WELL API Number: 043-06108 Status: DM Insp. Status: SI**Producing Well**Comment: well was producing at time of inspection. Inspection Supervisor shut well in after determining it was being used without approval and significant compliance issues that could impact public health, safety and welfare.

Corrective Action:

Date:

Idle WellPurpose: ☒ Shut In ☐ Temporarily Abandoned Reminder: _____Comment: well no longer used with no willing and authorized userCorrective Action: plug and abnadon well per Rule211.a

Date: _____

Optical Gas Imaging Survey

Survey Type: _____

Current Operations: ☐ Production ☐ Workover ☐ Flowback ☐ Referred to APCD

GPS(entrance of location): Lat: _____ Long: _____

Wind: Calm Speed: _____ (mph) Direction From: _____ Weather: _____ Temperature: (F)

Assisting Staff: _____ Camera #: _____

☐ Visible Smoke ☐ Referred to CDPHE

Times Surveyed

Equipment Surveyed

Time Survey Start	AM/PM	Time Survey End	AM/PM
9:20	AM	9:30	AM

Equipment
Flowline
Wellhead(s)

Comment: conducted survey after shutting valves on well and flowline, no leaks detected with FLIR on high sensitivity

Corrective Action: _____ Date: _____

Attached DocumentsYou can go to COGCC Images (<https://cogcc.state.co.us/weblink/>) and search by document number:

Document Num	Description	URL
402752721	INSPECTION SUBMITTED	http://ogccweblink.state.co.us/DownloadDocumentPDF.aspx?DocumentId=5482949
700300211	1 active and 1 ot in use flowlines at west house	http://ogccweblink.state.co.us/DownloadDocumentPDF.aspx?DocumentId=5482942
700300212	1 active and 1 not in use flowline at east house	http://ogccweblink.state.co.us/DownloadDocumentPDF.aspx?DocumentId=5482943