

FORM  
2

Rev  
12/20

State of Colorado  
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203  
Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

402759449

(SUBMITTED)

Date Received:

07/26/2021

APPLICATION FOR PERMIT TO:

☒ Drill ☐ Deepen ☐ Re-enter ☐ Recomplete and Operate

Amend ☐

TYPE OF WELL OIL ☒ GAS ☐ COALBED ☐ OTHER: \_\_\_\_\_

Refile ☒

ZONE TYPE SINGLE ZONE ☒ MULTIPLE ZONES ☐ COMMINGLE ZONES ☐

Sidetrack ☐

Well Name: Schneider 1414 Well Number: 06H  
Name of Operator: VERDAD RESOURCES LLC COGCC Operator Number: 10651  
Address: 1125 17TH STREET SUITE 550  
City: DENVER State: CO Zip: 80202  
Contact Name: Allison Schieber Phone: (720)845-6909 Fax: ( )  
Email: regulatory@verdadresources.com

RECLAMATION FINANCIAL ASSURANCE

Plugging and Abandonment Bond Surety ID: 20170009

WELL LOCATION INFORMATION

Surface Location

QtrQtr: NENW Sec: 14 Twp: 8N Rng: 60W Meridian: 6  
Footage at Surface: 241 Feet FNL/FSL 1413 Feet FEL/FWL FWL  
Latitude: 40.669103 Longitude: -104.062264  
GPS Data: GPS Quality Value: 1.5 Type of GPS Quality Value: PDOP Date of Measurement: 05/24/2018  
Ground Elevation: 4943  
Field Name: WILDCAT Field Number: 99999

Well Plan: is ☐ Directional ☒ Horizontal (highly deviated) ☐ Vertical

If Well plan is Directional or Horizontal attach Deviated Drilling Plan and Directional Data.

Subsurface Locations

Top of Productive Zone (TPZ)

Sec: 14 Twp: 8N Rng: 60W Footage at TPZ: 300 FNL 330 FEL  
Measured Depth of TPZ: 7593 True Vertical Depth of TPZ: 6100 FNL/FSL FEL/FWL

Base of Productive Zone (BPZ)

Sec: 14 Twp: 8N Rng: 60W Footage at BPZ: 300 FSL 330 FEL  
Measured Depth of BPZ: 12303 True Vertical Depth of BPZ: 6100 FNL/FSL FEL/FWL

Bottom Hole Location (BHL)

Sec: 14 Twp: 8N Rng: 60W Footage at BHL: 210 FSL 330 FEL  
FNL/FSL FEL/FWL

## LOCAL GOVERNMENT PERMITTING INFORMATION

County: WELD

Municipality: N/A

Is the Surface Location of this Well in an area designated as one of State interest and subject to the requirements of § 24-65.1-108 C.R.S.? Yes

Per § 34-60-106(1)(f)(I)(A) C.R.S., the following questions pertain to the Relevant Local Government approval of the siting of the proposed Oil and Gas Location.

SB 19-181 provides that when "applying for a permit to drill," operators must include proof that they sought a local government siting permit and the disposition of that permit application, or that the local government does not have siting regulations. § 34-60-106(1)(f)(I)(A) C.R.S.

Does the Relevant Local Government regulate the siting of Oil and Gas Locations, with respect to this Location? ☒ Yes ☐ No

☒ If yes, in checking this box, I hereby certify that an application has been filed with the local government with jurisdiction to approve the siting of the proposed oil and gas location.

The disposition of the application filed with the Relevant Local Government is: Approved Date of Final Disposition: 06/21/2019

Comments: WOGLA19-0105

## SURFACE AND MINERAL OWNERSHIP AT WELL'S OIL & GAS LOCATION

Surface Owner of the land at this Well's Oil and Gas Location: ☒ Fee ☐ State ☐ Federal ☐ Indian

Mineral Owner beneath this Well's Oil and Gas Location: ☒ Fee ☐ State ☐ Federal ☐ Indian

Surface Owner Protection Financial Assurance (if applicable): \_\_\_\_\_ Surety ID Number (if applicable): \_\_\_\_\_

### MINERALS DEVELOPED BY WELL

The ownership of all the minerals that will be developed by this Well is (check all that apply):

- ☒ Fee  
☐ State  
☐ Federal  
☐ Indian  
☐ N/A

### LEASE INFORMATION

Using standard QtrQtr, Section, Township, Range format describe one entire mineral lease as follows:

\* If this Well is within a unit, describe a lease that will be developed by the Well.

\* If this Well is not subject to a unit, describe the lease that will be produced by the Well.

(Attach a Lease Map or Lease Description or Lease if necessary.)

W2 SECTION 14 8N 60W 6TH PM: 320 ACRES

Total Acres in Described Lease: 320 Described Mineral Lease is: ☒ Fee ☐ State ☐ Federal ☐ Indian

Federal or State Lease # \_\_\_\_\_

### SAFETY SETBACK INFORMATION

Distance from Well to nearest:

Building: 5280 Feet  
Building Unit: 5280 Feet  
Public Road: 1383 Feet  
Above Ground Utility: 1445 Feet

#### INSTRUCTIONS:

- Specify all distances per Rule 308.b.(1).
- Enter 5280 for distance greater than 1 mile.
- Building - nearest building of any type. If nearest Building is a Building Unit, enter same distance for both.
- Building Unit – as defined in 100 Series Rules.

Railroad: 2834 Feet  
Property Line: 210 Feet

## OBJECTIVE FORMATIONS

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
NIOBRARA	NBRR	535-1097	640	SEC 14:ALL

Federal or State Unit Name (if appl): Unit Number:

## SUBSURFACE MINERAL SETBACKS

Enter 5280 for distance greater than 1 mile.

Is this Well within a unit? Yes

If YES:

Enter the minimum distance from the Completed Zone of this Well to the Unit Boundary: 300 Feet

Enter the minimum distance from the Completed Zone of this Well to the Completed Zone of an offset Well within the same unit permitted or completed in the same formation: 597 Feet

If NO:

Enter the minimum distance from the Completed Zone of this Well to the Lease Line of the described lease: Feet

Enter the minimum distance from the Completed Zone of this Well to the Completed Zone of an offset Well producing from the same lease and permitted or completed in the same formation: Feet

## Exception Location

☐ If this Well requires the approval of a Rule 401.c Exception Location, enter the Rule or spacing order number and attach the Exception Location Request and Waivers.

## SPACING & FORMATIONS COMMENTS

SEC 14 T8N R60W:ALL

## DRILLING PROGRAM

Proposed Total Measured Depth: 12393 Feet TVD at Proposed Total Measured Depth 6100 Feet

Distance from the proposed wellbore to nearest existing or proposed wellbore belonging to another operator, including plugged wells:

Enter distance if less than or equal to 1,500 feet: 151 Feet ☐ No well belonging to another operator within 1,500 feet

Will a closed-loop drilling system be used? Yes

Is H<sub>2</sub>S gas reasonably expected to be encountered during drilling operations at concentrations greater than or equal to 100 ppm? No If yes, attach an H<sub>2</sub>S Drilling Plan unless a plan was already submitted with the Form 2A per Rule 304.c.(10).

Will there be hydraulic fracture treatment at a depth less than 2,000 feet in this well? No

Will salt sections be encountered during drilling? No

Will salt based (>15,000 ppm Cl) drilling fluids be used? No

Will oil based drilling fluids be used? Yes

BOP Equipment Type: ☒ Annular Preventor ☒ Double Ram ☒ Rotating Head ☐ None

Beneficial reuse or land application plan submitted? No

Reuse Facility ID: or Document Number:

**CASING PROGRAM**

Casing Type	Size of Hole	Size of Casing	Grade	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	24	16		65	0	80	70	80	0
SURF	13+1/2	9+5/8		36	0	1800	489	1800	0
1ST	8+1/2	5+1/2		20	0	12393	1630	12393	0

☐ Conductor Casing is NOT planned

**POTENTIAL FLOW AND CONFINING FORMATIONS**

Zone Type	Formation /Hazard	Top M.D.	Top T.V.D.	Bottom M.D.	Bottom T.V.D.	TDS (mg/L)	Data Source	Comment
Groundwater	ALLUVIAL FILL	0	0	363	363	501-1000	CGS	USGS (USGS 404200104042401 SB00906034ADC: 836mg/L)
Groundwater	FOX HILLS	363	363	564	563	501-1000	USGS	TDS estimated based on regional USGS sampling (Site 400844104403901). No local samples found
Confining Layer	PIERRE	564	563	943	935			
Groundwater	UPPER PIERRE POROSITY	943	935	1620	1563	1001-10000	USGS	CO DNR Report Project Number 2141
Confining Layer	PIERRE	1620	1563	3738	3283			
Hydrocarbon	PARKMAN	3738	3283	4385	3804			
Hydrocarbon	PIERRE	4385	3804	7302	6047			
Hydrocarbon	SHARON SPRINGS	7302	6047	7490	6093			
Hydrocarbon	NIOBRARA	7490	6093	12393	6100			

**OPERATOR COMMENTS AND SUBMITTAL**

Comments Verdad would like to recycle AL API 123-50262-00 which is why this filing has been labeled a re-file.

The nearest well completed or permitted in the same formation is the Schneider 1414 05H, measured is 2D using GIS mapping.

The nearest existing or proposed well belonging to another operator is the Boomslang Fed 8-60 14B-13-18-5 API# 05-123-47117 operated by Bison, well status PR. This distance was measured in 3D using an anti collision report, attached as "other".

This well has a bottom hole location beyond the unit boundary setback. The bottom of the completed interval will be within the unit boundary setback 300'FSL and 330' FEL of section 14. The wellbore beyond the unit boundary setback will be physically isolated and will not be completed.

This application is in a Comprehensive Area Plan No CAP #: \_\_\_\_\_

Oil and Gas Development Plan Name \_\_\_\_\_ OGDID ID#: \_\_\_\_\_

Location ID: 432178

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: Allison Schieber

Title: Sr. Regulatory Analyst Date: 7/26/2021 Email: regulatory@verdadresources.c



Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules, applicable orders, and SB 19-181 and is hereby approved.

COGCC Approved: \_\_\_\_\_ Director of COGCC Date: \_\_\_\_\_  
Expiration Date: \_\_\_\_\_

**API NUMBER**

05 123 50262 00

### Conditions Of Approval

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

**COA Type**

**Description**

### Best Management Practices

**No BMP/COA Type**

**Description**

1	Drilling/Completion Operations	Operator will perform anti-collision evaluation of all active (producing, shut-in, of temporarily abandoned) offset wellbores that have the potential of being within 150' feet of the proposed well prior to drilling operations. Notice shall be given to all offset operators prior to drilling.
2	Drilling/Completion Operations	Rule 604.c.1: Upon initial rig-up and at least once every thirty (30) days during drilling operations thereafter, pressure testing of the casing string and each component of the blowout prevention equipment including flange connections shall be performed to seventy percent (70%) of working pressure or seventy percent (70%) of the internal yield of casing, whichever is less. Pressure testing shall be conducted and the documented results shall be retained by the operator for inspection by the Director for a period of one (1) year. Activation of the pipe rams for function testing shall be conducted on a daily basis when practicable.
3	Drilling/Completion Operations	Alternative Logging Program - One of the first wells drilled on the pad will be logged with Open Hole Resistivity Log and Gamma Ray Log from the kick-off point to into the surface casing. All wells on the pad will have a cement bond log with gamma-ray run on production casing (or on intermediate casing if production liner is run) into the surface casing. The horizontal portion of every well will be logged with a measured-while-drilling gamma-ray log. The form 5, Completion Report, for each well on the pad will list all logs run and have those logs attached. The Form 5 for a well without open-hole logs shall clearly state "Alternative Logging Program - No open-hole logs were run" and shall clearly identify (by API#, well name & number) the well in which open-hole logs were run.

Total: 3 comment(s)

### Attachment List

**Att Doc Num**

**Name**

402760244	OffsetWellEvaluations Data
402760266	DEVIATED DRILLING PLAN
402760267	DEVIATED DRILLING PLAN
402760268	WELL LOCATION PLAT
402760284	DIRECTIONAL DATA

Total Attach: 5 Files

## General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
		Stamp Upon Approval

Total: 0 comment(s)



## Public Comments

No public comments were received on this application during the comment period.

