

State of Colorado Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203
Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

402753698

Receive Date:

07/20/2021

Report taken by:

Candice (Nikki) Graber

Site Investigation and Remediation Workplan (Supplemental Form)

This form shall be submitted to the Director for approval prior to the initiation of site investigation and remediation activities. However, this shall not preclude the Operator from taking immediate action to protect public health or safety, the environment, wildlife, or livestock.

This Form 27 describes site conditions as currently understood by the Operator; approval of this Form 27 by COGCC is based on the site conditions accurately described herein; any changes in site conditions identified during or subsequent to the performance of the approved workplan may necessitate additional investigation or remediation which shall be described on a supplemental Form 27. This Form 27 is intended to provide basic information regarding the proposed site investigation and remediation actions, but the workplan may be more fully described in attached documentation.

Closure request is not available for an Initial Site Investigation and Remediation Workplan.

OPERATOR INFORMATION

Name of Operator: NOBLE ENERGY INC	Operator No: 100322	Phone Numbers Phone: (970) 3045329 Mobile: ()
Address: 1001 NOBLE ENERGY WAY		
City: HOUSTON State: TX Zip: 77070		
Contact Person: Jacob Evans	Email: jacob.evans@chevron.com	

PROJECT, PURPOSE & SITE INFORMATION

PROJECT INFORMATION

Remediation Project #: 12471 Initial Form 27 Document #: 401935594

PURPOSE INFORMATION

- ☐ Rule 913.c.(1): Pit or Cuttings Trench closure.
- ☐ Rule 913.c.(2): Buried or partially buried vessel closure, which will be by removal.
- ☐ Rule 913.c.(3): Remediation of Spill and Releases pursuant to Rule 912.
- ☐ Rule 913.c.(4): Land treatment of Oily Waste pursuant to Rule 905.e.
- ☐ Rule 913.c.(5): Closure of Centralized E&P Waste Management Facilities pursuant to Rule 907.h.
- ☒ Rule 913.c.(6): Remediation of impacted Groundwater pursuant to Rule 915.e.(3).D, and the contaminant concentrations in Table 915-1.
- ☐ Rule 913.c.(7): Investigation and remediation of natural gas in soil or Groundwater.
- ☐ Rule 913.c.(8): When requested by the Director due to any potential risk to soil, Groundwater, or surface water.
- ☐ Rule 913.c.(9): Decommissioning of Oil and Gas Facilities.
- ☐ Rule 913.g: Changes of Operator.
- ☐ Rule 915.b: Request to leave elevated inorganics in situ.
- ☐ Other: _____

SITE INFORMATION

Yes Multiple Facilities

Facility Type: LOCATION	Facility ID: 328125	API #: _____	County Name: WELD
Facility Name: AGRICULTURAL PROD INC-64N66W 32SWNE	Latitude: 40.269520	Longitude: -104.799510	
** correct Lat/Long if needed: Latitude: _____		Longitude: _____	
QtrQtr: SWNE	Sec: 32	Twp: 4N	Range: 66W Meridian: 6 Sensitive Area? Yes
Facility Type: SPILL OR RELEASE	Facility ID: 462437	API #: _____	County Name: WELD
Facility Name: Agricultural Products Federal 32-17	Latitude: 40.269576	Longitude: -104.797120	
** correct Lat/Long if needed: Latitude: _____		Longitude: _____	
QtrQtr: SWNE	Sec: 32	Twp: 4N	Range: 66W Meridian: 6 Sensitive Area? Yes

SITE CONDITIONS

General soil type - USCS Classifications SM

Most Sensitive Adjacent Land Use Crop Land

Is domestic water well within 1/4 mile? Yes

Is surface water within 1/4 mile? Yes

Is groundwater less than 20 feet below ground surface? Yes

Other Potential Receptors within 1/4 mile

Occupied Building 425'

SITE INVESTIGATION PLAN

TYPE OF WASTE:

- | | | |
|--|--|--|
| <input checked="" type="checkbox"/> E&P Waste | <input type="checkbox"/> Other E&P Waste | <input type="checkbox"/> Non-E&P Waste |
| <input checked="" type="checkbox"/> Produced Water | <input type="checkbox"/> Workover Fluids | |
| <input checked="" type="checkbox"/> Oil | <input type="checkbox"/> Tank Bottoms | |
| <input checked="" type="checkbox"/> Condensate | <input type="checkbox"/> Pigging Waste | |
| <input type="checkbox"/> Drilling Fluids | <input type="checkbox"/> Rig Wash | |
| <input type="checkbox"/> Drill Cuttings | <input type="checkbox"/> Spent Filters | |
| | <input type="checkbox"/> Pit Bottoms | |
| | <input type="checkbox"/> Other (as described by EPA) | |

DESCRIPTION OF IMPACT

Impacted?	Impacted Media	Extent of Impact	How Determined
Yes	GROUNDWATER	75' X 75'	Laboratory Analytical
Yes	SOILS	30' X 30' X 13' bgs	Laboratory Analytical

INITIAL ACTION SUMMARY

Description of initial action or emergency response measures take to abate, investigate, and/or remediate impacts associated with E&P Waste.

During tank battery dismantlement impacted media was discovered between the tanks and separators. Confirmation sidewall excavation samples were collected above the phreatic zone and submitted under proper chain of custody procedures to Origins Laboratory for analysis of TPH-DRO, TPH-GRO, BTEX, and Naphthalene by EPA Methods 8015 and 8260c. A base groundwater sample was also collected and analyzed for BTEX.

PROPOSED SAMPLING PLAN

Proposed Soil Sampling

☒ Will soil samples be collected as part of this investigation? (Number, type (grab/composite), analyses, and locations of samples):

Twelve grab soil samples were collected by Eagle Environmental during site investigation activities for analysis of TPH-DRO, TPH-GRO, BTEX, and Naphthalene by EPA Methods 8015 and 8260c. Additionally, SS-02@3' was also analyzed for SAR by 20B Saturated Paste, EC by specific conductance by Modified 9050A, and pH by EPA 9045D.

Proposed Groundwater Sampling

☒ Will groundwater samples be collected as part of this investigation? (Number, analyses, and locations of samples):

Seven groundwater samples were collected by Eagle Environmental during site investigation activities and were submitted to Origins Laboratory for analysis of BTEX by EPA Method 8260c.

Proposed Surface Water Sampling

☐ Will surface water samples be collected as part of this investigation? (Number, analyses, and locations of samples):

Additional Investigative Actions

☐ Additional alternative investigative actions described in attached Site Investigation Plan (summary):

SITE INVESTIGATION REPORT

SAMPLE SUMMARY

Soil

Number of soil samples collected 12

Number of soil samples exceeding 915-1 2

NA / ND

-- Highest concentration of TPH (mg/kg) 628

-- Highest concentration of SAR 9.55

Was the areal and vertical extent of soil contamination delineated? No

BTEX > 915-1 Yes

Approximate areal extent (square feet) 900

Vertical Extent > 915-1 (in feet) 12

Groundwater

Number of groundwater samples collected 7

-- Highest concentration of Benzene (µg/l) 8250

Was extent of groundwater contaminated delineated? Yes

ND Highest concentration of Toluene (µg/l)

Depth to groundwater (below ground surface, in feet) 13'

-- Highest concentration of Ethylbenzene (µg/l) 898

Number of groundwater monitoring wells installed 6

-- Highest concentration of Xylene (µg/l) 8890

Number of groundwater samples exceeding 915-1 6

NA Highest concentration of Methane (mg/l)

Surface Water

0 Number of surface water samples collected

Number of surface water samples exceeding 915-1

If surface water is impacted, other agency notification may be required.

OTHER INVESTIGATION INFORMATION

☐ Were impacts to adjacent property or offsite impacts identified?

☐ Were background samples collected as part of this site investigation?

☐ Was investigation derived waste (IDW) generated as part of this investigation?

Volume of solid waste (cubic yards)

Volume of liquid waste (barrels)

☐ Is further site investigation required?

REMEDIAL ACTION PLAN

Does this Supplemental Form 27A include changes to a previously approved Remedial Action Plan? No

SOURCE REMOVAL SUMMARY

Describe how source is to be removed.

The source was removed on June 24, 2019 through excavation of impacted soil above COGCC Table 910-1 standards. Eagle Environmental collected confirmation grab soil samples above the phreatic zone to determine the lateral and vertical extent of the excavation.

REMEDIATION SUMMARY

Describe how remediation of existing impacts to soil and groundwater is to be accomplished (i.e. summarize remedial action plan). Provide a brief narrative description including: technical justification, schedule for implementation, estimated time to attain NFA status, plus plans and specifications for the selected remedial action technology.

Fourteen monitoring wells were installed to delineate dissolved phase impacts. An AS/SVE system has been installed and is currently operational.

Soil Remediation Summary

☐ In Situ

☒ Ex Situ

Bioremediation (or enhanced bioremediation)

Yes Excavate and offsite disposal

Chemical oxidation

If Yes: Estimated Volume (Cubic Yards) 330

Air sparge / Soil vapor extraction

Name of Licensed Disposal Facility or COGCC Facility ID #

Natural Attenuation

No Excavate and onsite remediation

Other

Land Treatment

_____ Bioremediation (or enhanced bioremediation)

_____ Chemical oxidation

_____ Other _____

Groundwater Remediation Summary

_____ No _____ Bioremediation (or enhanced bioremediation)

_____ No _____ Chemical oxidation

_____ No _____ Air sparge / Soil vapor extraction

_____ Yes _____ Natural Attenuation

_____ Yes _____ Other _____ A groundwater amendment was applied to the base of the excavation.

GROUNDWATER MONITORING

If groundwater has been impacted, describe proposed monitoring plan, including # of wells or sample points, monitoring schedule, analytical methods, points of compliance. Attach a groundwater monitoring location diagram.

Fourteen monitoring wells were installed and will be sampled on a quarterly basis. Groundwater samples were collected by Eagle Environmental and transported to Origins Laboratory for analysis of BTEX, naphthalene, sulfates, 1,2,4-trimethylbenzene, 1,3,5-trimethylbenzene.

REMEDIATION PROGRESS UPDATE

PERIODIC REPORTING

Approved Reporting Schedule:

☐ Quarterly

☐ Semi-Annually

☒ Annually

☐ Other _____

☐ **Request Alternative Reporting Schedule:**

☐ Semi-Annually

☐ Annually

☐ Other _____

Rule 913.e:

After initial approval of a Form 27, the Operator will provide quarterly update reports in a Supplemental Form 27 to document progress of site investigation and remediation, unless an alternative reporting schedule has been requested by the Operator and approved by the Director. The Director may request a more frequent reporting schedule based on site-specific conditions.

Report Type: ☒ Groundwater Monitoring ☐ Land Treatment Progress Report ☐ O&M Report

☐ Other _____

WASTE DISPOSAL INFORMATION

Was E&P waste generated as part of this remediation? Yes

Describe beneficial use, if any, of E&P Waste derived from this remediation project:

No beneficial use

Volume of E&P Waste (solid) in cubic yards _____ 330

E&P waste (solid) description _____ E&P solid waste derived from excavation of source impacts

COGCC Disposal Facility ID #, if applicable: _____

Non-COGCC Disposal Facility: _____ Waste Management Landfill/Bufalo Ridge

Volume of E&P Waste (liquid) in barrels _____ 0

E&P waste (liquid) description _____

COGCC Disposal Facility ID #, if applicable: _____

Non-COGCC Disposal Facility: _____

REMEDIATION COMPLETION REPORT

REMEDIATION COMPLETION SUMMARY

Is this a Final Closure Request for this Remediation Project? No _____

If YES:

☐ Compliant with Rule 913.h.(1).

☐ Compliant with Rule 913.h.(2).

☐ Compliant with Rule 913.h.(3).

Do all soils meet Table 915-1 standards? Yes _____

Does the previous reply indicate consideration of background concentrations? _____

Does Groundwater meet Table 915-1 standards? No _____

Is additional groundwater monitoring to be conducted? Yes _____

Operator shall comply with the COGCC 1000-Series Reclamation Requirements for all impacted and disturbed areas.

RECLAMATION PLAN

RECLAMATION PLANNING

Describe reclamation plan. Discuss existing and new grade recontouring; method and testing of compaction alleviation; and reseeding program, including location of new seed, seed mix and noxious weed prevention. Attach diagram or drawing.

Reclamation will be in accordance with COGCC 1004 Rule.

Is the described reclamation complete? No _____

Does the reclamation described herein constitute interim or final reclamation of the Oil and Gas Location?

☐ Interim

☐ Final

Did the Surface Owner provide the seed mix? _____

If YES, does the seed mix comply with local soil conservation district recommendations? _____

Did the local soil conservation district provide the seed mix? _____

SITE RECLAMATION DATES

Proposed date of commencement of Reclamation. 02/11/2019

Proposed date of completion of Reclamation. _____

IMPLEMENTATION SCHEDULE

Per Rule 913.d.(2): Any change from the approved implementation schedule will be requested at least 14 days in advance, and the Operator may not make the change without the Director's approval.

PRIOR DATES

Date of Surface Owner notification/consultation, if required. 12/21/2020

Actual Spill or Release date, or date of discovery. _____

SITE INVESTIGATION DATES

Date of Initial Actions described in Site Investigation Plan (start date). 02/11/2019

Proposed site investigation commencement. _____

Proposed completion of site investigation. 02/21/2020

REMEDIAL ACTION DATES

Proposed start date of Remediation. 06/24/2019

Proposed date of completion of Remediation. _____

Per Rule 913.d.(2): Any change from the approved implementation schedule will be requested at least 14 days in advance, and the Operator may not make the change without the Director's approval.

☐ Change from approved implementation schedule per Rule 913.d.(2).

Basis for change in implementation schedule:

OPERATOR COMMENT

I hereby certify all statements made in this form are to the best of my knowledge true, correct, and complete.

Signed: ` Jacob Evans _____

Title: Environmental Specialist _____

Submit Date: ` 07/20/2021 _____

Email: jacob.evans@chevron.com _____

Based on the information provided herein, this Application for Site Investigation and Remediation Workplan complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: Candice (Nikki) Graber _____

Date: 08/05/2021 _____

Remediation Project Number: 12471 _____

Condition of Approval

COA Type

Description

0 COA	

Attachment Check List

Upon approval, the approved Form 27 and all listed attachments will be indexed to the Remediation Project file. Only the approved Form 27 will also be indexed to the related Facilities.

Att Doc Num

Name

402753698	FORM 27-SUPPLEMENTAL-SUBMITTED
402753712	MONITORING REPORT

Total Attach: 2 Files

General Comments

User Group

Comment

Comment Date

Environmental	COGCC agrees to the sampling plan.	08/05/2021
---------------	------------------------------------	------------

Total: 1 comment(s)