



ABANDONMENT PROGNOSIS
MT. HOPE FIELD
C. F. GREEN "B" LEASE, WELL NO. 18

Present Status:

Elev: 4240' KB

PBTD: 5063'

4-1/2" Csg. Hd: 4233' Retirement W.O. No. 6242

Proposed Work:

1. Fill 4-1/2" casing with cement from PBTD-5020' to 50' above Muddy perfs - approx. 4850'.
2. Locate casing free point.
3. Shoot off and pull casing above casing free point. Fill hole w/heavy mud.
4. Place 15 sacks plug at bottom of surface casing and 10 sacks plug at top of surface casing.
5. Install abandonment marker.

NOTE: Colorado Oil and Gas Commission must be notified 24 hours prior to commencement of job.

Muddy Perfs.
4906-4907
PBTD-5020

4-1/2" Csg @ 5097'

A. T. Rylands
A. T. Rylands

W. T. Nance
W. T. Nance

C. D. Sweet
C. D. Sweet

CAN
CFW: jr
February 13, 1962
Billings, Montana