

FORM
2

Rev
12/20

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203
Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

402759303

Date Received:

07/26/2021

APPLICATION FOR PERMIT TO:

☒ Drill ☐ Deepen ☐ Re-enter ☐ Recomplete and Operate

Amend ☐

Refile ☒

Sidetrack ☐

TYPE OF WELL OIL ☒ GAS ☐ COALBED ☐ OTHER: _____

ZONE TYPE SINGLE ZONE ☒ MULTIPLE ZONES ☐ COMMINGLE ZONES ☐

Well Name: Schneider 1414 Well Number: 05H
Name of Operator: VERDAD RESOURCES LLC COGCC Operator Number: 10651
Address: 1125 17TH STREET SUITE 550
City: DENVER State: CO Zip: 80202
Contact Name: Allison Schieber Phone: (720)845-6909 Fax: ()
Email: regulatory@verdadresources.com

RECLAMATION FINANCIAL ASSURANCE

Plugging and Abandonment Bond Surety ID: 20170009

WELL LOCATION INFORMATION

Surface Location

QtrQtr: NENW Sec: 14 Twp: 8N Rng: 60W Meridian: 6

Footage at Surface: 241 Feet FNL 1397 Feet FWL
FNL/FSL FEL/FWL

Latitude: 40.669103 Longitude: -104.062322

GPS Data: GPS Quality Value: 1.5 Type of GPS Quality Value: PDOP Date of Measurement: 05/24/2018

Ground Elevation: 4943

Field Name: WILDCAT Field Number: 99999

Well Plan: is ☐ Directional ☒ Horizontal (highly deviated) ☐ Vertical

If Well plan is Directional or Horizontal attach Deviated Drilling Plan and Directional Data.

Subsurface Locations

Top of Productive Zone (TPZ)

Sec: 14 Twp: 8N Rng: 60W Footage at TPZ: 300 FNL 927 FEL
Measured Depth of TPZ: 7263 True Vertical Depth of TPZ: 6100 FNL/FSL FEL/FWL

Base of Productive Zone (BPZ)

Sec: 14 Twp: 8N Rng: 60W Footage at BPZ: 300 FSL 931 FEL
Measured Depth of BPZ: 11970 True Vertical Depth of BPZ: 6100 FNL/FSL FEL/FWL

Bottom Hole Location (BHL)

Sec: 14 Twp: 8N Rng: 60W Footage at BHL: 210 FSL 931 FEL
FNL/FSL FEL/FWL

LOCAL GOVERNMENT PERMITTING INFORMATION

County: WELDMunicipality: N/A

Is the Surface Location of this Well in an area designated as one of State interest and subject to the requirements of § 24-65.1-108 C.R.S.? Yes

Per § 34-60-106(1)(f)(I)(A) C.R.S., the following questions pertain to the Relevant Local Government approval of the siting of the proposed Oil and Gas Location.

SB 19-181 provides that when "applying for a permit to drill," operators must include proof that they sought a local government siting permit and the disposition of that permit application, or that the local government does not have siting regulations. § 34-60-106(1)(f)(I)(A) C.R.S.

Does the Relevant Local Government regulate the siting of Oil and Gas Locations, with respect to this Location? ☒ Yes ☐ No

☒ If yes, in checking this box, I hereby certify that an application has been filed with the local government with jurisdiction to approve the siting of the proposed oil and gas location.

The disposition of the application filed with the Relevant Local Government is: Approved Date of Final Disposition: 06/21/2019

Comments: WOGLA19-0105

SURFACE AND MINERAL OWNERSHIP AT WELL'S OIL & GAS LOCATION

Surface Owner of the land at this Well's Oil and Gas Location: ☒ Fee ☐ State ☐ Federal ☐ Indian

Mineral Owner beneath this Well's Oil and Gas Location: ☒ Fee ☐ State ☐ Federal ☐ Indian

Surface Owner Protection Financial Assurance (if applicable): _____ Surety ID Number (if applicable): _____

MINERALS DEVELOPED BY WELL

The ownership of all the minerals that will be developed by this Well is (check all that apply):

- ☒ Fee
☐ State
☐ Federal
☐ Indian
☐ N/A

LEASE INFORMATION

Using standard QtrQtr, Section, Township, Range format describe one entire mineral lease as follows:

* If this Well is within a unit, describe a lease that will be developed by the Well.

* If this Well is not subject to a unit, describe the lease that will be produced by the Well.

(Attach a Lease Map or Lease Description or Lease if necessary.)

W2 SECTION 14 8N 60W 6TH PM: 320 ACRES

Total Acres in Described Lease: 320 Described Mineral Lease is: ☒ Fee ☐ State ☐ Federal ☐ Indian

Federal or State Lease # _____

SAFETY SETBACK INFORMATION

Distance from Well to nearest:

Building: 5280 Feet
Building Unit: 5280 Feet
Public Road: 1367 Feet
Above Ground Utility: 1429 Feet
Railroad: 5280 Feet

INSTRUCTIONS:

- Specify all distances per Rule 308.b.(1).
- Enter 5280 for distance greater than 1 mile.
- Building - nearest building of any type. If nearest Building is a Building Unit, enter same distance for both.
- Building Unit – as defined in 100 Series Rules.

Property Line: 210 Feet

OBJECTIVE FORMATIONS

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
NIOBRARA	NBRR	535-1097	640	Sec 14: ALL

Federal or State Unit Name (if appl):

Unit Number:

SUBSURFACE MINERAL SETBACKS

Enter 5280 for distance greater than 1 mile.

Is this Well within a unit? Yes

If YES:

Enter the minimum distance from the Completed Zone of this Well to the Unit Boundary: 300 Feet

Enter the minimum distance from the Completed Zone of this Well to the Completed Zone of an offset Well within the same unit permitted or completed in the same formation: 597 Feet

If NO:

Enter the minimum distance from the Completed Zone of this Well to the Lease Line of the described lease: Feet

Enter the minimum distance from the Completed Zone of this Well to the Completed Zone of an offset Well producing from the same lease and permitted or completed in the same formation: Feet

Exception Location

☐ If this Well requires the approval of a Rule 401.c Exception Location, enter the Rule or spacing order number and attach the Exception Location Request and Waivers.

SPACING & FORMATIONS COMMENTS

Sec 14 T8N R60W: All: 640 Acres

DRILLING PROGRAM

Proposed Total Measured Depth: 12060 Feet

TVD at Proposed Total Measured Depth 6100 Feet

Distance from the proposed wellbore to nearest existing or proposed wellbore belonging to another operator, including plugged wells:

Enter distance if less than or equal to 1,500 feet: 334 Feet ☐ No well belonging to another operator within 1,500 feet

Will a closed-loop drilling system be used? Yes

Is H₂S gas reasonably expected to be encountered during drilling operations at concentrations greater than

or equal to 100 ppm? No If yes, attach an H₂S Drilling Plan unless a plan was already submitted with the Form 2A per Rule 304.c.(10).

Will there be hydraulic fracture treatment at a depth less than 2,000 feet in this well? No

Will salt sections be encountered during drilling? No

Will salt based (>15,000 ppm Cl) drilling fluids be used? No

Will oil based drilling fluids be used? Yes

BOP Equipment Type: ☒ Annular Preventor ☒ Double Ram ☒ Rotating Head ☐ None

Beneficial reuse or land application plan submitted? No

Reuse Facility ID: or Document Number:

CASING PROGRAM

<u>Casing Type</u>	<u>Size of Hole</u>	<u>Size of Casing</u>	<u>Grade</u>	<u>Wt/Ft</u>	<u>Csg/Liner Top</u>	<u>Setting Depth</u>	<u>Sacks Cmt</u>	<u>Cmt Btm</u>	<u>Cmt Top</u>
CONDUCTOR	24	16	N/A	65	0	80	70	80	0
SURF	13+1/2	9+5/8	J55	36	0	1800	489	1800	0
1ST	8+1/2	5+1/2	HCP110	20	0	12060	1593	12060	

☐ Conductor Casing is NOT planned

POTENTIAL FLOW AND CONFINING FORMATIONS

<u>Zone Type</u>	<u>Formation /Hazard</u>	<u>Top M.D.</u>	<u>Top T.V.D.</u>	<u>Bottom M.D.</u>	<u>Bottom T.V.D.</u>	<u>TDS (mg/L)</u>	<u>Data Source</u>	<u>Comment</u>
Groundwater	alluvial fill	0	0	363	363	501-1000	USGS	USGS (USGS 404200104042401 SB00906034ADC: 836mg/L)
Groundwater	fox hills	363	363	563	563	501-1000	USGS	TDS estimated based on regional USGS sampling (Site 400844104403901). No local samples found.
Confining Layer	pierre	563	563	942	935			
Groundwater	upper pierre porosity	942	936	1617	1563	1001-10000	USGS	CO DNR Report Project Number 2141
Confining Layer	pierre	1617	1563	3620	3283			
Hydrocarbon	parkman	3620	3283	4228	3804			
Confining Layer	pierre	4228	3804	6981	6047			
Hydrocarbon	sharon springs	6981	6047	7163	6093			
Hydrocarbon	niobrara	7163	6093	12060	6100			

OPERATOR COMMENTS AND SUBMITTAL

Comments The nearest well completed or permitted in the same formation is the Schneider 1414 06H, measured is 2D using GIS mapping.

The nearest existing or proposed well belonging to another operator is the Pintail 2-11-8HN API#05-123-46546 operated by Mallard, well status DG. This distance was measured in 3D using an anti collision report, attached as "other".

This well has a bottom hole location beyond the unit boundary setback. The bottom of the completed interval will be within the unit boundary setback 300'FSL and 931' FEL of section 14. The wellbore beyond the unit boundary setback will be physically isolated and will not be completed.

Verdad would like to use AL API#123-50273-00 for this new location permit to drill.

This application is in a Comprehensive Area Plan No CAP #: _____

OGDP ID#: _____ OGDP Name: _____ Expiration Date: _____

Location ID: 432178 Location Name: _____

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Allison Schieber

Title: Sr. Regulatory Analyst Date: 7/26/2021 Email: regulatory@verdadresources.c

Operator must have a valid water right or permit allowing for industrial use or purchased water from a seller that has a valid water right or permit allowing for industrial use, otherwise an application for a change in type of use is required under Colorado law. Operator must also use the water in the location set forth in the water right decree or well permit, otherwise an application for a change in place of use is required under Colorado law. Section 37-92-103(5), C.R.S. (2011).

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules, applicable orders, and SB 19-181 and is hereby approved.

COGCC Approved: _____

Director of COGCC

Date: 9/15/2021

Expiration Date: 09/14/2024

API NUMBER

05 123 50273 00

Conditions Of Approval

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

Condition of Approval

COA Type

Description

Drilling/Completion Operations	Bradenhead Testing Per COGCC Order 1-232, Bradenhead tests shall be performed according to the following schedule and Form 17 submitted within 10 days of each test: 1) Within 60 days of rig release, prior to stimulation. If any pressure greater than 200 psi, must contact COGCC engineer prior to stimulation. 2) If a delayed completion, 6 months after rig release and prior to stimulation. If any pressure greater than 200 psi, must contact COGCC engineer prior to stimulation. 3) A post-production test within 60 days after first sales, as reported on the Form 10, Certificate of Clearance.
Drilling/Completion Operations	1) Submit Form 42 electronically to COGCC 48 hours prior to MIRU (spud notice) for the first well activity with a rig on the pad and provide 48 hour spud notice via Form 42 for all subsequent wells drilled on the pad. 2) Provide cement coverage from TD to a minimum of 500' above Niobrara. Verify coverage with cement bond log. 3) Oil-based drilling fluid is to be used only after all fresh water aquifers are covered. 4) The Operator will abide by the COGCC Policy for Bradenhead Monitoring During Hydraulic Fracturing Treatments in the Greater Wattenberg Area, May 29, 2012.
Drilling/Completion Operations	Operator will ensure the wellbore beyond the unit boundary setback is physically isolated and is not completed. In the Operator Comments on the Form 5A the operator will (1) report the footages from the section lines of the bottom of the completed interval (2) describe how the wellbore beyond the unit boundary setback is physically isolated and (3) certify that none of the wellbore beyond the setback was completed.
Drilling/Completion Operations	Operator shall comply with Notice to Operators: Interim Reclamation Procedures for Delayed Operations (dated January 5, 2017).
Drilling/Completion Operations	If conductors are preset, operator shall comply with Notice to Operators: Procedures for Preset Conductors (dated September 1, 2016).
5 COAs	

Best Management Practices

No	BMP/COA Type	Description
1	Drilling/Completion Operations	Operator will perform anti-collision evaluation of all active (producing, shut-in, of temporarily abandoned) offset wellbores that have the potential of being within 150' feet of the proposed well prior to drilling operations. Notice shall be given to all offset operators prior to drilling.
2	Drilling/Completion Operations	Upon initial rig-up and at least once every thirty (30) days during drilling operations thereafter, pressure testing of the casing string and each component of the blowout prevention equipment including flange connections shall be performed to seventy percent (70%) of working pressure or seventy percent (70%) of the internal yield of casing, whichever is less. Pressure testing shall be conducted and the documented results shall be retained by the operator for inspection by the Director for a period of one (1) year. Activation of the pipe rams for function testing shall be conducted on a daily basis when practicable.
3	Drilling/Completion Operations	Alternative Logging Program - One of the first wells drilled on the pad will be logged with Open Hole Resistivity Log and Gamma Ray Log from the kick-off point to into the surface casing. All wells on the pad will have a cement bond log with gamma-ray run on production casing (or on intermediate casing if production liner is run) into the surface casing. The horizontal portion of every well will be logged with a measured-while-drilling gamma-ray log. The form 5, Completion Report, for each well on the pad will list all logs run and have those logs attached. The Form 5 for a well without open-hole logs shall clearly state "Alternative Logging Program - No open-hole logs were run" and shall clearly identify (by API#, well name & number) the well in which open-hole logs were run.

Total: 3 comment(s)

Applicable Policies and Notices to Operators

Notice Concerning Operating Requirements for Wildlife Protection.
http://cogcc.state.co.us/documents/reg/Policies/Wildlife_Notice.pdf

Policy for Bradenhead Monitoring During Hydraulic Fracturing Treatments in the Greater Wattenberg Area.
<http://cogcc.state.co.us/documents/reg/Policies/PolicyGwaBradenheadMonitoringFinal.pdf>

Attachment List

<u>Att Doc Num</u>	<u>Name</u>
402759303	FORM 2 SUBMITTED
402759977	WELL LOCATION PLAT
402759979	DEVIATED DRILLING PLAN
402759980	OTHER
402759982	DIRECTIONAL DATA
402812118	OffsetWellEvaluations Data
402812417	OFFSET WELL EVALUATION

Total Attach: 7 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Engineer	•Surface Casing Check complete •Offset well review complete - Requested and received updated OWE spreadsheet from Operator 317.r - No wells 317.s - No wells •Engineering review complete	09/15/2021
Permit	Final Review Completed.	09/10/2021
Permit	Corrected Safety Setback Distances per operator information. Permitting review complete.	09/09/2021
OGLA	The Location and its associated Form 2A materials was fully reviewed during the review of this APD. This APD complies with all COGCC Rules and is adequately protective of public health, safety, welfare, the environment, and wildlife resources. OGLA task passed.	08/17/2021

Total: 4 comment(s)