

State of Colorado Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203
Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

402808605

Receive Date:

09/13/2021

Report taken by:

CHRIS CANFIELD

Site Investigation and Remediation Workplan (Supplemental Form)

This form shall be submitted to the Director for approval prior to the initiation of site investigation and remediation activities. However, this shall not preclude the Operator from taking immediate action to protect public health or safety, the environment, wildlife, or livestock.

This Form 27 describes site conditions as currently understood by the Operator; approval of this Form 27 by COGCC is based on the site conditions accurately described herein; any changes in site conditions identified during or subsequent to the performance of the approved workplan may necessitate additional investigation or remediation which shall be described on a supplemental Form 27. This Form 27 is intended to provide basic information regarding the proposed site investigation and remediation actions, but the workplan may be more fully described in attached documentation.

Closure request is not available for an Initial Site Investigation and Remediation Workplan.

OPERATOR INFORMATION

Name of Operator: NOBLE ENERGY INC	Operator No: 100322	Phone Numbers Phone: (970) 3045329 Mobile: ()
Address: 1001 NOBLE ENERGY WAY		
City: HOUSTON	State: TX Zip: 77070	
Contact Person: Jacob Evans	Email: jacob.evans@chevron.com	

PROJECT, PURPOSE & SITE INFORMATION

PROJECT INFORMATION

Remediation Project #: 8440 Initial Form 27 Document #: 2148980

PURPOSE INFORMATION

- ☐ Rule 913.c.(1): Pit or Cuttings Trench closure.
- ☐ Rule 913.c.(2): Buried or partially buried vessel closure, which will be by removal.
- ☒ Rule 913.c.(3): Remediation of Spill and Releases pursuant to Rule 912.
- ☐ Rule 913.c.(4): Land treatment of Oily Waste pursuant to Rule 905.e.
- ☐ Rule 913.c.(5): Closure of Centralized E&P Waste Management Facilities pursuant to Rule 907.h.
- ☒ Rule 913.c.(6): Remediation of impacted Groundwater pursuant to Rule 915.e.(3).D, and the contaminant concentrations in Table 915-1.
- ☐ Rule 913.c.(7): Investigation and remediation of natural gas in soil or Groundwater.
- ☐ Rule 913.c.(8): When requested by the Director due to any potential risk to soil, Groundwater, or surface water.
- ☐ Rule 913.c.(9): Decommissioning of Oil and Gas Facilities.
- ☐ Rule 913.g: Changes of Operator.
- ☐ Rule 915.b: Request to leave elevated inorganics in situ.
- ☐ Other: _____

SITE INFORMATION

No Multiple Facilities

Facility Type: LOCATION	Facility ID: 376820	API #: _____	County Name: ADAMS
Facility Name: FRI-61S67W 18CSE		Latitude: 39.960989	Longitude: -104.926653
** correct Lat/Long if needed: Latitude: _____		Longitude: _____	
QtrQtr: CSE	Sec: 18	Twp: 1S	Range: 67W Meridian: 6 Sensitive Area? Yes

SITE CONDITIONS

General soil type - USCS Classifications CL Most Sensitive Adjacent Land Use CROP LAND

Is domestic water well within 1/4 mile? Yes Is surface water within 1/4 mile? Yes

Is groundwater less than 20 feet below ground surface? No

Other Potential Receptors within 1/4 mile

SURFACE WATER 640' E, WATER WELL 836' N.

SITE INVESTIGATION PLAN**TYPE OF WASTE:**☒ **E&P Waste** ☐ **Other E&P Waste** ☐ **Non-E&P Waste**☒ Produced Water☐ Workover Fluids☒ Oil☐ Tank Bottoms☒ Condensate☐ Pigging Waste☐ Drilling Fluids☐ Rig Wash☐ Drill Cuttings☐ Spent Filters☐ Pit Bottoms☐ Other (as described by EPA)**DESCRIPTION OF IMPACT**

Impacted?	Impacted Media	Extent of Impact	How Determined
Yes	GROUNDWATER	~53,500 SQUARE FEET	Lab Analytical
Yes	SOILS	~367,500 CUBIC FEET	Lab Analytical

INITIAL ACTION SUMMARY

Description of initial action or emergency response measures take to abate, investigate, and/or remediate impacts associated with E&P Waste.

SEE FORM 19, COGCC DOCUMENT #2147193.

PROPOSED SAMPLING PLAN**Proposed Soil Sampling**☒ Will soil samples be collected as part of this investigation? (Number, type (grab/composite), analyses, and locations of samples):

Soil samples were collected as part of the site investigation and analyzed for TPH-GRO, TPH-DRO, Naphthalene, and BTEX.

Proposed Groundwater Sampling☒ Will groundwater samples be collected as part of this investigation? (Number, analyses, and locations of samples):

Groundwater samples were collected as part of the site investigation and analyzed for BTEX. Groundwater monitoring will be scheduled on a quarterly basis. Point of compliance has been achieved at the location.

Proposed Surface Water Sampling☐ Will surface water samples be collected as part of this investigation? (Number, analyses, and locations of samples):**Additional Investigative Actions**☐ Additional alternative investigative actions described in attached Site Investigation Plan (summary):**SITE INVESTIGATION REPORT****SAMPLE SUMMARY**

Soil

Number of soil samples collected 33
Number of soil samples exceeding 915-1 6
Was the areal and vertical extent of soil contamination delineated? Yes
Approximate areal extent (square feet) 52000

NA / ND

-- Highest concentration of TPH (mg/kg) 1859
NA Highest concentration of SAR
BTEX > 915-1 Yes
Vertical Extent > 915-1 (in feet) 53

Groundwater

Number of groundwater samples collected 42
Was extent of groundwater contaminated delineated? Yes
Depth to groundwater (below ground surface, in feet) 29'
Number of groundwater monitoring wells installed 42
Number of groundwater samples exceeding 915-1 24

-- Highest concentration of Benzene (µg/l) 15000
-- Highest concentration of Toluene (µg/l) 33000
-- Highest concentration of Ethylbenzene (µg/l) 1200
-- Highest concentration of Xylene (µg/l) 18000
NA Highest concentration of Methane (mg/l)

Surface Water

0 Number of surface water samples collected
0 Number of surface water samples exceeding 915-1
If surface water is impacted, other agency notification may be required.

OTHER INVESTIGATION INFORMATION

☐ Were impacts to adjacent property or offsite impacts identified?

☐ Were background samples collected as part of this site investigation?

☐ Was investigation derived waste (IDW) generated as part of this investigation?

Volume of solid waste (cubic yards) Volume of liquid waste (barrels)

☐ Is further site investigation required?

REMEDIAL ACTION PLAN

Does this Supplemental Form 27A include changes to a previously approved Remedial Action Plan? No

SOURCE REMOVAL SUMMARY

Describe how source is to be removed.

Source removal is being addressed by LNAPL recovery wells, total fluid extraction wells, and soil vapor extraction.

REMEDIATION SUMMARY

Describe how remediation of existing impacts to soil and groundwater is to be accomplished (i.e. summarize remedial action plan). Provide a brief narrative description including: technical justification, schedule for implementation, estimated time to attain NFA status, plus plans and specifications for the selected remedial action technology.

LNAPL recovery wells were installed and are operational. Additional total fluid recovery pumps have also been installed and are operational. The soil vapor extraction system has been activated and is currently removing mass.

Soil Remediation Summary

☒ In Situ

☐ Ex Situ

No Bioremediation (or enhanced bioremediation) Excavate and offsite disposal

No Chemical oxidation If Yes: Estimated Volume (Cubic Yards)

Yes Air sparge / Soil vapor extraction

Yes Natural Attenuation

No Other _____

Name of Licensed Disposal Facility or COGCC Facility ID # _____

Excavate and onsite remediation

No Land Treatment

No Bioremediation (or enhanced bioremediation)

No Chemical oxidation

No Other _____

Groundwater Remediation Summary

No Bioremediation (or enhanced bioremediation)

No Chemical oxidation

Yes Air sparge / Soil vapor extraction

Yes Natural Attenuation

Yes Other LNAPL Recovery wells/Total
Fluid Recovery

GROUNDWATER MONITORING

If groundwater has been impacted, describe proposed monitoring plan, including # of wells or sample points, monitoring schedule, analytical methods, points of compliance. Attach a groundwater monitoring location diagram.

Monitoring wells SB07, SB08, SB10, SB13, SB14, SB15, SB19, SB20, SB22R, SB27R, SB29, and SB33 were sampled. Groundwater samples were collected by Tasman Geosciences and transported to Summit Scientific under proper chain of custody procedures and analyzed for BTEX by EPA Method 8260b. Monitoring wells SB05, SB09, SB10, SB16R2, SB23R, SB30, SB31, and SB37 had measurable LNAPL and therefore groundwater samples were not collected from these locations. Monitoring wells SB17, SB24R, SB25R, and SB28R were not gauged or sampled because they have been destroyed. During the 1st quarter 2021 sample event groundwater will be sampled for BTEX, naphthalene, 1,2,4-trimethylbenzene, and 1,3,5-trimethylbenzene. Inorganic parameters will be sampled during the 1st quarter 2021 sampling event.

REMEDIATION PROGRESS UPDATE

PERIODIC REPORTING

Approved Reporting Schedule:

☐ Quarterly☐ Semi-Annually☒ Annually☐ Other

☐ Request Alternative Reporting Schedule:

☐ Semi-Annually☐ Annually☐ Other

Rule 913.e:

After initial approval of a Form 27, the Operator will provide quarterly update reports in a Supplemental Form 27 to document progress of site investigation and remediation, unless an alternative reporting schedule has been requested by the Operator and approved by the Director. The Director may request a more frequent reporting schedule based on site-specific conditions.

Report Type:

☒ Groundwater Monitoring☐ Land Treatment Progress Report☐ O&M Report☐ Other

WASTE DISPOSAL INFORMATION

Was E&P waste generated as part of this remediation? Yes

Describe beneficial use, if any, of E&P Waste derived from this remediation project:

No beneficial use

Volume of E&P Waste (solid) in cubic yards 0

E&P waste (solid) description

COGCC Disposal Facility ID #, if applicable:

Non-COGCC Disposal Facility:

Volume of E&P Waste (liquid) in barrels 2300

E&P waste (liquid) description E&P liquid waste derived from total fluid and LNAPL recovery

COGCC Disposal Facility ID #, if applicable:

Non-COGCC Disposal Facility: NGL

REMEDIATION COMPLETION REPORT

REMEDIATION COMPLETION SUMMARY

Is this a Final Closure Request for this Remediation Project? No

If YES:

☐ Compliant with Rule 913.h.(1).☐ Compliant with Rule 913.h.(2).☐ Compliant with Rule 913.h.(3).

Do all soils meet Table 915-1 standards? No

Does the previous reply indicate consideration of background concentrations?

Does Groundwater meet Table 915-1 standards? No

Is additional groundwater monitoring to be conducted?

Operator shall comply with the COGCC 1000-Series Reclamation Requirements for all impacted and disturbed areas.

RECLAMATION PLAN

RECLAMATION PLANNING

Describe reclamation plan. Discuss existing and new grade recontouring; method and testing of compaction alleviation; and reseeding program, including location of new seed, seed mix and noxious weed prevention. Attach diagram or drawing.

Final reclamation will be in accordance with COGCC 1000 Series Rules.

Is the described reclamation complete? Yes _____

Does the reclamation described herein constitute interim or final reclamation of the Oil and Gas Location?

☒ Interim ☐ Final

Did the Surface Owner provide the seed mix? _____

If YES, does the seed mix comply with local soil conservation district recommendations? _____

Did the local soil conservation district provide the seed mix? _____

SITE RECLAMATION DATES

Proposed date of commencement of Reclamation. 04/21/2014

Proposed date of completion of Reclamation. _____

IMPLEMENTATION SCHEDULE

Per Rule 913.d.(2): Any change from the approved implementation schedule will be requested at least 14 days in advance, and the Operator may not make the change without the Director's approval.

PRIOR DATES

Date of Surface Owner notification/consultation, if required. _____

Actual Spill or Release date, or date of discovery. 11/04/2013

SITE INVESTIGATION DATES

Date of Initial Actions described in Site Investigation Plan (start date). _____

Proposed site investigation commencement. 11/04/2013

Proposed completion of site investigation. 04/21/2014

REMEDIAL ACTION DATES

Proposed start date of Remediation. 11/12/2013

Proposed date of completion of Remediation. _____

Per Rule 913.d.(2): Any change from the approved implementation schedule will be requested at least 14 days in advance, and the Operator may not make the change without the Director's approval.

☐ Change from approved implementation schedule per Rule 913.d.(2).

Basis for change in implementation schedule:

OPERATOR COMMENT

--

I hereby certify all statements made in this form are to the best of my knowledge true, correct, and complete.

Signed: ` Jacob Evans _____

Title: Environmental Specialist _____

Submit Date: ` 09/13/2021 _____

Email: jacob.evans@chevron.com _____

Based on the information provided herein, this Application for Site Investigation and Remediation Workplan complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: CHRIS CANFIELD _____

Date: 09/25/2021 _____

Remediation Project Number: 8440 _____

Condition of Approval**COA Type****Description**

0 COA	

Attachment Check List

Upon approval, the approved Form 27 and all listed attachments will be indexed to the Remediation Project file. Only the approved Form 27 will also be indexed to the related Facilities.

Att Doc Num**Name**

402808605	FORM 27-SUPPLEMENTAL-SUBMITTED
402808620	MONITORING REPORT

Total Attach: 2 Files

General Comments**User Group****Comment****Comment Date**

		Stamp Upon Approval
--	--	---------------------

Total: 0 comment(s)