

**Foundation Energy Management, LLC**  
**WELLBORE DIAGRAM**

Well / Battery	Prospect Name		Total Depth	Current Status
Helling 32-21			1767	TA
Location	Sec-Twn-Rng		Producing Horizon	County & State
Bonny	21-4S-43W		Niobrara	Yuma, CO

## WELLBORE DIAGRAM

**Prepared Date:** 9/29/21  
**Prepared By:** Ray Prentice

### General Info

API #: 05-125-06700

KB Elevation: 3824

GL Elevation: 3828

Spud Date: 3/11/82

Completion Date: 3/27/82

TVD: 1767

MD:

Last PBTD: 1538

### Tubing Detail

inch(OD)

```
# (weight)
```

grade

### Tubing Tally

KB

Length

Depth

0

0

0

0

0

### Surface Casing

7 inch (OD)

17 # (weight)

grade

282 depth from KB

cement top

75 sacks of cement

9 7/8 inch (OD) HOLE SIZE

### Production Casing

4.5 inch (OD)

9.5 # (weight)

grade

1767 depth from KB

ment top

100 sacks of cement

6 456 inch (OD) HOLE SIZE

### Perforations

1591

1 sx cement

1538'

1606