

Date:	12/3/12
Preparer:	twm
Lease #:	8305

Wellname:	UPRR 1-1		
Field:	Golden Spike		
County:	Cheyenne	State:	CO
API:	05-017-06031		

Spot Location	SW SE
Sec:	1
Twp:	16S
Rge:	45W

CASING

Size	Weight	Grade	Depth	Cement	Date Cmt'd	Comment
8 5/8	24		1261	550	4/6/69	
5 1/2	14		5652	125	4/26/69	TOC-CBL: 4650
Port Collar						

DST'S

5350' -5400' (St Louis)	258' GIP, 50 O, 123' MCO, 420' SMCO	952 -944 #
-------------------------	-------------------------------------	------------

PERFORATIONS

Formation	Top	Btm	SPF	# of holes	Date	Status
St Louis	5294	5304	4	6	5/3/69	squeezed
Spergen	5366	5388	4	6	5/1/69	squeezed
St Louis	5291	5304	2	26	5/5/80	open
Spergen	5364	5388	2	48	5/5/80	open
Warsaw	5473	5477	2	8	4/29/69	Below CIBP

KB:	4345
GL:	4336
Diff:	9

8 5/8 @ 1261

(12/81) Sqz 150 sx 2230-2400

TOC-CBL: 4650

St Louis (miss) 5291 - 5304 ==

Spergen (miss)	5364 - 5388	=====
----------------	-------------	-------

PBTD	5430
------	------

Leaky CIBP 5440

Warsaw 5473 - 5477

PBTD 5634

5 1/2 @ 5652

RTD	<u>5665</u>
-----	-------------

LTD	<u>5657</u>
-----	-------------

SN 5375

2/19/79 set CIBP @ 5440',

4/28/80	CIBP leaking and lower perfs communicating with upper perfs.
---------	--

Squeeze StLouis+Spergen+leaky CIBP w/ 150 sx, **DOC** from 5157 to 5430.

Re-PERF 5291-5304, 5364-88.

12/8/81 **Squeeze** csg leaks 2230-2400 w/150 sx. DO cmt 2140' - 2458'

6/1/87	Murfin takes over operations.
--------	-------------------------------