

Phillips Luff 3-30  
API 05-103-08668

CONDUCTOR  
13 3/8 48# 42'  
Cemented to SURF FROM 42'

SURFACE 8 5/8 24#  
SURFACE to 3840'  
Cemented to surface

5 1/2 x 8 5/8 casing hanger  
TOP at 3758

5 1/2 LINER 15.5#  
Set FROM 3758' TO 6635'  
Cemented FROM 3758 TO 6635'

Perforations  
Fourteen holes 6403' TO 6521'

T.D. 6635'

