

Oxy COA Operations Summary

Well:	HAUCK 17-29	Spud Date:	6/26/2008 8:30:00 PM
Project:	COLORADO-WELD-NAD83-UTM13	Site:	HAUCK 7-29 PAD
Event:	ABANDONMENT	Rig Name:	RANGER 5531
Start Date:	8/2/21	End Date:	10/12/21
Datum:	KB @ 4932	Well UWI:	0/2/N/68/W/29/0/SWNE/6/PM/N/2,103.00/E/0/1,990.00/0/0

Department	Approved By	Date Approved
LEAD	ROBERT A. PITTS	08/18/2021

7/28/21

Time From	Subcode	Subcode Description	Operation
8:35	C	FORM 42 SUBMIT WITH 48 HOURS NOTICE	<p>FORM 42 APPROVED</p> <p>START DATE: 7/30/2021; 08:00AM</p> <p>FORM 6: VALID THROUGH 11/20/2021</p> <p>FORM 4: NOT REQUIRED</p> <p>FAA: APPROVED</p> <p>BLM: NO</p> <p>FORM 17: COMPLETED</p> <p>SAMPLE: COMPLETED</p>

7/29/21

Time From	Subcode	Subcode Description	Operation
16:44	J	CONTROLLED VENTING AND VAPORS	Operator shall implement measures to control venting, to protect health and safety, and to ensure that vapors and odors from well plugging operations do not constitute a nuisance or hazard to public welfare.

8/9/21

Time From	Subcode	Subcode Description	Operation
7:14	F	VERIFY NO MIGRATION BEFORE SC SHOE PLUG	After placing plug at 2000' assure that all fluid migration has been eliminated by monitoring the well for a minimum of 8 hours before proceeding to the next plug. If at any time after placing this plug there is evidence of pressure or of fluid migration, contact COGCC engineering before continuing operations.

8/10/21

Time From	Subcode	Subcode Description	Operation
7:14	F	VERIFY NO MIGRATION BEFORE SC SHOE PLUG	Prior to placing the 875' plug: verify that all fluid migration (liquid or gas) has been eliminated. If evidence of fluid migration or pressure remains, contact COGCC Engineer for an update to plugging orders.

9:59	I	ALL PLUGS PUMPED WERE A MINIMUM OF 100' LONG	Leave at least 100' of cement in the wellbore for each plug.
10:59	L	BIRD STIPULATION	<p>"This oil and gas location is within a CPW-mapped bald eagle roost or communal roost High Priority Habitat. Plugging and abandonment (P&A) activities should not take place from November 15 to March 15. If P&A activities must occur from November 15 to March 15, and there is direct line of sight within 0.5 mile from an active roost to the activity, operator will consult with CPW to develop site specific measures to avoid, minimize, and mitigate impacts to wildlife."</p> <p>RDMO 8/10/2021</p>