

# Sawyer/Powell #32-4 Before P&A



DESCRIPTION DEPTH WELLBORE

10sx Surface Plug

27'

75sx balanced plug

(half in, half out of sfc csg)

175'

8-5/8" Surface Casing:

(cement to surface)

223'

275'

50sx Balanced Plug

(original abandonment)

1225'

1275'

50sx Balanced Plug

(original abandonment)

1400'

1450'

30sx Balanced Plug

(original abandonment)

7800'

7900'

7-7/8" Production Hole TD:

8217'

**WELL:** Sawyer/Powell #32-4

**LOCATION:** NWSW 32 1N 65W  
2038FSL 831FWL (Planned)  
40.006199°N, -104.694386°E

**FORMATION:** JSND 11/3/1990

**API #:** 05-123-14807

**Field:** Wattenberg

**CURRENT STATUS:** PA

**Spud:** 10/25/1990

## Casing and Tubular Data

Type	Size	Weight	Top	Bottom	Hole Size
Surface	8-5/8"	24 ppf	0	223'	12-1/4"
Open Hole			0	8217'	7-7/8"

## Elevation Data

GL	5020	feet
KB	5030	feet
Difference	10	feet

## Formation Tops Data

Formation	Depth	
Base of Fox Hills	1207'	MD
Base of Upper Pierre	1600'	MD
Sussex	4683'	MD
Niobrara	7026'	MD
D Sand	7836'	MD
J Sand	7896'	MD